

Executive Engineer  
South Zone-A(Udhana)



Surat Municipal Corporation  
South Zone-A(Udhana)  
Opp. Satyanagar, Udhana,  
Surat.

☎ 2277043, 2278429.

## QUOTATION INQUIRY

SZ-A/Tech./No.3548

Dtd.: - 04/07/2024

To,

.....  
.....

Sub: - S.E.T.C. work of Pipe Earthing System with 2 years Annual Maintenance Contract (AMC) for various muni. building in South Zone-A(Udhna) area, SMC Surat..

Dear Sir,

South Zone of Surat municipal corporation is inviting quotation for the work of S.E.T.C. of Pipe Earthing System with 2 years Annual Maintenance Contract (AMC) for various muni. building in South Zone-A(Udhna) area, SMC Surat..

You are requested to Send your offer in a sealed cover So as to reach in the office of Executive Engineer [South Zone-A Udhna] on or before Dt. 12/07/2024 up to 6.00 pm. Please note that the sealed cover shall be super scribed with the name of work. Details of work required is as following.

### Quotation

Sr. No.	Item	Qty. (Aprox)	Unit	Rate per Unit without GST in Rs.	Total Amount Without GST in Rs.
1	Providing and erecting Pipe type earthing having 150 cms.long and 2.5 cms. dia. galvanised iron pipe with coupling and buch buried in specially prepared earth pit complete with necessary 8 SWG earth wire.	85	Ea.	364.41	30,974.58
2	Providing and erecting Pipe type earthing with 40 mm dia 2.5 mtr long 'B' grade G.I. pipe with necessary coupling buch buried in specially prepared earth pit & G.I. earth wire of 8 SWG erected & connected as directed.	40	Ea.	813.56	32,542.37
3	Providing and erecting HOT deep Galvanised iron strip/wire 8 to 16 SWG.	128.75	Kg.	76.27	9,819.92
4	For using salt and charcoal / coke as required for pipe type earthing.	2500	Kg.	3.50	8,750.00
5	Add Extra for excavation in Semi hard rock (Murrum) by dry and wet blasting and chiselling for pipe type earthing	8	Ea.	110.17	881.36
6	Add Extra for excavation in Hard rock by dry and wet blasting and chiselling for pipe type earthing.	8	Ea.	275.42	2,203.39

(P.T.O.)

7	Providing and erecting ISI mark Medium class RIGID PVC PIPES of following size complete to be erected on/in wall or ceiling erected with necessary PVC fittings & Junction boxes fixed with adhesive solution & Clamps with following dia of pipes, in approved manner as directed (a)20 mm	1375	Mtr.	22.03	30,296.61
8	" as above " (b) 25 mm	10	Mtr.	30.51	305.08
9	RCC Chamber with Cover for Earthing System size 300mm x 300mm x 300mm	125	Ea.	338.98	42,372.88
10	Maintain the earthing as mentioned in detailed Scope of work	125	Each	81.35	10,168.75
Total Amount without GST					1,68,314.94
18% GST					30,296.69
Total Amount With GST					1,98,611.63
<b>Tender limit up to (with GST)</b>					<b>2,00,000.00</b>

I/We here by tendered to execute the above mentioned description of a work in accordance the accompanying specification and condition in consideration of the quantity of the work to be executed at PAR rate i .e. same cost / at \_\_\_\_\_ % (Percentage) in word \_\_\_\_\_ Percentage Below / Above amount shown in Above Schedule-B

**Scope Of Work during DFL periods (12 month) & Maintenance periods (24 month):-**

- Measure the value of resistance at least once in a year & submit report
- Check the tightness of various necessary connection of earthing rod/GI strip/GI wire
- Regular watering and charging of the earth pit with salt / charcoal whenever & if needed.

**📖 Terms/conditions of quotation 📖**

★	Work Completion Period of entire work :-	(A) 30 Days for Capital Work (Item no.1 to 9) (B) 2 Year for maintenance Work after 12 month of DFL period (Item no.10)
★	All Taxes/Duties, Octroi etc.: -	Included. Rate Excluded GST
★	FOR: -	S.E.T.C. work of Pipe Earthing System for various muni. building in South Zone(Udhna) area, SMC Surat..
★	Validity of quotation: -	120 Days
★	Payment condition: -	Payment shall be made satisfaction completion of work.
★	Penalty Terms:-	0.2% / Day of Delayed unexecuted portion of work will be Deducted / Recovered from Bill

- Bidder must provide all necessary test certificate report for all material
- Make shall be decided by engineer in charge from the offer list given by Bidder
- After SETC Job bidder has to provide certificate for earth resistance value which must be within permissible limit and maintained throughout the AMC periods .
- Quantity mentioned here are approximate only. It may vary as per actual requirement.
- SMC will not pay any transportation charges and also not provide any type of assistance which carrying out above mention work. All accessories needed in installation of above mentioned items are in bidders scope only.
- Bidders are suggested to visit the site location before quoting this quotation and for any further query, bidder can contact Light department of South Zone, SMC.
- Successful Contractor have to do Agreement, Surety & Undertaking on the non judicial stamp paper of Rs.300/- each purchased from Surat city only.
- Successful Contractor shall deposit Security Deposit of 2 % of amount of Work order within 10 days from work order date. If Contractor fails to deposit same, penalty at 0.065% of SD amount per day will be levied.
- The rates should be inclusive of all taxes/ duties and Octroi but wihtout GST Fulfillments of this condition are must or else the quotation shall be liable for outright rejection.
- All the Central/state/local Govt. Rules & Regulations Including safety Terms Must be Followed by Bidder.
- **The name of work i.e.“ Quotation for the work of .....” must be mentioned on the envelope without which quotation is likely to be rejected, which must be noted.**
- Item no. 1 to 9 (Capital work) shall be completed within 30 days & Payment shall be made after satisfactory completion of whole SETC work as per actual measurement.
- Payment for Item no.10 (Maintenance work for 2 years) shall be made after satisfactory completion of Maintenance contract (2 years) .
- No payment will be made for maintenance work during 12 month Defect liability period.

Thanking You,

-Sd-  
Executive Engineer  
South Zone (Udhna),  
Surat Municipal Corporation.

\* SIGNATURE & SEAL OF CONTRACTOR \*