

Executive Engineer
South Zone-A(Udhna)



Surat Municipal Corporation
South Zone-A(Udhna)
Opp. Satyanagar, Udhna, Surat.
☎ 2277043, 2278429.

QUOTATION INQUIRY

SZ-A/Tech./No.4019

Dtd.: - 18/07/2024

To,

.....
.....

Sub: - S.E.T.C. of Empty Feeder Pillar for street light system with buyback of old Empty Feeder Pillar box in South Zone-A(Udhna).

Dear Sir,

South Zone-A(Udhna) of Surat municipal corporation is inviting quotation for the work of S.E.T.C. of Empty Feeder Pillar for street light system with buyback of old Empty Feeder Pillar box in South Zone-A(Udhna).

You are requested to Send your offer in a sealed cover So as to reach in the office of Executive Engineer [South Zone-A(Udhna)] on or before Dt.26/07/2024 up to 6.00 pm. Please note that the sealed cover shall be super scribed with the name of work. Details of work required is as following.

Quotation

| Sr. No. | Item Description | Qty. | Unit | Rate per Unit without GST in Rs. | Total Amount Without GST in Rs. |
|---------|---|------|------|----------------------------------|---------------------------------|
| 1 | S.E.T.C. of 3 phase G.I. empty feeder pillar as per specification mentioned below | 05 | Nos. | | |
| 2 | S.E.T.C. of 1 phase G.I. empty feeder pillar as per specification mentioned below | 00 | Nos. | | |
| 3 | Less: Buyback value of old 3 phase empty feeder pillar | 05 | Nos. | | |
| 4 | Less: Buyback value of old 1 phase empty feeder pillar | 00 | Nos. | | |
| | Total Amount without GST | | | | |

❖ Grill type box:-

For 1 phase:-

- G.I. feeder pillar contain a powder coated siemens grey G.I. grill type box with dimension of H*W*D of 550*780*300 mm This box consist of two part first part for contains space for existing CCMS box, second part contains space for DGVCL/TORRENT meter box GI box. Fixing arrangement must be provided for this two part.
- The box shall be stand mounting self supportive type. Grill size of 2.5mm & 18 gage. Box have single door with standard lock which cannot be opened by all kinds of commonly available tools.

(P.T.O.)

- Grill type box stand having four leg length of 700 mm with M.S. Angle size -35 X 5 mm
- Door angle size-35 X 5 mm
- Supporting strip-25 X 5 mm
- CCMS Supporting strip-40 X 6 mm
- Skirting size-300mm
- Un-detachable canopy with slope shall be provided for weather proof outdoor.

For 3 phase:-

- G.I. feeder pillar contain a powder coated siemens grey G.I. grill type box with dimension of H*W*D of 1250*700*350 mm This box consist of two part first part for contains space for existing CCMS box, second part contains space for DGVCL/TORRENT meter box GI box. Fixing arrangement must be provided for this two part.
 - The box shall be stand mounting self supportive type. Grill size of 2.5mm & 18 gage. Box have door with standard lock which cannot be opened by all kinds of commonly available tools.
 - Grill type box stand having four leg length of 700 mm with M.S. Angle size -35 X 5 mm
 - Door angle size-35 X 5 mm
 - Supporting strip-25 X 5 mm
 - CCMS Supporting strip-65 X 6 mm
 - Skirting size-300mm
 - Un-detachable canopy with slope shall be provided for weather proof outdoor.
- ❖ **Detailed specification for C.C. foundation for feeder pillar:-**
- The CCMS unit shall be installed on suitable fabricated stand made from GI. Reinforced Cement Concrete (RCC) foundation having Grade M20 along with necessary Foundation Bolt, Nuts, Washers with anchor plate and DWC pipe for cable access etc. shall be casted having required size as proposed by manufacturer of CCMS unit with necessary plastering. Foundation should be made in such a way as site requirement. This section should be finished in decorative manner as directed by Engineer-in-charge. The item includes excavation, necessary reinforcement recommended by manufacturing co, Shuttering and M20 grade CC from preferably RMC plant or mixture of 1:1.5:3 M20 grade CC. The Contractor should make necessary arrangement for curing required for the works at his own cost. The site should be cleaned or excess material should be removed after the work is completed. While making foundation, best civil engineering practice(s) must be exercised. Bidder must take approval of foundation drawing before carrying out the work.
- ❖ **Detailed specification for earthing of feeder pillar:-**
- The pipe type earthing having 1.5 m long and 2.5 cm Φ galvanized iron pipe with coupling and buried in specially prepared earth pit complete with necessary 25 X 3 mm size GI earthing strip with coupling and GI plug for earthing of switch gear as directed by engineer in charge. This item includes supply, erection, testing and commissioning. The earthing must be as per IS 3043 (1987) with latest amendment(s), if any.

Terms/conditions of quotation

| | |
|--|---|
| * Work Completion Period of entire work :- | 30 Days. |
| * All Taxes/Duties, Octroi etc.: - | Included. Rate Excluded GST |
| * Warranty period:- | Minium 1 year from the date of commissioning |
| * Validity of quotation: - | 120 Days |
| * Payment condition: - | Payment shall be made within 30 days after satisfactory completion of work and submission of invoice. |
| * Penalty Terms:- | 0.2% / Day of Delayed unexecuted portion of work will be Deducted / Recovered from Bill |

- Bidder must provide all necessary test certificate report for all material.
- Make shall be decided by engineer in charge from the offer list given by Bidder.
- Quantity mentioned here are approximate only. It may vary as per actual requirement.
- SMC will not pay any transportation charges and also not provide any type of assistance which carrying out above mention work. All accessories needed in installation of above mentioned items are in bidders scope only.
- Bidders are suggested to visit the site location before quoting this quotation and for any further query, bidder can contact Light department of South Zone, SMC.
- Successful Contractor have to do Agreement, Surety & Undertaking on the non judicial stamp paper of Rs.300/- each purchased from Surat city only.
- Successful Contractor shall deposit Security Deposit of 2 % of amount of Work order within 10 days from work order date. If Contractor fails to deposit same, penalty at 0.065% of SD amount per day will be levied.
- The rates should be inclusive of all taxes/ duties and Octroi but wihtout GST Fulfillments of this condition are must or else the quotation shall be liable for outright rejection.
- All the Central/state/local Govt. Rules & Regulations Including safety Terms Must be Followed by Bidder.
- **The name of work i.e. “ Quotation for the work of” must be mentioned on the envelope without which quotation is likely to be rejected, which must be noted.**

Thanking You,

sd/-
Executive Engineer
South Zone-A(Udhna),
Surat Municipal Corporation.

* SIGNATURE & SEAL OF CONTRACTOR *