



**SURAT MUNICIPAL CORPORATION  
NORTH ZONE  
QUOTATION/CONSENT FORM**

<b>QUOTATION NO. Add.City Engineer /North Zone/ 05 /2025-26</b>		<b>DATE : 21/04/2025</b>
<b>NAME OF WORK :-</b> Supply And Installation Of Various Types Of Electrical Accessories And Material Along With Electrical Wiring Work In Various Housing Properties In North Zone (Katargam) Area		
<b>validity period : 120 Days</b>		<b>Agency Category : --- Experienced</b>
<b>Estimated Amount : 5,00,000-00</b>		<b>EMD Amount : 5,000-00</b>
<b>Required Documents</b>		
1	GST Registration Certificate	Yes
2	Contractor Registration Copy	Yes
<b>TENDER AVAILABILITY</b>		
<b>ISSUING AUTHORITY</b>	Executive Engineer, North Zone, Surat	
<b>ISSUING OFFICE</b>	Administrative office, North Zone(Katargam), Nr. Gajera School, B/S Ramji krupa Raw House, Katargam, Surat.	
<b>INVITING AUTHORITY</b>	Executive Engineer, North Zone, Surat	
Submission Date		
<b>Last date: 28/04/2025</b>		SUBMITTED To, <b>EXECUTIVE ENGINEER</b> ADMINISTRATIVE BUILDING, NORTH ZONE (KATARGAM), NR. GAJERA SCHOOL, B/S RAMJI KRUPA RAW HOUSE, KATARGAM, SURAT.
Time : 17.30 P.M.		
<u><b>GST CLAUSE FOR CONSTRUCTION/ ERECTION/ COMMISSIONING/ INSTALLATION/ REPAIRS/ MAINTENANCE/ RENOVATION/ FABRICATION OF STRUCTURE INCLUDING BUILDING (MEANS ALL WORKS CONTRACT/ TURN KEY PROJECT/ SUPPLY OF MATERIAL/ GOODS)</b></u>		
<p>GST (Goods and service tax has come in existence from 1st July, 2017. Contractor / Successful Bidder is bound to pay any amount of GST prescribed by the govt. of India as per the terms of contract agreed upon during the course of execution of this contract.</p> <p>During the course of execution of contract, if there is any change in rate of GST (Goods and Service Tax) by the Government, the same shall be reimbursed/recovered separately by SMC.subject to the submission of original receipt/proof for the amounts actually remitted by the contractor/ successful Tenderer to the competent Authority along with a certificate from Chartered Accountant of contractor/ successful Tenderer certifying that the amount of GST paid to the government and the same shall be intimated/submitted/claimed within 30 (Thirty) days from the date of payment. Remittance of GST within stipulated period shall be the sole responsibility of the successful contractor/Tenderer, failing which SMC may recover the amount due, from any other payable dues with SMC and decision of Municipal Commissioner shall be final and binding on the contractor/ successful Tenderer in this regard. Further, the non-payment of GST to the government may lead to the termination of contract and forfeiture of security Deposit/Performance Guarantee Amount.</p> <p>If imposition of any other new taxes/Duties/levies/Cess or any other incidentals etc. or any increase in the existing taxes/Duties/Levies/Cess or any other incidentals etc. (Excluding GST) are imposed during the course of the contract, the same shall be borne by the successful contractor/Tenderer only, in no case SMC shall be liable for the same.</p>		
<b>SIGNATURE OF ISSUING AUTHORITY</b>		
S/D EXECUTIVE ENGINEER NORTH ZONE SURAT MUNICIPAL CORPORATION		

**COMPARATIVE STATEMENT  
SURAT MUNICIPAL CORPORATION**

**NORTH ZONE (KATARGAM)**

**LIGHT DEPARTMENT**

**NAME OF WORK:-**

Supply And Installation Of Various Types Of Electrical Accessories And Material Along With Electrical Wiring Work In Various Housing Properties In North Zone (Katargam) Area

Sr No	S.O.R. NO	Description	Qty	Unit	S.O.R 2023-24 (With GST)			
					Rate Rs.	1% cc	Rate Rs.	Amount Rs.
1	1.2.1	Point wiring for Light / Bell with 2-1.5 sq.mm & earth wire of 1.5 sq.mm (Green) both are of ISI marked 1.1 KV grade FRLS PVC insulated multi strand copper wires up to 10 mtr length , in below type of pipe erected with 6A Modular type switch / bell push & accessories and earth continuity of following type, erected on PVC / Metallic/Wooden box, single mounting base frame covered with textured/metallic/white front plate modules erected on / in wall / ceiling as per pipe erected, with necessary Lamp holder/ceiling rose / H.D. Connector as directed.						
		(a) with medium class Rigid PVC pipe and accessories erected flushed on wall/ceiling complete	30	Pt.	489.0	4.89	493.89	14816.70
		(c) with oval conduit /PVC casing capping double lock type erected flushed on wall/ceiling complete	50	Pt.	433.0	4.33	437.33	21866.50
3	1.2.2	Point wiring for FAN with 2-1.5 sq.mm & earth wire of 1.5 sq.mm (Green) both are of .ISI marked 1.1 KV Grade FRLS PVC insulated multi strand copper wires up to 10 mtr length, in below type of pipe erected with 6A Modular type switch and hum free EME step type electronic fan regulator mounted and accessories with earth continuity of following type erected on PVC / Metallic/Wooden box, single mounting base frame covered with textured/metallic/white front plate modules erected on / in wall / ceiling as per pipe erected. with necessary ceiling rose / H.D. Connector as directed.						
		(a) with medium class Rigid PVC pipe and accessories erected flushed on wall/ceiling complete	5	Pt.	699.0	6.99	705.99	3529.95
		(c) with oval conduit /PVC casing capping double lock type erected flushed on wall/ceiling complete	10	Pt.	653.0	6.53	659.53	6595.30
4	1.2.3	Point wiring for Individual Plug with & earth wire of 1.5 sq.mm (Green) both are of ISI marked 1.1 KV grade FRLS PVC insulated multi strand copper wires up to 10 mtr length, in below type of pipe erected complete with Modular type switch & 5 pin Plug erected on PVC / Metallic/Wooden box covered with appropriate front plate modules erected on / in wall / ceiling as per pipe erected with following type of accessories.						
		[I] For 6A Plug and 6 a switch with 2-1.5 sq.mm Cu. Wire from nearby switchboard/mcb db board						
		(a) with medium class Rigid PVC pipe and accessories erected flushed on wall/ceiling complete	0	Pt.	519.0	5.19	524.19	0.00
		(c) with oval conduit /PVC casing capping double lock type erected flushed on wall/ceiling complete	10	Pt.	472.0	4.72	476.72	4767.20
		[II] For 16A Plug and 16 amp switch with 2-2.5 sq.mm Cu. Wire from mcb db board.						
	(a) with medium class Rigid PVC pipe and accessories erected flushed on wall/ceiling complete	0	Pt.	781.0	7.81	788.81	0.00	

		(c) with oval conduit /PVC casing capping double lock type erected flushed on wall/ceiling complete	10	Pt.	676.0	6.76	682.76	6827.60
5	1.2.6	Providing following type of Modular Type Accessories mounted with PVC / metallic/Wooden box, single mounting base frame covered with textured / metallic/white front plate , modules erected with necessary connections as per site situation directed by Engineer In charge.						
		Do as above (1) One No. SP 6 Amp Modular Switch Cat. III	100	Each	167.0	1.67	168.67	16867.00
		Do as above (2) One No 5 pin plug Cat. III	100	Each	167.0	1.67	168.67	16867.00
		Do as above (5) Electronic hum Free four or more steps EME Fan regulator Cat. III	50	Each	444.0	4.44	448.44	22422.00
		Do as above (9) 16 Amp. SP one way switch Cat. III	25	Each	200.0	2.00	202.00	5050.00
		Do as above (10) 6/16Amp. Universal socket Cat. III	25	Each	222.0	2.22	224.22	5605.50
6	1.2.7	Providing & erecting following type of Modular Type Accessories with necessary connection. As desired by Engineer In charge						
		(1) 6 Amp. SP one way switch	500	Each	29.00	0.29	29.29	14645.00
		(2) 16 Amp. SP one way switch	100	Each	56.00	0.56	56.56	5656.00
		(3) 6/16Amp. Universal socket	100	Each	90.00	0.90	90.90	9090.00
		(4) 6 A socket	200	Each	45.00	0.45	45.45	9090.00
7	1.6.8	Providing & erecting ISI marked 3 pin plug top.						
		(a) for 5/6 A., 240 V	25	Each	23.0	0.23	23.23	580.75
		(b) for 15/16A, 240 V	25	Each	35.0	0.35	35.35	883.75
8	1.4.8	Supplying & erecting approved make LAN cable of following size in existing pipe as per direction						
		[C] CAT - 6	300	Mtr.	51.0	0.51	51.51	15453.00
9	1-6-1.	Providing & Erecting following Shockproof tissino type accessories erected on 3 mm thick PC (Polycarbonate) sheet in PVC/ Metal/Wooden Box. erected on wall/ ceiling.						
		(1) One no Single pole 6 A Switch / Bell push	200	Each	34.0	0.34	34.34	6868.00
		(2) One no 3/5 pin 6 A Socket	100	Each	34.0	0.34	34.34	3434.00
		(5) One no Single pole 16 A Switch & One no 6/16 A Universal Socket combined	20	Each	105.0	1.05	106.05	2121.00
		(8) Bakelite lamp holder	50	Each	23.0	0.23	23.23	1161.50
		(14) Electronic Hum free EME Socket Type Steps Fan Regulator	50	Each	244.0	2.44	246.44	12322.00
10	1.6.2(A)	Providing & erecting Switch board for Computer or electric apparatus consisting of following items in single board erected on PVC / Metal/Wooden board concealed/open with 3 mm thick PC (Polycarbonate) / Acrylic sheet erected as directed						
		1 no. 6A/16A universal plug-switch combined. 3 nos. 6A Switch 3 nos. 6A 5 pin Plug						
		For Tissino Type Accessories	10	Each	370.0	3.70	373.70	3737.00
		For Modular Type Accessories	10	Each	1,262.0	12.62	1274.62	12746.20
11	1-6-3.	Bakelite adopter for Holder to be erected.	30	Each	10.0	0.10	10.10	303.00

12	2-15-1	Supplying and erecting LED indoor fittings with LEDs of wattage 0.2 Watt to 0.5 Watt assembled on single MCPCB, with housing used as a heat sink shall be made of thick sheet Steel conforming to IS: 513/CRCA/ aluminium die cast powder coated and high U.V. & corrosion resistance with diffuser with company mark/name 160V to 270V, Power Factor more than 0.95, THD < 15%, CCT 3000 K to 6500K, Luminaire efficacy > 85 lumens/watt ,LED LED driver efficiency > 85 % ( fitting required LM-79 & LM-80 Certificates)(NOTE: Below description have shown ranges of Wattage capacity of LED fittings. The Engineer in charge may select any wattage capacity between the ranges shown.)						
		(A) Tube Light with integral driver						
		(iii) 18-20 Watts, Surge - 2KV,IP-20, conventional 4 feet	300	Each	345.0	3.45	348.45	104535.00
13	2-15-2	Supplying and erecting led lamps with following wattage capacity of 220 to 240 voltage, minimum 15000 burning hours life, 500 V in built-surge protection, Polycarbonate diffuser, mounting suitable for E14 / E27 / B22 lamp holders, pf >= 0.5						
		(A) LED Lamps integral type, with PC diffuser suitable LAMP holder						
		(iii) 10 to 15 watts	25	Each	220.0	2.20	222.20	5555.00
14	3-10-1.(B)	providing and erecting Miniature circuit breaker single pole 6A to 25A suitable to operate on 240 V A.C. system and having breaking capacity 10 KA to be erected in existing box. confirming to IS 8828/1996 with ISI Mark	30	Each	130.0	1.3	131.3	3939.00
15	3.10.2	Providing & erecting 240 V MCB double pole switch for motor & inductive load (C Curve) having 10 KA breaking capacity & confirms to IS : 8828 in existing box having following capacity						
		(A) 6 to 32 Amp.	40	Each	350.0	3.50	353.50	14140.00
		(B) 40 Amp.	5	Each	385.0	3.85	388.85	1944.25
16	3.10.5	Providing & erecting 415 V MCB Four Pole for Motor & Inductive Load (C Curve) having 10KA breaking capacity & confirms to IS :8828 in existing box having following capacity						
		(a) 6 to 32 Amp.	15	Each	695.0	6.95	701.95	10529.25
		(b)40 Amp.	15	Each	780.0	7.80	787.80	11817.00
		(c)63 Amp.	0	Each	860.0	8.60	868.60	0.00
17	3.11.2	Plastic enclosure fitted with DIN rail suitable for incorporating One / Two nos. MCB	10	Each	60.0	0.60	60.60	606.00
18	3.11.3	Plastic enclosure fitted with DIN rail suitable for incorporating Three /Four nos. MCB	10	Each	125.0	1.25	126.25	1262.50
19	3-11-4.	Sheets steel powder coated enclosure suitable for incorporating One/Two nos. MCB.	10	Each	205.0	2.05	207.05	2070.50
20	3.12.1	providing and erecting Approved make RCCBs conforming to IS: 12640 and having sensitivity of 30 mA and Short Circuit withstand capacity of 10 KA and suitable for operation on single phase 240 V,50Hz. having characteristic of quick action & tripping with all advance feature & do not incorporate any electronic component. for following Max. rating erected as directed						
		(i) 25 Amps.DP	2	Each	2300.00	23.00	2323.00	4646.00

		(ii) 40Amps. DP	2	Each	2610.00	26.10	2636.10	5272.20
		(iii) 63 Amps. DP	0	Each	3100.00	31.00	3131.00	0.00
21	3.12.2	Providing and erecting Approved make RCCBs conforming to IS: 12640 and having sensitivity of 30 mA and Short Circuit withstand capacity of 10 KA and suitable for operation on 3 phase and neutral 415V,50Hz. having characteristic of quick action & tripping with all advance feature & do not incorporate any electronic component for following Max. rating erected as directed.						
		(i) 25 Amps. FP	5	Each	3000.00	30.00	3030.00	15150.00
		(ii) 40Amps. FP	5	Each	3080.00	30.80	3110.80	15554.00
		(iii) 63 Amps. FP	0	Each	3550.00	35.50	3585.50	0.00
		(iv) 100 Amps. FP (100 mA Sensitivity)	0	Each	5040.00	50.40	5090.40	0.00
22	3-14-6-A	Providing and erecting Pipe type earthing having 150 cms. long and 2.5 cms. dia. galvanized iron pipe with coupling and buch buried in specially prepared earth pit complete with necessary 8 SWG earth wire.	10	Ea.	430.0	4.30	434.30	4343.00
23	4-2-1.	Supplying & erecting XLPE(IS:7098)(I)-88 ISI unarmored copper cable 1.1 KV grade to be erected as directed of following size.						
		(E) 3 core 2.5 Sq. mm	100	Mtr	158.0	1.58	159.58	15958.00
24	1-4-5	Supplying and erecting Flexible PVC insulated multi strand multi core 1.1 kv grade ISI marked copper wires of following size to be erected as directed.						
		(e) 1.50 Sq.mm 3 core round PVC sheathed	200	Mtr	51.0	0.51	51.51	10302.00
		(c) 1.00 Sq.mm 2 core round/ flat PVC sheathed	50	Mtr	24.0	0.24	24.24	1212.00
25	5.1.6.	Providing & erecting Approved make Power Saving 50 Watt Ceiling Fan with double ball bearing ISI mark with Condenser 230 volt A.C. 50 Hz 1200 mm sweep complete having 3blades with aluminum blades with , canopy & 30 cm. down rod erected with earthing.(Make shall be approved by Engineer in charge))	10	Each	2,275.0	22.75	2297.75	22977.50
26	5-6-8.	Replacing condenser for ceiling fan/ Exhaust Fan / Pedestal Fan / Table Fan / Cabin Fan {Credit of D.M. retained by Agency.}	200	Each	75.0	0.75	75.75	15150.00
27	5.2.1	Supplying and erecting 19 / 20 mm. nominal bore Medium Class M.S. Pipe down rod erected duly painted for fan complete with proper insulation without leakage and earthing.	20	Mtr	125.0	1.25	126.25	2525.00
28	5.2.2	Supplying & erecting Fan Hook of 10 mm M.S. Round bar grouted in RCC slab with Making the site as original.	25	Each	50.0	0.50	50.50	1262.50
29	5.2.4	Providing Fan clamp of 30 x 5 mm flat of required length & 10 mm M.S. Bolt & Nuts erected with necessary hook of 10 mm M.S. Round Bar.	25	Mtr.	115.0	1.15	116.15	2903.75
30	1-6-13.	Supplying & erecting Electronic Type Cordless Call Bell erected on PVC/Metal board having portable bell push working on D.C. & bell on 230V A.C. supply with cells / battery	10	Each	278.0	2.78	280.78	2807.80
<b>Net Estimate Rs.(With GST) :-</b>								<b>499768.20</b>

I / We ..... [Name of the authority] owner / proprietor / partner / director of ..... [Name of firm] having registered office At..... [Address of the firm] hereby declares that I/we have read all the documents carefully and thoroughly. Our agency is agreed to carry out the stated work as per the terms, conditions and scope of work depicted in quotation documents at a rate .....% (Above / Below/ At par) compared to the rates mentioned in the table above.

- Contractor shall supply the material as per the terms and condition and requirement of Surat Municipal Corporation. All the material supplied as per relevant BIS.Vender list of material shall be as follow.

**VENDOR'S LIST**

Sr. No.	Equipments/ Accessories	Make
1	Wires	Torrent, Finolex, Havells, KEI, R R Kabel,Polycab
2	Un armoured Cable	Finolex,Torrent,Havells,KEI,R R Kabel,Bharat Cab, CCI,Universal,Incab,Gloster,Tropodure, Avocab, Unistar
3	Switch and Accessories	Anchor Roma/Penta , Jainex, Indoasian, Legrand, L&T,Straco Schneider Electric,Vinay, Alex, Gm,Pointeer ,Gret White,Plus,
4	ELCB/MCB/RCCB Distribution Board	Standard, Indo kopp, MDS, Havell's, Hager, Schneider, Siemens, ABB, L & T, C & S, Legrand
5	Tube Lights, lamps,	Philips, Havells, Bajaj, Surya,
6	Led Lamps, LED Tube	Philips, Havells, Bajaj, Osram
7	Ceiling Fan, Pedestal / wall fan, Exhaust Fan ( High Speed Fan)	Crompton, Havells, Usha, Almonard.Khetan,Bajaj.
9	PVC Pipe/casing capping accessories	Precisson, Poly Cab, Finolex, Nihir
10	CAT-6 Cable	Finolex ,Havells,D-Link,Polycaab

**NOTE :** Prior Approval For Any Other item Apart Than Listed Above Shall be taken By the Contractor and Decision of Engineer In Charge shall be final and Binding to all.

**Terms/conditions of quotation**

*	Delivery period: -	24 hours as intimated by SMC.
*	All Taxes/ Duties, Octroi etc.: -	Included
*	FOR: -	North Zone (Katargam) S.M.C.
*	Validity of quotation: -	<b>120 Days</b>
*	Payment condition: -	Payment shall be made within 20 days after safe receipt & inspection/ testing of material.

**Terms and Conditions**

- The rate should be **including of GST** and including of all other taxes, duties, labor charges and transportation,loading unloading, watch and ward etc. at Site.
- Quotation once offered shall not be withdrawn by Vendor.
- Quotation once accepted shall be binding to the Vendor/Contractor.
- Right to Accept any or to Reject or all the offers without assigning any reason thereof is reserved by the competent authority of Surat Municipal Corporation.
- All necessary measure and precaution (including those laid down in the various relevant Indian Standards Shall be taken to ensure the Safety of men, material and machinery on the works as also of the work itself.
- The firm will have to Supply and Installation above Electrical Material within 24 hours from order of Light dept. of SMC. if not, the SMC will get it from other contractor and the expenditure so incurred on such supplied items including administrative charges will be deducted from the ARC payment, due for payment to contractor.

- Overall lowest bidder shall be taken for consideration.
- Conditional offer shall not be accepted.
- Defect liability period for the above entire work shall be of one (1) year.
- The Contactor Shall be Constituted according to and subject to laws in India and state of Gujarat and under the Jurisdiction of courts of Gujarat at Surat city only.
- An EMD of Rs.5000/- in Form of DD or pay order issued in favour of "Commissioner, Surat Municipal Corporation" and payable at Surat must accompany this quotation.
- The services should be provided on regular basis during office hours. In case of emergency contractor must supply & install above Electrical Items beyond office hours & on holiday as well. Failing which penalty @ 0.2% of order value of unexecuted portion per day of delay subject to maximum 10% of unexecuted portion order value shall be charged and shall be deducted from the bill.
- The successful contractor shall also be required to enter into contract agreement along with undertaking and local surety on Gujarat Stamp Paper purchased from Surat worth Rs.900.00 (i.e. 300.00 + 300.00 + 300.00 for each) (to be brought from Surat by the contractor) on getting the order. However, the stamp duty at prevailing rate shall be applicable if revised by Government.
- The successful Contractor shall be required to deposit an amount equal to 2% of the total order value as Security Deposit in Municipal Treasury in Cash/ by Demand Draft within 10 (Ten) days of order failing which penalty @ 0.065% of the Security Amount per day of delay shall be charged.
- The firm must have an office in Surat.
- The period of Annual Rate Contract For Supply Of Electrical Materials Will be Two (2) Year From The date of the award of the contract or work order Amount Limit Whichever is Earlier.
- SMC will not pay any transportation charges and also not provide any type of assistance which carrying out above mention work. Contractor must replace faulty spare with genuine spare only Faulty Replaced Spare Need Not Submit to SMC
- The rates quoted shall remain in force for full period of contract.
- After bidding process, No objection entertained later.
- All the pages of this Quotation shall be signed and stamped by the bidding agency.
- The bidder should have a valid Electrical Contractor licence Form concern department of Gov.of Gujarat.
- All Mentioned Electrical items supplied & Installed as per Vendor list only.
- The rates should be inclusive of all taxes/ duties, GST and Octroi. Fulfillments of this condition are must or else the quotation shall be liable for outright rejection.
- Rates must be filled in this quotation paper only and returned duly sealed & signed.
- The name of work i.e. " Quotation for the work of ....." must be mentioned on the envelope without which quotation is likely to be rejected, which must be noted.

Thanking You,

S/D

**EXECUTIVE ENGINEER  
NORTH ZONE(KATARGAM)  
SURAT MUNICIPAL CORPORATION**

\* SIGNATURE & SEAL OF CONTRACTOR \*