

Surat Municipal Institute of Medical Education and Research

Opp. Bombay Market, Umarwada, Surat – 395 010 (Guj.)-India.

Medical Superintendent-Extn.1600
SMIMER Hospital
Phone Nos. 2368040 to 43

FAX No.(0261) 2360306
GST No.24AAALS0678Q1ZE



SMIMER/Hosp/Out/ No.827

Date: 15/05/2025

To,
M/s _____

Quotation

Sub : Quotation for Dismantling of Copper Piping and Manifold System at SMIMER Hospital, Surat.

Dear Sir,

Quotations are invited for dismantling of copper piping and manifold System at SMIMER Hospital, Surat as per following terms & conditions.

1. The rates should be F.O.R. destination inclusive of all taxes & charges i.e. freight, GST, packing and insurance etc.
2. Rate should be quoted as per serial number of list.
3. Items which are not found to our specifications will not be accepted.
4. During dismantling, if any items are damaged the same shall be repaired or replaced by the bidder at their own cost.
5. Overwriting, erasures or correction in quotations shall not be considered.
6. **Quotations are to be sent in sealed cover as above.**
7. Quotations received after due date will not be considered.
8. Dismantling work should be completed **within 1 week from the** date of receipt of work order or time limit allowed which will be mentioned in Purchase order/work order failing which penalty will be imposed @ 0.2% per day of order amount maximum up to 10%.
9. The successful awardee will be required to place Security Deposit (SD`) @ 5% (Five percent) of the consideration of the contract amount by demand draft or Banker's Cheque of any scheduled / nationalized bank payable at Surat drawn in favour of "Commissioner, Surat Municipal Corporation". Security deposit must be submitted within 15 days or time limit allowed in work order/Purchase order from the date of notice of award of contract, failing which a delay penalty @ 0.065% of the amount of security deposit will be imposed for each day.
10. On awarding the contract, the awardee agency will have to enter into a written agreement using Stamp Paper value of Rs.300/-.
11. The Security Deposit will be returned after the completion of dismantling works are completed as per the satisfactory certification of Medical Gas pipeline Committee, SMIMER and after the fulfillment of obligation created under the contract awarded.
12. **Quotations sent by post or courier or services or in person is preferable.**
13. Guarantee/warranty should be mentioned in quotation.
14. Shop & Establishment registration certification should be submitted preferably.

15. GST CLAUSE FOR CONSTRUCTION/ ERECTION/ COMMISSIONING/INSTALLATION/ REPAIRS/ MAINTENANCE/RENOVATION/ FABRICATION OF STRUCTURE INCLUDING BUILDING(MEANS ALL WORKS CONTRACT/TURN KEY PROJECTS/SUPPLY OF MATERIAL/GOODS)

GST (Goods & Service Tax) has come in existence from 1st July, 2017. Contractor/Successful Bidder is bound to pay any amount of GST prescribed by the Govt. of India as per the Terms of contract agreed upon during the course of execution of this Contract.

During the course of execution of contract, if there is any change in Rate of GST(Goods & Service Tax) by the Government, the same shall be reimbursed / recovered separately by SMC, subject to **the submission of original Receipt/Proof for the amounts actually remitted by** the successful Tenderer /Contractor to the Competent Authority along with a Certificate from Chartered Accountant of Contractor / Successful Bidder certifying that the amount of GST paid to the Government and the same shall be intimated / submitted/claimed within 30 (Thirty) Days from the date of payment. Remittance of GST within stipulated period shall be the sole responsibility of the Successful Bidder/Contractor, failing which, SMC may recover the amount due, from any other payable dues with SMC and decision of Municipal Commissioner shall be final and binding on the Contractor / Successful Bidder in this regard. Further, the non-payment of GST to the Government may lead to the termination of the contract and forfeiture of Security Deposit / Performance Guarantee Amount.

If imposition of any other new Taxes /Duties /Levies / Cess or any other incidentals etc. or any increase in the existing Taxes / Duties / Levies / Cess or any other incidentals etc.(Excluding GST) are imposed during the course of the contract, the same shall be borne by the Contractor / Successful Bidder only, in no case SMC shall be liable for the same.

The contractor will submit the invoice to the SMC having GSTIN of SMC mentioned therein and the taxes shall be shown separately on the face of the invoice so as to claim as ITC by SMC.

Envelope should bear on top: "Quotation for Dismantling of Copper Piping and Manifold System at SMIMER Hospital ".

Quotations are to be sent in sealed cover addressed to office of Medical Superintendent shree, SMIMER Hospital by post/courier/in person so as to reach on or before **Dt.20.05.2025 up to 5:00 P.M.** Quotation received thereafter will not be accepted.

Medical Superintendent
SMIMER Hospital

Specification for Dismantling of Copper Piping and Manifold System

Location: LMO Battery Area & Oxygen Storage cum Manifold Room, SMIMER Hospital near Multilevel parking.

1. Objective:

This specification outlines the scope of work, safety guidelines, and qualifications required for the safe dismantling of medical-grade copper piping and 20x20 oxygen manifold system (including emergency manifold) in the LMO battery area and adjacent oxygen storage cum manifold room at SMIMER Hospital. The work must be executed with no damage to the control panels, manifolds, to enable reinstallation and reuse.

2. Scope of Work:

2.1 Dismantling Activities:

- Dismantling of all **medical-grade copper pipelines** installed in:
 - The LMO battery bank area
 - The nearby oxygen storage room
- Complete **removal of the 20x20 manifold system**, including:
 - Main manifold block
 - Emergency manifold
 - Pigtails, isolation valves, NRVs, and pressure gauges
- Safe disconnection of the copper piping from:
 - Manifold control panel(s)

2.2 Handling and Preservation:

- All, manifold blocks, and control panel must be:
 - Carefully dismantled to prevent damage
 - Securely handed over for storage or relocation.
- Ensure no damage occurs during pipe removal to the property near to it.

3. Safety & Precautions:

- Verify the system is **fully depressurized and isolated** before starting work
- Use only **certified tools** suitable for copper piping and gas fittings
- Ensure use of appropriate PPE and adherence to safety protocols for working with pressurized gas infrastructure
- Protect nearby electrical/control panels and wall-mounted devices during dismantling
- Conduct a pre-job safety briefing and implement hazard control measures

4. Equipment to be Preserved for Reuse:

- 20x20 Oxygen Manifold Block
- Emergency Manifold Block
- Pressure Gauges and Isolation Valves
- Stainless Steel or Brass Pigtails
- Manifold Control Panel(s)
- All reusable copper piping and fittings

5. Bidder Qualification Criteria:

- The bidder must have proven experience in the dismantling and handling of hospital medical gas pipeline systems (MGPS)
- The team must consist of trained and skilled technicians capable of handling:
 - Medical-grade copper piping
 - Oxygen manifold systems
 - Critical control panels and valves
- Bidders must submit:
 - Relevant project completion certificates or work orders
 - Details of manpower and tools proposed for the job
 - Safety compliance record and protocols followed in similar jobs.
 -

6. Compliance and Standards:

- All work must be compliant with:
 - **HTM 02-01 / NABH guidelines** for MGPS systems
 - Safety standards for oxygen system handling

7. Site Restoration:

- All dismantled components must be handed over to authorized hospital staff with an inventory list.
- Temporary sealing or capping of open pipe ends if required.

PRICE BID

Sr. No.	Job Description	Amount in Rs	GST %	GST in Rs.	Total amount in Rs.
1.	Dismantling and shifting of copper pipelines in the LMO battery area and adjacent Oxygen storage cum manifold room, along with proper dismantling of 20X20 manifolds with emergency manifold and Control panel as described in the scope of work.				

Medical Superintendent
SMIMER Hospital
Surat Municipal Corporation