

Surat Municipal Institute of Medical Education and Research

Opp. Bombay Market, Umarwada, Surat – 395 010 (Guj.)-India.

Medical Superintendent-Extn.1600
SMIMER Hospital
Phone Nos. 2368040 to 43

FAX No.(0261) 2360306
GST No.24AAALS0678Q1ZE



SMIMER/Hosp/Out/ No.828

Date: 15/05/2025

To,
M/s _____

Quotation

Sub : Quotation for dismantling and shifting of LMO Tank, Vaporizers, and PRS Skids
Near Multilevel Parking, SMIMER Hospital, Surat.

Dear Sir,

Quotations are invited for dismantling and shifting of LMO Tank, Vaporizers, and PRS Skids at SMIMER Hospital, Surat as per following terms & conditions.

1. The rates should be F.O.R. destination inclusive of all taxes & charges i.e. freight, GST, packing and insurance etc.
2. Rate should be quoted as per serial number of list.
3. Items which are not found to our specifications will not be accepted.
4. During dismantling, if any items are damaged the same shall be repaired or replaced by the bidder at their own cost.
5. Overwriting, erasures or correction in quotations shall not be considered.
6. **Quotations are to be sent in sealed cover as above.**
7. Quotations received after due date will not be considered.
8. Dismantling work should be completed **within 1 week from the** date of receipt of work order or time limit allowed which will be mentioned in Purchase order/work order failing which penalty will be imposed @ 0.2% per day of order amount maximum up to 10%.
9. The successful awardee will be required to place Security Deposit (SD`) @ 5% (Five percent) of the consideration of the contract amount by demand draft or Banker's Cheque of any scheduled / nationalized bank payable at Surat drawn in favour of "Commissioner, Surat Municipal Corporation". Security deposit must be submitted within 15 days or time limit allowed in work order/Purchase order from the date of notice of award of contract, failing which a delay penalty @ 0.065% of the amount of security deposit will be imposed for each day.
10. On awarding the contract, the awardee agency will have to enter into a written agreement using Stamp Paper value of Rs.300/-.
11. The Security Deposit will be returned after the completion of dismantling works are completed as per the satisfactory certification of Medical Gas pipeline Committee, SMIMER and after the fulfillment of obligation created under the contract awarded.
12. **Quotations sent by post or courier or services or in person is preferable.**
13. Guarantee/warranty should be mentioned in quotation.
14. Shop & Establishment registration certification should be submitted preferably.

15. GST CLAUSE FOR CONSTRUCTION/ ERECTION/ COMMISSIONING/INSTALLATION/ REPAIRS/ MAINTENANCE/RENOVATION/ FABRICATION OF STRUCTURE INCLUDING BUILDING(MEANS ALL WORKS CONTRACT/TURN KEY PROJECTS/SUPPLY OF MATERIAL/GOODS)

GST (Goods & Service Tax) has come in existence from 1st July, 2017. Contractor/Successful Bidder is bound to pay any amount of GST prescribed by the Govt. of India as per the Terms of contract agreed upon during the course of execution of this Contract.

During the course of execution of contract, if there is any change in Rate of GST(Goods & Service Tax) by the Government, the same shall be reimbursed / recovered separately by SMC, subject to **the submission of original Receipt/Proof for the amounts actually remitted by** the successful Tenderer /Contractor to the Competent Authority along with a Certificate from Chartered Accountant of Contractor / Successful Bidder certifying that the amount of GST paid to the Government and the same shall be intimated / submitted/claimed within 30 (Thirty) Days from the date of payment. Remittance of GST within stipulated period shall be the sole responsibility of the Successful Bidder/Contractor, failing which, SMC may recover the amount due, from any other payable dues with SMC and decision of Municipal Commissioner shall be final and binding on the Contractor / Successful Bidder in this regard. Further, the non-payment of GST to the Government may lead to the termination of the contract and forfeiture of Security Deposit / Performance Guarantee Amount.

If imposition of any other new Taxes /Duties /Levies / Cess or any other incidentals etc. or any increase in the existing Taxes / Duties / Levies / Cess or any other incidentals etc.(Excluding GST) are imposed during the course of the contract, the same shall be borne by the Contractor / Successful Bidder only, in no case SMC shall be liable for the same.

The contractor will submit the invoice to the SMC having GSTIN of SMC mentioned therein and the taxes shall be shown separately on the face of the invoice so as to claim as ITC by SMC.

Envelope should bear on top: "Quotation for dismantling and shifting of LMO Tank, Vaporizers, and PRS Skids Near Multilevel Parking, SMIMER Hospital, Surat ".

Quotations are to be sent in sealed cover addressed to office of Medical Superintendent shree, SMIMER Hospital by post/courier/in person so as to reach on or before **Dt. 20.05.2025 up to 5:00 P.M.** Quotation received thereafter will not be accepted.

Medical Superintendent
SMIMER Hospital

Specification for Dismantling and Shifting of LMO Tank, Vaporizers, and PRS Skids

Location: Near Multilevel Parking, SMIMER Hospital

1. Objective:

This document outlines the scope of work, safety requirements, and responsibilities for the safe **dismantling and shifting** of the following equipment located near the multilevel parking of SMIMER Hospital without causing any damage to the equipment or associated piping:

2. Equipment Details:

2.1 Liquid Medical Oxygen (LMO) Tank:

- **Make:** INOX CVA
- **Capacity:** 20 KL
- **Model:** IC5.0k-ECT
- **Job No.:** 1012021216/1
- **Current Tank Pressure:** 10 kg/cm²
- **Water Capacity:** 0 MM WC

2.2 Vaporizers (Qty: 2):

- **Model:** AAV 1000
- **Job No.:**
 - 1022025168/1
 - 1022025168/2

2.3 Pressure Regulating Skids (PRS) (Qty: 2):

- **Tag No.:** Skid-67
- **Job No.:**
 - 1012024014/67
 - 1012024014/68

3. Scope of Work:

3.1 Dismantling Activities:

- Dismantle the 20 KL LMO tank with extreme caution to prevent the tank and its connected valves and accessories.
- Dismantle both AAV 1000 vaporizers (Qty: 2).
- Dismantle both PRS skids (Qty: 2)
- Carefully dismantle all **stainless steel (SS) connecting pipelines**:
 - From LMO tank to Vaporizers
 - From Vaporizers to PRS Skids
- Ensure all joints, flanges, and valves are disassembled carefully for reuse.
- Ensure no damage or deformation occurs to piping and equipment during dismantling or handling.
- Manpower, tools and gases (if any) required for the work will be under the bidders scope of work.

3.2 Safety Measures:

- Confirm tank is depressurized and purged prior to any work.
- Use certified tools and follow standard operating procedures.
- Proper PPE and fire safety measures must be in place.
- Conduct tool-box talk and risk assessment prior to job execution.

4. Responsibility of PI Cell, SMIMER Hospital:

- Provide a **suitable crane** with certified lifting capacity for dismantling and lifting operations.
- Arrange **transport truck(s)** for safe shifting of dismantled equipment.
- Undertake **removal of fencing** surrounding the LMO tank installation.
- Ensure route clearance for transport within or outside hospital premises.
- Coordinate logistics and obtain necessary safety and operation permits.

5. Bidder Qualification Criteria:

- The **bidder must have prior experience** in dismantling and shifting of cryogenic LMO tanks and related medical gas infrastructure.
- The **execution team must include skilled and trained personnel** with demonstrated knowledge of:
 - Handling of pressurized cryogenic systems
 - Dismantling stainless steel pipelines and PRS equipment
 - Safe transportation of high-value medical gas equipment
- Bidders must submit:
 - Relevant work experience certificates
 - Safety compliance records
 - List of tools and skilled manpower to be deployed for the job.

6. General Requirements:

- All work shall be carried out under the supervision of qualified technical personnel.
- Equipment must be handled per manufacturer’s guidelines.
- All safety and environmental protocols of the hospital and applicable regulations must be strictly followed.

PRICE BID

Sr. No.	Job Description	Amount in Rs	GST %	GST in Rs.	Total amount in Rs.
1.	Dismantling and shifting of 20KL tank qty-1, Vaporizer qty-2 and PRS qty-2 along with disconnecting S.S pipelines connected from LMO tank to Vaporizer and from vaporizer to PRS as described in the scope of work.				

Medical Superintendent
SMIMER Hospital
Surat Municipal Corporation