કાર્યપાલક ઈજનેર સાઉથ વેસ્ટ (અઠવા) ઝોન. આદર્શભવનની બાજુમાં,અઠવાલાઈન્સ, સરત મહાનગરપાલિકા. સરત.



કોન નંબર : ૨૬૬૩૦૪૯–૫૦ 2559655 મ્યનિસિપલ ઝોન ઓફિસ, સુરત.

## સંમતિપત્ર

નં.સા.વે.ઝોન(	(અઠવા)/આ.
તારીખઃ	

ાતિ,		
		• • • • • • • • • • • • • • • • • • • •
• • • • • • • • • • • • • •		
•••••	•••••	

વિષય :–સાઉથ વેસ્ટ (અઠવા) ઝોન વિસ્તારમાં આવેલ હળપતિવાસ વેસુ–૨ આંગણવાડી નં. ૩૩ નું મેઈન્ટેનન્સ અને રીનોવેશન કરવાનં કામ.

સંદર્ભઃ— (૧) સ્થા.સ.ઠ.નં.૧૬૮૬/૨૦૨૪, તા.૨૪/૧૦/૨૦૨૪ થી મંજુર થયેલ ટેન્ડરના ભાવે અને શરતે (૨) મા.ડે.કમિશ્નરશ્રીની તા. જે. લ્લાયક્સપ્રના રોજની મંજુરી.

મહાશય.

સાઉથ વેસ્ટ (અઠવા) ઝોન વિસ્તારમાં આવેલ હળપતિવાસ વેસુ–૨ આંગણવાડી નં. ૩૩ નું મેઈન્ટેનન્સ અને રીનોવેશન કરવાના કામે ઉકત સંદર્ભ (૧)મુજબ સ્થા.સ.ઠ.નં.૧૬૮૬/૨૦૨૪, તા.૨૪/૧૦/૨૦૨૪ થી મંજુર થયેલ ટેન્ડરના ભાવે અને શરતે રૂા.ર,૦૦,૦૦૦.૦૦ પૈ. ની મર્યાદામાં કામગીરી કરાવવા સંદર્ભ (ર) હેઠળથી મંજુરી મળેલ. આ કામ કરવા સંમત હોય તો આપશ્રીની લેખીત સંમતિ બંધ કવરમાં તા..Ωું.∤ઠ.∰.ો≾ઙર઼પ઼ સુઘીમાં નીચે સહી કરનારની કચેરીમાં પહોંચાડવા પ્રબંધ કરશો. ઉપરોક્ત જણાવેલ તારીખ પછી કોઈ બંધ કવરો સ્વીકારવામાં આવશે નહી.

## —ઃ શરત<u>ો ઃ—</u>

- ૧. અર્નેસ્ટમની ડીપોઝીટની રકમ કમિશ્નરશ્રી, સુરત મહાનગરપાલિકાના નામનો સુરતની રાષ્ટ્રીયકૃત શીડયુલ બેંકના ડીમાન્ડ ડ્રાફટ / પે. ઓર્ડરથી સંમતિપત્રક સાથે રૂા.૨,૦૦૦ /– ની આપવાની રહેશે.
- ૨. ઈજારદારે અંદાજીત રકમ ના ૨૦% એટલે કે રૂા.૪૦,૦૦૦.૦૦ પૈ. કે તેથી વધુ રકમની વર્તમાન (ચાલુ) વર્ષની રાષ્ટ્રીયકૃત બેંકની સોલવંશી સર્ટીફીકેટ સંમતિપત્રક સાથે આપવાની રહેશે.
- ૩. ઈજારદારે રજીસ્ટ્રેશન સર્ટીફીકેટ રજૂ કરવાનું રહેશે.
- ૪. ઈજારદારે GST રજીસ્ટ્રેશન સર્ટીફીકેટની નકલ સંમતિપત્રક સાથે આપવાની રહેશે.
- ૫. ઈજારદારે પાન કાર્ડ રજુ કરવાનું રહેશે.
- ૬. ઈજારદારે શીડયુલ–બી માં જણાવેલ ભાવ અને ટેકનીકલ બીડની શરતોને બંધનકર્તા રહેશે.
- ૭. કોઈપણ તથા બધાજ સંમતિપત્રક રદ કરવાનો અધિકાર સુરત મહાનગરપાલિકાને અબાધિત રહેશે તે અંગે કોઈ પણ કારણો આપવામાં આવશે નહી.
- ૮. તમામ પ્રકારના વેરા / સરકારી ટેક્ષ ઈજારદારે ભોગવવાનાં રહેશે.
- ૯. તમામ સરકારી/ અર્ધ સરકારી લાગુ પડતા કાયદાનું ઈજારદારે પાલન કરવાનું રહેશે.
- ૧૦. સદર કામગીરી બાબતે અત્રેના હાઉસીંગ વિભાગના ટેકનીકલ સ્ટાફનો સંપર્ક કરવો.

**બીડાલ્ર** : (૧) શીડયુલ–બી ની નકલ.

કાર્યપાલક ઈજનેર સાઉથ વેસ્ટ(અઠવા)ઝોન સુરત મહાનગરપાલિકા

નકલ ૨વાના : તમામ ખાતા/ઝોનના કાર્યપાલક ઈજનેરશ્રી પ્રતિ જાણ તથા નોટીસ બોર્ડ પર પ્રસિધ્ધ કરવા સારૂ.

# **SURAT MUNICIPAL CORPORATION**

#### **SOUTH WEST (ATHWA) ZONE**

MAINTAINANCE AND REPAIRING WORK OF ANGANWADI NO.33,HARPATIVAS IN SOUTH WEST (ATHWA) ZONE, SURAT.

### **SCHEDULE-B**

			S		S.O.R. 2023-24
Sr. No.	ITEM	Qty.	Rate	Per	Amount
	Part -A Civil Work.				
1	Demolition including stacking of serviceable materials and disposal of unserviceable materials with all lead & lift.				
2	(i) RCC work  Demolition of brick work and stone masonary including stacking of serviceable materials and disposal of unserviceable materials with all	2.00	1057.47	C.M.	2114.94
	(II) in Cement mortar.	0.00	550.40	C.M.	0.00
3	Removing the scraping of old deteriosted plaster of any thickness from wall/R.C.C. member including strcking of serviceable material and disposal of unserviceable from site of work with all lead and lift.				
4	Dismentalling tiled or stone floors laid in mortar including stacking of serviceable materials and disposal of unserviceable materials with all lead & lift.	50.00	19.57 47.72		0.00 2386.00
5	Dismantling doors windows ventilators etc. (wood or steel) shutters including chowkhats, Architraves, holdfasts and other attachment etc. comp. and stacking them within all lead & lift. (I) not exceeding 3 sq.m. in area.				
6	Demolition of terrace including stacking serviceable materials and disposal of unserviceable materials with all lead and lift. (i) Brick tile covering.	0.00	187.71 42.42	S.M.	563.13
	Dismentaling steel work including dismembering and staking the materials with all lead and lift	0.00	3.67	Kg.	0.00
7	Dismantling sanitary fittings like wash basin, w.c. pan Indian and Europeans type, flushing tank etc. including stacking the materials with all lead & lift.	1.00	405.65	Each	405.65
8	Dismantling PVC pipe / A.C Rainwater /G.I pipes pipes with fittings and clamps including stacking the materials with all lead and lift. (For all floors).	0.00	74.77	R.M	0.00
9	Removing of All Scrap Material in tractor with hydraulic trailer and 8 Nos. Of labours from Campus Boundry Tiles flooring/Dedo	0.00	2600.00 47.72	Day S.M.	0.00 143.16
11	Providing & construction brick work using Fly Ash bricks having crushing strength not less than 35 Kg./sq.cm. in foundation & plinth in C.M. 1:6 (1 cement:6 sand ) etc. comp. Up to G.L./P.L.	0.00	4237.00		0.00
12	Providing & Applying 10mm.th.cement plaster in single coat on brick/concrete walls similar surfaces for plastering & finished even & smooth with a floating coat of cement slurry mixed with admixture of lime or neeru in required proportion etc. comp. in C.M 1:3 (1 cement : 3sand)	3.00		<u> </u>	0.00
	(A) For wall and similar surfaces Ground Floor	0.00	189.79	S.M.	0.00
13	Providing & Applying 20mm.th. Sand faced cement plaster on walls or similar surfaces at all floor levels consisting of 12 mm. Av. Th. backing coat of C.M. 1:3(1 cement:3 sand) & 8 mm.th. Finishing coat of C.M.1:1 (1 cement: 1 sand) - GroundFloor,FirstFloor,Second Floor	0.00		<b>5</b>	0.00
14	and Third(Terrace) Floor  Providing throating or plaster drip and moulding it to R. C. C. chajja etc. comp For all floor	0.00	330.88		0.00
15	Providing <b>20 mm deep finished groove</b> in plaster in line and level etc. Comp. For all Floor (M.R.)	0.00	41.66 50.00	R.M.	0.00
16	Providing & Laying green polished kota stone slab flooring at all floor levels, over 20 mm av.th.base of C.M. 1:6(1cement: 6 sand) laid over&joined with grey cement slurry incl. Rubbing & polishing etc.				
	comp. (A) 25 mm. (Tolerance +/- 2mm) For all Floor	5.00	989.45	S.M.	4947.25

Sr.					
No.	ITEM	Qty.	Rate	Per	Amount
17	Providing & Laying <b>polished kota stone</b> of machine cut edge slab 25 mm. th. in riser of steps, tread, dedo & pillars center piece not less than 1.2 mt.in width &side pieces of equal size as per design, laid on 10 mm.th. C.M.1:3(1 cement:3 sand)joined & polishing etc. For all Floor				
		10.00	1076.94	S.M.	10769.40
18	Providing & Laying white <b>glazed tiles</b> 6mm. th. of Orient, Kajaria, Jhonson,Nitco,Somani, Bell make at all floor levels, <b>in flooring</b> , treads of steps & landings laid on a bed of 12 mm. Av. Th.C.M.1:3(1cement :3 sand) finished with flush pointing in white cement etc.com. For all floors (Basic Rate: -Rs.285.0/S.M.)	0.00	057.42	S.M.	0.00
19	Providing & Laying white <b>glazed tiles</b> 6mm. th. Of Orient, Kajaria, Jhonson,Nitco,Somani,Bell make at all floor levels in <b>skirting</b> risers of steps & dado on 10 mm. th. C.M.1:3(1cement :3 sand) including necessary cement paste for fixing and joined with white cement slurry etc. complete. For all floors (Basic Rate:- Rs.285.0/S.M.)	0.00	857.42 887.64		0.00
20	Providing & laying granite slab 18mm thick in Window-Door seal Frame Etc laid on 10mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand) with nessary adhesive material and finished with flush pointing in white or colour cement, including rubbing & polishing comp (Basic Rate:- Rs.1200.0/S.M.) (MR)	0.00	2026.00		0.00
21	Labour Charges For Edge Finished For Granite	0.00	43.43		0.00
22	Providing & laying Vitrified tiles of 8mm thick of Orient, Kajaria, Jhonson, Nitco, Somani, Bell, Asian or Euro make in flooring,treads of steps & Landing laid on bed of 20 mm (Average) base of cement mortar 1:6 (1 Cement : 6 Coarse sand) on new surface or fixing on existing flooring by adhesive material including dismentaling of existing flooring and jointed with colour cement slurry including finished with flush pointing & cleaning the surface etc. comp.Size 24" x 24" (Basic Rate-Rs.612.0/S.M.)  For Antiskid tiles	10.00	1397.83	S.M.	13978.30
23	Providing and laying <b>Vitrified tiles 8 to 10 mm thick</b> , 24" x 24" in flooring treads of steps and landing laid on a bed of 12mm thick cement mortar 1:3 (1 cement : 3 coarse sand) finishing with flush pointing in				
24	white cement. (Basic Rate-Rs.366.0/S.M.)  Providing and laying Vitrified tiles 8 to 10 mm thick, 36" x 36" in skrting risers of steps and dedo on 10mm thick cement plaster 1:3 (1 cement : 3 coarse sand) and jointed with white cement slurry. (Basic Rate- Rs.750.0/S.M.)	10.00	1484.61 1538.85		74230.50 15388.50
25	Providing and laying Cement Concrete pavement (25mm to 50mm thick) with 1:2:4 (1 cement : 2 coarse sand : 4 stone aggregate 20mm nominal size) including finishing with floating coat of neat cement	10.00	1000.00	C.IVI.	10000.50
26	complete.  Providing & fixing at all floor levels, both face polished machine cut edge green kota stone slab (30mm) for urinal partition joined with grey cement slurry (1:1) incl. Rubbing & polishing etc. complete. (M.R.)	0.00	900.00		0.00
27	Providing & fixing 35mm.th. Flush Door Solid Double Core type Both Face water proof Ply Vennered & 1.5 mm th.laminate shall be pasted on both side with adhesives as specified by the manufacturers. The laminate shall be as per approved shade & texture, of make incl. Sal wood frames of finished size 12cm x 7cm.incl. S.S. Hinges with nessary screws & Anodized aluminum fixtures & fastenings For all Floor (MR)	2.00	3720.00		7440.00
	(A) Same as Above But Without Frame	0.00	2520.00		0.00
28	Providing and fixing FRP FRAME size 125 x 65 mm and 35 mm thick FRP shutter with wood grain raised panneled design finish shutter having extra reinforcement on sides & edges in Gel coat finish. The core of the shutter & frmae is to be filed up with injected polyurethene foam done in situ along with embedded wooden pieces for stiffening & also taking hinges & fixtures. The whole FRP frame & shutter is to be water proof weather proof,termite proof &resistance to mild acid/alkali. Rates are to be inclusive of S.S.hinges with fastener sleeve & alluminium fixtures & fastentings. Product should have 3 years performance guarantee and company have ISO 9001-2000 certificate.	2.00	2019.98	S.M.	4039.96
	(A) Same as Above But Without Frame	0.00	2805.78		0.00

Sr.					
No.	ITEM	Qty.	Rate	Per	Amount
29	Replacement of wooden office table / file storage parts ISI marks with				
	necessary hardware, screws materials etc. complete as per instruction				
	by engineer in charge. (A) Drawer / shutter locks	1.00	250.00	No.	250.00
	(B) SS 4" D Handles	2.00	80.00	No.	160.00
	(C) Drawer channel	2.00	275.00	No.	550.00
	(D) SS 3" heavy hinges	1.00	80.00	No.	80.00
30	Providing & fixing wooden notice board with Righting laminated board finish using 12mm th.Back commercial plywood approved make, 01mm th. SF finish laminate,teakwood framing & necessary hardware				
	materials etc. inside and liping french polish finish complete in all respects by engineer in charge complete.	0.00	1950.00	S.M.	0.00
31	Providing and fixing window having extruded aluminium <b>Powder</b>	0.00	1000.00	O.IVI.	0.00
	Coated section frame main outer size 63.50 x 38.10 x1.95 mm (of Jindal section no.4605, @ Wt. 1.094Kg/mt) horizontal <b>Two track</b> member size 61.85 mm x 31.75 mm x 1.20 mm (of jindal section no:8687, @ Wt. 0.695 Kg/mt.) vertical member of size 61.85 mm x 31.75 mm x 130 mm (of jindal section no:8758 @ wt. of 0.659 kg/mt) with sliding shutters of horizontal member size 40 mm x18 mm x 1.29 mm ( of jindal section no:8949, @ Wt. of .456 Kg/mt) vertical member of size 40 mm x 18 mm x 1.29 mm (of jindal section no:8947, @ Wt. of 0.456 Kg/mt/section 8948, @ Wt. of 0.457 Kg/mt) with 5 mm thick				
	tranparent bronze colour tineted float glass with powder coated aluminium fittings and fixtures and transparent silicon sealant glass				
	fixing to frame as per details etc. complete for window.				
		0.00	1705.67	S.M.	0.00
- 00	(A) Same as above but Colour anodized	4.00	1705.67	S.M.	6822.68
32	Providing and fixing standared extruded of aluminium section of size 61 x 37.0 x0.90 mm (of Jindal section no.14080, @ Wt. 0.471 Kg per mt) with colour <b>powder coated</b> alluminium frame for Lovered Glass ventilation with 4 mm thick Figured glass as details etc. complete <b>for ventilation</b> . (MR)	0.00	2414.00	S.M.	0.00
	(A) Same as above but Colour anodized	1.00	2414.00		2414.00
33	Providing and fixing standared extruded of aluminium section of size 61 x 37.0 x0.90 mm (of Jindal section no.14080, @ Wt. 0.471 Kg per mt) with <b>Powder Coated</b> alluminium frame with 5 mm thick transparent bronze colour tinted float glass as details etc. complete for <b>fix window</b> .				
	(MR)	0.00	2336.00		0.00
34	(A) Same as above but Colour anodized Providing & fixing M.S.Grills of required pattern to wooden frames of windows etc. At all floor levels with M.S. flats at required spacing & frame around square or round bars with round headed bolts & round headed bolts and nuts or by screws incl. Priming coat of Red lead	0.00	2336.00	S.M.	0.00
	paint etc. comp. (A) Plain grill For all Floors	100.00	104.20	Kg.	10420.00
35	Providing & fixing in position <b>collapsible steel shutters</b> with vertical channels 20 x10 x 2 mm. Braced with flat iron diagonals 20 x5mm size with top & bottom rails of T-iron 40x40x6mm. with 38mm dia. steel pulleys comp. with bolts, locking arrangements, stoppers, handles incl. applying a priming coat of Redlead paint etc. comp.	2.00	5865.10	e M	11720 20
36	Providing & fixing M.S.Fan clamps at all floor levels type I of 16 mm	2.00	5005.10	S.M.	11730.20
	dia M.S. Bar bent to shape with hooked ends to R.C.C. Slabs during				
	laying all as per standard design For All Floor	0.00	129.02	Each	0.00
37	Distempering two coats with oil bound washable distemper of approved brand & manufacture & of required shade on wall surface to give an even shade over and & incl. a priming coat of alkali resistance primer of approved brand after throughly brushing the surface to give an even shade after throughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surface even and smooth.				
	(A) For wall & similar surfaces	80.00	72.23	S.M.	5778.40
38	(B) For ceilings and soffits do Extra Subsequant coat over above Item	30.00	80.35	S.M.	2410.50
- 50	(A) For wall & similar surfaces	0.00	30.39	S.M.	0.00
	(B) For ceilings and soffits	0.00	33.57	S.M.	0.00
39	Applying <b>two coats of primer &amp; two coats of putty</b> before applying colour to any new surface making surface even & smooth incl. cleaning the surface of all dirt, dust & foreign matter.	100.00	40.59	S.M.	4059.00

41	Distempering two coats on previously distempering wall (without primer) with oil bound washable distemper of approved brand &				
41	required shade on wall surface to give an even shade after throughly brushing the surfaces clean of all grease, dirt loose places of sceles & also including preparing the surface even and smooth.	0.00	38.50	S.M.	0.00
	Wall painting with <b>two coats of Acrylic emulsion plastic paint</b> of approved brand over existing surface to give an even shade & surface free from mortar dropping & other foreign matter & sand papered smooth etc. comp.	0.00	52.92		0.00
42	Applying <b>Priming coat over new steel and other metal surface</b> after over and including preparing the surface by throughly cleaning oil, grease dirt and other foreign matter and scoured with brushed fine steel wool, scrapers and sand paper with ready mixed priming paint brushing red lead.	30.00	35.00		1050.00
43	Painting two coat (excluding priming coat) on new steel and other metal surface with synthetic enemal paint, burshing to give an even shade including cleaning the surface of all dirt, dust and other foreign matters.				
44	Painting two coats of enamel paint (Excluding priming coat) over previously painted wall with even shade & surface after removing dirt, dust foreign matter etc. comp.(M.R.)	0.00	65.31 38.03		1959.30
45	Painting two coats of enamel paint over priming coat after removing entire whitewash/colourwash surface dirt, dust foreign matter & also incl. preparing the surface even & sand papered smooth etc. comp.(M.R.)	0.00	90.00		0.00
46	Providing & applying two coats of weather shield max paint (3 coats may be required in case of darker colours.) of ICI Dulux or Apex Ultima of Asian Paint including applying exterior acrylic primer coat as per manufacturers specification and directions in shade and colour approved by architects, on exterior surfaces of the building including scaffolding, preparing the surface, watering, curing etc. complete and as directed by the architects and manufacturers.  Surface Preparation: surface is thoroughly clean, dry and free from all loose dirt, chalk, grease, fungi, algae and flaking paint. This can be achieved by brushing with a wire/ stiff coir brush, followed by water jetting if required. Fill up all minor cracks and defects with white cement and sand mixture in the ratio 1:3. For application on previously painted wall, previous coatings of paint must be thoroughly scraped off and Clean the surface thoroughly using wire brushes.  Priming: Apply a liberal coat of exterior acrylic primer and allow it to dry for 4-5 hours. Application of putty is not recommended. Minimum 4-6 hours duration is required between each coat of weather shield max paint (M.R.)				
47	Steel work welded in built up sections, framed work including cutting, hoisting, fixing in position and applying a priming coat of red lead paint  (A) in beams & joists channels angles, tees, flats with connection plates	50.00	82.00	S.M.	4100.00
	or angle cleats as in main & cross beams,hip & trussed purlins connected to common raffers & the like.  (B)For work like chain link fencing, above compound wall etc.  (C)in trusses & trussed purlins upto 25m.Span &15m.Overall height	100.00 15.00 15.00	90.48 90.48	Kg. Kg.	9048.00 1357.20 1357.20
48	Providing & Fixing Polycarbonate sheet roofing with surface of the sheet is coated with an anti-UV Co-extrusion layer having good weather resistance, it can maintain its optical properties and mechanical performance for a long time. Fasting is usually done by screws. , The fastening screws should be inserted about 500 mm apart and 300mm apart. Along the supporting internal purlin and edge pulin.All fixing holes with diameter at least 2 mm larger than screw must be predrilled into each screw location. The screws should be 6mm diameter with length according to sheet thickness and corrosion resistant, with at least heavy duty hot dripped galvanized or stainless steel. Excluding the cost of purlins rafter and trusses. (M.R.)	0.00	1261.00	S.M.	0.00

Sr. No.	ITEM	Qty.	Rate	Per	Amount
131	Providing & fixing <b>black board</b> on walls of <b>1.8mt.x1.2mtsize</b> made up to 12 mmth.B.W.P. Plywood (Brand Saras, Kitply, Uniply, Anchor, Green, Wood Stock or century) fixed with teak wood beading of 65 mmx 50mm size, rubbing & sanding comp., incl. applying two coats of black board paint over a priming coat on plywood & French polishing the frame all round etc. Comp. as per instruction of Engineer in charge				
49	(M.R.) Providing & Fixing Reading table size 8' x 4' and height 2'-6" with table top 18mm thick (Brand Saras,Kitply,Uniply, Anchor, Green,Wood Stock or century) commercial plywood with 1.0mm thick lamination sheet fitting with teakwood moulding table top supported on 3" x 3" teakwood leg & 3" x 11/2" teakwood framing top and bottom with french polish labour work hardware etc. as per site in charge instruction and	1.00	3915.00		3915.00
50	as per drawing. (M.R.) Crack Repairs:-Crack filling using fiber reinforced polymer modified mortar after openning crack in "V" grove, Making Surface dust free, with a bond coat of polymer as per the data sheet for crack repairing cracks less than 8mm	0.00	12450.00	No.	12450.00
51	Providing and Fixing Stainless Steel (Grade 304) Railing made of Hollow tubes, channels, plates etc. Including Welding, Grinding, Buffing, Polishing and Making Curvature (Wherever Required) and fitting the same with necessary Stainless Steel Nuts and Bolts Complete, i/c fixing the Railing with Necessary Accessories & Stainless Steel Dash Fastenders, Stainless Steel Bolts etc. of Required size, on the top of the floor or the side of waist slab with suitable arrangement as per aprproval of Engineer-incharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.)	0.00	450.00	Kg.	0.00
52	Carring out plinth treatment to post construction / existing structure by spraying chemical solution for termite control treatment including labour and material consistment with ISI specification. Using Chlordene and Chiorpurfiles 20 EC. As per 6131_paret-II Consentration Weight one percent is recommended i.e. one litre 20 EC chemical emulsion with 19 liter give 1% concrentration inclusive of one litre chemical emulsion appication at the rate of 5 litre chemical / Sqm of surface is				
	recommended as per IS.	0.00	82.89	S.M.	0.00
	WATER SUPPLY & SANITARY ITEMS				
53	Prov.& Fixing water closet squatting pan (Orissa type W.C.pan) at all floor levels, size 500mm incl. 100 mm size "P'or "S" trap for water closet squatting pan joining the trap with the pan & soil pipe in C.M. 1:1 (1cement :1 fine sand) etc. Comp.(A) Vitreous china long pattern of	0.00	2075.00	Na	0.00
	approved colour For all Floor Make -Cera,Parry ware, Jaquar, Hindware	0.00 1.00	3275.00 2150.00		0.00 2150.00
54	Providing and fixing <b>Wash Down Water closet European type W.C. pan</b> with integral P or S trap including jointing the trap with soil pipe in cement mortar 1:1 (1 cement : 1 find sand) (seat and cover to be measured and paid for separately) (A) Viterous china pattern - I (i) in				
55	approved colour  Providing and fixing Wash Down Water closet European type W.C. pan with integral P or S trap with normal closing seat cover L bend including jointing the trap with soil pipe in cement mortar 1:1 (1 cement : 1 find sand) (A) Viterous china pattern - I	0.00	1303.71	Each	0.00
56	Make -Cera,Parry ware, Hindware, Jaquar - 350 x 500 x 390 mm  Providing and fixing plastic seat and cover for wash down water closet with C.P. brass hinges and rubber buffers (B) Black plastic seat	1.00	3800.00	No.	3800.00
57	and cover.  Providing & fixing wash basin with single hole for pillar tap at all floor levels, with C.I. or M.S. Brackets painted white incl. cutting holes & making good the same incl. fittings such as pillar tap, capstan head screw down high pressure with screws, shanks & back nuts, C.P. Brass waste trap, screw down stop tap 15 mm. dia. etc. complete. (A) Vitreous china flat back wash basin 550 mm.x 400 mm. size in	0.00	291.33		0.00
58	annoved colour For all Floor. Providing & fixing wash Hung basin with single hole for pillar tap, Size 550x400mm at all floor levels, with C.I. or M.S. Brackets painted white incl. cutting holes & making good the same etc. complete. For all Floor	0.00	2000.00	110.	3.00
	Make -Cera,Parry ware, Jaquar, Hindware	1.00	2656.00	No.	2656.00

Sr.	itte.	<b>0</b> tu	Data	Don	A
No.	ITEM	Qty.	Rate	Per	Amount
59	Providing & fixing <b>Urinal</b> or approved quality including conecting the Urinal with waste pipe, tap etc. complete. (A) White earthenware flat back or corner type size 430 mm x 260mm x 350mm	0.00	1036.27	Each	0.00
60	Providing & fixing white viterious china <b>Urinal</b> of size 450 x 325 mm as per IS-2556 (Part-2) with C.I. Hangers and 15mm dia. C.P. Spreader, 32mm dia CP bottle trap and pipe to wall with C.P. Flange complete including cutting and making good the walls and floors wherever required.				
61	Make -Cera,Parry ware, Jaquar, Hindware Providing & fixing 600 mm.x 450 mm. mirror of superior glass at all	10.00	2476.00	No.	24760.00
01	floor levels, mounted on 6 mm. th. A.C. sheet or plywood sheet & fixed to wooden plugs with C.P.brass screws and washers etc. For all Floor				
62	Providing & fixing <b>Health Faucet ABS Body</b> with wall Hook & 1 Meter	0.00	833.73	No.	0.00
02	Chrome plated PVC Hose Pipe.				
63	Make -Cera,Parry ware, Jaquar, Hindware  Providing & Fixing Hand Shower at all floor levels,	1.00	1350.00	No.	1350.00
	of approved quality including fixing etc. Complete				
64	Make -Cera, Parry ware, Jaquar, Hindware Prov. & Fixing S.W. Gully trap with C.I.grating brick masonary (C.M	0.00	1800.00	No.	0.00
04	1:5)chamber & water tight C.I. cover with frame of 300mmx300mm size (inside) with weight to be not less than 4.53kg, includ. plastering smooth inside & outside 15mm. th' in C.M.1:3 etc. comp. (i) Square				
	mouth traps (A) 100mm x 100mm Size -P type	0.00	1292.19	No.	0.00
0.5	(B) 150mm x 100mm Size- P Type	0.00	1246.92	No.	0.00
65	Prov. & Fixing <b>S.W. Gully trap</b> with C.I.grating brick masonary (C.M 1:5)chamber & water tight Pre cast R.C.C. cover of 300mmx300mm size (inside) includ. plastering smooth inside & outside 15mm. th' in C.M.1:3 etc. comp. (i) Square mouth traps				
	(A) 100mm x 300mm Size -P type	0.00	1098.48 1053.30	No.	0.00
66	(B) 150mm x 100mm Size- P Type  Prov. & Fix. 10 cm.x15 cm.(4" x 6") S.W. trap with Inside dimension ,455 x 610 mm & 450 mm deep sewer trap chamber with 23 cm th'  B.B. masonary walls in C.M 1:5 with cement plaster 15 mm th' in C.M.  1:3 inside & outside to exposed faces, R.C.C. top slab with 1:2:4 mix ( 1 cement: 2 Sand: 4 Grade stone aggregate 20mm size) ,Foundation concrete 1:5:10 & fixing C.I. cover with frame to be not less than 38 kg.  On top etc. comp. for single pipe.				
	.(A).Same as above but Precast RCC heavy duty Cover instead of C.I.	0.00	3155.63	No.	0.00
	Cover	0.00	2904.47	No.	0.00
67	Extra for every additional depth of 0.1 mt beyoung 0.45 mt Providing & construction simple chamber of 23 cm. th' B.B. Masonary in C.M 1:5 with cement plaster 15 mm th' in C.M. 1:3 inside & outside to exposed faces, R.C.C. top slab with 1:2:4 mix (1 cement: 2 Sand: 4 Grade stone aggregate 20mm size) ,Foundation concrete 1:5:10 & fixing C.I. cover with frame to be not less than 38 kg. On top etc. comp. Inside dimension,455 x 610 mm &450 mm deep for single pipe	0.00	222.71	Each No.	0.00
	.(A).Same as above but Precast RCC heavy duty Cover instead of C.I.	0.00	2932.93	INO.	0.00
	Cover	1.00	2681.76		2681.76
68	Extra for every additional depth of 0.1 mt beyoung 0.45 mt Providing, Lowering & laying joining R.C.C. NP2 CLASS Pipe In C.M.  1:1 of following nominal internal diameters incl. Testing of pipes and joints etc. Comp	0.00	242.39	Each	0.00
	(A) 150 mm. dia	0.00	248.67	R.M.	0.00
	(B) 200 mm. dia (C) 250 mm. dia	0.00	255.53 462.58		0.00
69	Providing & Fixing C.P. Brass screw down bib tap at all floor levels, polished bright etc. comp(A) 15mm dia. For all Floors	0.00	186.63	R.M.	0.00
70	Providing and fixing <b>15mm Dia bib tap</b> with wall Flange at all floor levels,polished bright etc. Comp.  Make -Cera,Parry ware, Hindware, Jaquar	3.00	1323.00	No.	3969.00
71	Providing & Fixing <b>abonite ball cock</b> of approved qualities directed etc. comp.				
72	(A) 25 mm. dia.  Pro. & Fix. P.V.C. Ball valve at all floor levels etc. comp.	1.00	102.91	No.	102.91
'-	(A) 15 mm dia.	0.00	150.00	No.	0.00

Sr. No.	ITEM	<b>Qty.</b>	<b>Rate</b> 250.00	Per	Amount
	(B) 25 mm dia. (C) 40 mm dia.	0.00	400.00	No.	0.00
	(D) 50 mm dia.	0.00	774.21	No.	0.00
	(E) 65 mm dia.	0.00	1866.00	No.	0.00
	(F) 75 mm dia.	0.00	3568.47	No.	0.00
73	Providing and fixing Screw down stop taps.				
	(A) 15 mm dia.	0.00	241.39	No.	0.00
	(B) 20 mm dia.	0.00	262.60		0.00
	(C) 25 mm dia.	0.00	260.58	No.	0.00
74	Providing & fixing Metropole flush valve with wall flange 25mm with lever Knob at all floor levels, of approved quality incl. Fixing in pipe line etc. Comp				
	Make -Cera, Parry ware, Jaquar, Hindware	0.00	1690.00	No	0.00
75	Providing & Fixing Brass Laboratery cock at various places at all floor approved quality as directed By Eng.in charge.	0.00	957.50	No	0.00
76	Providing <b>Flush Cock</b> consisting lever, cartridge sleeve & flange & concealed part				
	Make -Cera, Parry ware, Jaquar, Hindware	1.00	2110.00	No.	2110.00
77	Providing & fixing <b>15mm C.P. Brass angle valve</b> (stop cock) with C.P. Copper connecting pipe 450mm long and nuts, washer and brass flange complete, including cutting and making good the wall where required.				
	Make -Cera, Parry ware, Hindware	1.00	1432.00	No.	1432.00
	Make -Jaquar	0.00	1432.00	No.	0.00
78	Pro. & Fix. Pilarcock with connection pipe at all floor level etc. comp.				
	(A) 15 mm dia.	0.00	225.00	No.	0.00
79	Providing and fixing C.P. Brass <b>pillar cock</b> with copper connection ,C.P. Brass screws complete				
	Make -Cera,Parry ware, Hindware, Jaquar	1.00	1423.00	No.	1423.00
80	Providing and fixing waste Pipe for Washbasin or sink (A ) 32 mm Dia	2.00	99.08	No.	198.16
81	Providing & Fixing PVC West Cuplin at various places at all floor approved quality as directed By Eng.in charge.	2.00	60.50	No.	121.00
82	Providing & Fixing S.S. West Cuplin at various places at all floor approved quality as directed By Eng.in charge.	0.00	93.50		0.00
83	Providing and fixing <b>Supply Pipe</b> for Washbasin or sink	2.00	80.00	No.	160.00
84	Providing and fixing Jet Sprey Cock at all floor level etc. complete.	0.00	500.00	No.	0.00
85	Providing & Fixing Brass Tee at all floor levels, of approved quality including fixing etc. Complete	0.00	000.00	NI.	0.00
00	(A) 15 mm dia.	0.00	300.00	No.	0.00
86	Providing & Fixing U.P.V.C Tee at all floor levels, of approved quality including fixing etc. Complete	0.00	200.00	NIa	0.00
87	(A) 25 mm dia.  Providing & Fixing U.P.V.C Alba at all floor levels, of approved quality	0.00	300.00	No.	0.00
	including fixing etc. Complete	0.00	0		
88	(A) 25 mm dia.  Providing and fixing chromium plate bottle trap with necessary coupling	0.00	300.00	No.	0.00
89	of approved quality for wash- basin Providing & Fixing Water proof M-Seal at various places approved	0.00	331.28		0.00
90	quality as directed By Eng.in charge. Providing and fixing	0.00	176.00	No.	0.00
90	(A) 40 mm thick RCC cover for simple chamber,s.w.trap & tank Top	0.00	400.00	No.	0.00
	(B) PVC water tank cover upto 2000 Lit.	0.00	200.00	No.	0.00
91	Supplying and fixing C.I. cover 300 mm X 300mm. without frame for gully trap (standard pattern) the weight of cover to be not less than 4.53 Ka.	0.00	660.00	No.	0.00
92	Providing and fixing C.I. Manhole cover 0.60 x 0.45 mt. Size having	5.50	200.00		5.00
93	weight not less than 35 Kg. etc. complete. Providing & Fixing R.C.C.Manhole Cover	0.00	958.17	No.	0.00
	(A) 12' x 12'	0.00	785.00	No.	0.00
	(B) 18' x 18'	0.00	985.00		0.00
	(C) 24' x 18'	0.00	1020.00		0.00
	(D) 24' x 24'	0.00	1175.00	No.	0.00
	(E) 30' x 30'	0.00	1350.00	No.	0.00

Providing & Fixing U-PVC pipe (SWR) confirming to IS no. 13592 (Type '8') of Prince/Supreme/Jain/Astral/Tusi make for soil and waste discharge system at all floor levels in All fixtures like bends, tees, shoe etc. jointed with resin of approved brand & manufacture etc. comp. (M.R.)	
(Type 'B') of Prince/Supreme/Jain/Astral/Tulsi make for soil and waste discharge system at all floor levels incl. All fixtures like bends, tese, shoe etc. jointed with resin of approved brand & manufacture etc. comp. (M.R.)  (A) 75mm Dia 5.00 100 100 100 100 100 100 100 100 100	mount
(A) 75mm Dia (B) 100 Met.)  (B) 10 mm. Dia. (D) 100 444.00 R.M. (D) 100 444.00 R.M. (D) 160 mm. Dia. (D) 160 mm. Dia. (D) 160 mm. Dia. (D) 160 mm. Dia. (D) 171 met. (D) 172 met. (D) 173 met. (D) 173 met. (D) 173 met. (D) 175 m	
Bij 110 mm. Dia.   10.00   444.00   R.M.   C) 130 mm. Dia.   10.00   47.00   R.M.   C) 100 mm. Dia.   10.00   17.10   R.M.   10.00   17	0000.00
C) 160 mm. Dia.	2060.00 4440.00
of Prince/Supreme/Jain/Astral/ Tulsi make for rain water at all floor levels incl. fixtures like bends, Lees, shoe etcipined with resin of approved brand & manufacture etc. comp. (M.R.).  (A) 75 mm. Dia	0.00
Eli 110 mm. Dia.   10.00   325.00 R.M.   Cl. 180 mm. Dia.   0.00   674.00 R.M.	
C() 160 mm. Dia.   0.00   674.00   R.M.	2030.00
Providing, Laying and jointing on true line and level LIPVC pipe (SCH-40) line of Prince/Supreme/Jain/Astral/ Tulsi/Finolex make including fittings make or equivalent as approved by angineer-in-charge. Pipe shall be fixed on the wall the help of clamp at every two meter C/C or shall be concealed as directed including necessary fittings etc. including testing of pipe and joints and fixing the same with adhesive solvent, including cost of all materials.    (A) 15 mm dia.	3250.00
40) line of Prince/Supreme/Jain/Astral/ Tulsi/Finolex make including fittings make or equivalent as approved by angineer-in-charge. Pipe shall be cincealed as directed including necessary fittings etc. including testing of pipe and joints and fixing the same with adhesive solvent, including cost of all materials.    (A) 15 mm dia.	0.00
(B) 25 mm dia. (C) 32 mm dia. (D) 40 mm dia. (E) 50 mm dia. (E) 50 mm dia. (F) 65 mm dia. (M.R.)  97 Providing & Fixing P.V.C. pipes (SCH-80) of Prince/ Supreme/ Jain/ Astral/ Tulsi/Finolex make for water supply line at all floor levels incl. fixtures like bends, tese, shoe etc. including testing of pipe and joints and fixing the same with adhesive solvent, including cost of all materials. (M.R.) (A) 15 mm dia. (B) 25 mm dia. (C) 40 mm dia. (E) 50 mm dia. (D) 40 mm dia. (E) 50 mm dia. (E) 50 mm dia. (D) 40 mm dia. (E) 50 mm d	
(C) 32 mm dia. (D) 40 mm dia. (E) 50 mm dia. (F) 65 mm dia. (N.R.)  Providing & Fixing P.V.C. pipes (SCH-80) of Prince/ Supreme/ Jain/ Astral/ Tulsi/Finolex make for water supply line at all floor levels incl. fixtures like bends, tees, shoe etc joined with resin of approved brand & manufacture etc. comp. Pipe shall be fixed on the wall the help of clamp at every two meter C/C or shall be concealed as directed including necessary fittings etc. including testing of pipe and joints and fixing the same with adhesive solvent, including cost of all materials.  (M.R.)  (A) 15 mm dia. (B) 25 mm dia. (D) 40 mm dia. (E) 50 mm dia. (E) 50 mm dia. (E) 50 mm dia. (D) 40 mm dia. (E) 50 mm dia. (E) 50 mm dia. (D) 40 mm dia. (E) 50 mm dia. (D) 40 mm dia. (E) 50 mm dia. (E) 50 mm dia. (E) 50 mm dia. (E) 50 mm dia. (D) 40 mm dia. (E) 50 mm dia. (D) 40 mm dia. (E) 50 mm dia. (D) 40 mm dia. (D) 40 mm dia. (E) 50 mm dia. (D) 40 mm dia. (D) 40 mm dia. (E) 50 mm dia. (D) 40	726.50
(D) 40 mm dia. (E) 50 mm dia. (NR.)  97 Providing & Fixing P.V.C. pipes (SCH-80) of Prince/ Supreme/ Jain/ Astral/ Tulsi/Finolex make for water supply line at all floor levels incl. fixtures like bends, tees, shoe etc joined with resin of approved brand & manufacture etc. comp. Pipe shall be fixed on the wall the help of clamp at every two meter C/C or shall be concealed as directed including necessary fittings etc. including testing of pipe and joints and fixing the same with adhesive solvent, including cost of all materials.  (M.R.)  (A) 15 mm dia. (B) 25 mm dia. (C) 40 mm dia. (E) 50 mm dia. (D) 40 mm dia. (E) 50 mm dia. (E) 50 mm dia. (D) 40 mm dia. (E) 55 mm dia. (E) 55 mm dia. (E) 55 mm dia. (E) 55 mm dia. (E) 50 mm dia. (E)	918.40
(E) 50 mm dia. (M.R.)  97 Providing & Fixing P.V.C. pipes (SCH-80) of Prince/ Supreme/ Jain/ Astral/ Tulsi/Finolex make for water supply line at all floor levels incl. fixtures like bends, tees, shoe etc joined with resin of approved brand & manufacture etc. comp. Pipe shall be fixed on the wall the help of clamp at every two meter C/C or shall be concealed as directed including necessary fittings etc. including testing of pipe and joints and fixing the same with adhesive solvent, including cost of all materials.  (M.R.)  (A) 15 mm dia.  (B) 25 mm dia.  (C) 40 mm dia.  (E) 50 mm dia.  (F) 65 mm dia.	0.00
Formiding & Fixing P.V.C. pipes (SCH-80) of Prince/ Supreme/ Jain/ Astral/ Tulsi/Finolex make for water supply line at all floor levels incl. fixtures like bends, tees, shoe etc joined with resin of approved brand & manufacture etc. comp. Pipe shall be fixed on the wall the help of clamp at every two meter C/C or shall be concealed as directed including necessary fittings etc. including testing of pipe and joints and fixing the same with adhesive solvent, including cost of all materials. (M.R.)  (A) 15 mm dia.	0.00
Providing & Fixing P.V.C. pipes (SCH-80) of Prince/ Supreme/ Jain/ Astral/ Tulsi/Finolex make for water supply line at all floor levels incl. fixtures like bends, tees, shoe etc joined with resin of approved brand & manufacture etc. comp. Pipe shall be fixed on the wall the help of clamp at every two meter C/C or shall be concealed as directed including necessary fittings etc. including testing of pipe and joints and fixing the same with adhesive solvent, including cost of all materials. (M.R.)  (A) 15 mm dia.	0.00
(B) 25 mm dia. (D) 40 mm dia. (E) 50 mm dia. (E) 50 mm dia. (F) 65 mm dia.  98 Providing & Fixing PVC Nanhi trap 3 <sup>1</sup> / <sub>2</sub> " ht.of Prince/ Supreme/ Jain/ Astral/ Tulsi/Finolex make at all floor levels of self cleaning design with screwed down or hinged grating incl. cost of cutting making good the walls & floors etc. For all Floor  99 Providing and fixing 100x 100 mm Size P.V.C /C.I Greting (Jali ) for Nani Trap.  100 Providing & Fixing in position PVC Cowl vent to pipes of Prince/Supreme/Jain make etc.Comp. (M.R.) (A) 75 mm. dia. (B) 110 mm Dia.  101 Providing & fixing M.S. Holder Bat clamps at all floor levels of approved design to C.I. Or S.C.I pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm. dia. (M.R.)  102 Providing & fixing G.I./Aluminum Patti clamps at all floor levels of approved design to C.I. Or S.C.I pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm. dia. (M.R.)  103 Providing & fixing Z - clamps at all floor levels of approved design to C.I. S.C.I. or PVC pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm. dia. (M.R.)  103 Providing & fixing Z - clamps at all floor levels of approved design to C.I. S.C.I. or PVC pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm dia as per architect instructions. (M.R.)  (M.R.) (A) 40 to 50 mm dia  (B) 75 to 90 mm dia  0.00 75.00 No.	
(B) 25 mm dia. (D) 40 mm dia. (E) 50 mm dia. (E) 50 mm dia. (E) 65 mm dia.  (F) 65 mm dia.  0.00 372.00 R.M. (F) 65 mm dia.  0.00 635.00 R.M.  Providing & Fixing PVC Nanhi trap 3 <sup>1</sup> / <sub>2</sub> " ht.of Prince/ Supreme/ Jain/ Astral/ Tulsi/Finolex make at all floor levels of self cleaning design with screwed down or hinged grating incl. cost of cutting making good the walls & floors etc. For all Floor  99 Providing and fixing 100x 100 mm Size P.V.C /C.I Greting (Jali ) for Nani Trap.  100 Providing & Fixing in position PVC Cowl vent to pipes of Prince/Supreme/Jain make etc.Comp. (M.R.) (A) 75 mm. dia. (B) 110 mm Dia.  101 Providing & fixing M.S. Holder Bat clamps at all floor levels of approved design to C.I. Or S.C.I pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm. dia. (M.R.)  102 Providing & fixing G.I./Aluminum Patti clamps at all floor levels of approved design to C.I. Or S.C.I pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm. dia. (M.R.)  103 Providing & fixing Z - clamps at all floor levels of approved design to C.I. Or S.C.I pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm. dia. (M.R.)  103 Providing & fixing Z - clamps at all floor levels of approved design to C.I. S.C.I. or PVC pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm dia as per architect instructions. (M.R.)  (M.R.)  (A) 40 to 50 mm dia  0.00 62.00 No.	2490.00
E  50 mm dia.	5120.00
Fig. 65 mm dia.   0.00   635.00   R.M.	0.00
98 Providing & Fixing PVC Nanhi trap 3¹/₂* ht.of Prince/ Supreme/ Jain/ Astral/ Tulsi/Finolex make at all floor levels of self cleaning design with screwed down or hinged grating incl. cost of cutting making good the walls & floors etc. For all Floor  99 Providing and fixing 100x 100 mm Size P.V.C /C.I Greting (Jali ) for Nani Trap.  100 Providing & Fixing in position PVC Cowl vent to pipes of Prince/Supreme/Jain make etc.Comp. (M.R.)  (A) 75 mm. dia. (B) 110 mm Dia.  101 Providing & fixing M.S. Holder Bat clamps at all floor levels of approved design to C.I. Or S.C.I pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm. dia. (M.R.)  102 Providing & fixing G.I./Aluminum Patti clamps at all floor levels of approved design to C.I. Or S.C.I pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm. dia. (M.R.)  103 Providing & fixing Z - clamps at all floor levels of approved design to C.I. S.C.I. or PVC pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm. dia. (M.R.)  103 Providing & fixing Z - clamps at all floor levels of approved design to C.I. S.C.I. or PVC pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm dia as per architect instructions. (M.R.)  (M.R.)  (A) 40 to 50 mm dia  100 0.00 62.00 No.	0.00
99 Providing and fixing 100x 100 mm Size P.V.C /C.I Greting (Jali ) for Nani Trap.  100 Providing & Fixing in position PVC Cowl vent to pipes of Prince/Supreme/Jain make etc.Comp. (M.R.)  (A) 75 mm. dia. (B) 110 mm Dia.  101 Providing & fixing M.S. Holder Bat clamps at all floor levels of approved design to C.I. Or S.C.I pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm. dia. (M.R.)  102 Providing & fixing G.I./Aluminum Patti clamps at all floor levels of approved design to C.I. Or S.C.I pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm. dia. (M.R.)  103 Providing & fixing Z - clamps at all floor levels of approved design to C.I. S.C.I. or PVC pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm. dia. (M.R.)  103 Providing & fixing Z - clamps at all floor levels of approved design to C.I. S.C.I. or PVC pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm dia as per architect instructions. (M.R.)  (A) 40 to 50 mm dia  (B) 75 to 90 mm dia  2.00 40.00 NO  0.00 30.00 NO	0.00
Nani Trap.  100 Providing & Fixing in position PVC Cowl vent to pipes of Prince/Supreme/Jain make etc.Comp. (M.R.)  (A) 75 mm. dia. (B) 110 mm Dia.  101 Providing & fixing M.S. Holder Bat clamps at all floor levels of approved design to C.I. Or S.C.I pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm. dia. (M.R.)  102 Providing & fixing G.I./Aluminum Patti clamps at all floor levels of approved design to C.I. Or S.C.I pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm. dia. (M.R.)  103 Providing & fixing Z - clamps at all floor levels of approved design to C.I. S.C.I. or PVC pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm. dia. (M.R.)  (A) 40 to 50 mm dia (B) 75 to 90 mm dia (C) 0.00 43.63 No.  2.00 40.00 NO  0.00 30.00 NO  0.00 30.00 No  0.00 20.00 No.	1116.72
Prince/Supreme/Jain make etc.Comp. (M.R.)  (A) 75 mm. dia. (B) 110 mm Dia.  2.00 40.00 NO  Providing & fixing M.S. Holder Bat clamps at all floor levels of approved design to C.I. Or S.C.I pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm. dia. (M.R.)  Providing & fixing G.I./Aluminum Patti clamps at all floor levels of approved design to C.I. Or S.C.I pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm. dia. (M.R.)  Providing & fixing Z - clamps at all floor levels of approved design to C.I. S.C.I. or PVC pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm. dia. (M.R.)  Providing & fixing Z - clamps at all floor levels of approved design to C.I. S.C.I. or PVC pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm dia as per architect instructions. (M.R.)  (A) 40 to 50 mm dia 0.00 62.00 No.  (B) 75 to 90 mm dia 0.00 75.00 No.	0.00
(A) 75 mm. dia. (B) 110 mm Dia. 2.00 40.00 NO  Providing & fixing M.S. Holder Bat clamps at all floor levels of approved design to C.I. Or S.C.I pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm. dia. (M.R.)  Providing & fixing G.I./Aluminum Patti clamps at all floor levels of approved design to C.I. Or S.C.I pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm. dia. (M.R.)  Providing & fixing Z - clamps at all floor levels of approved design to C.I. S.C.I. or PVC pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm. dia. (M.R.)  (A) 40 to 50 mm dia (B) 75 to 90 mm dia (B) 75 to 90 mm dia (C) 0.00 40.00 NO.	
(B) 110 mm Dia.  101 Providing & fixing M.S. Holder Bat clamps at all floor levels of approved design to C.I. Or S.C.I pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm. dia. (M.R.)  102 Providing & fixing G.I./Aluminum Patti clamps at all floor levels of approved design to C.I. Or S.C.I pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm. dia. (M.R.)  103 Providing & fixing Z - clamps at all floor levels of approved design to C.I. S.C.I. or PVC pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm dia sper architect instructions. (M.R.)  (M.R.)  (A) 40 to 50 mm dia  (B) 75 to 90 mm dia  0.00 50.00 No.	80.00
approved design to C.I. Or S.C.I pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm. dia. (M.R.)  102 Providing & fixing G.I./Aluminum Patti clamps at all floor levels of approved design to C.I. Or S.C.I pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm. dia. (M.R.)  103 Providing & fixing Z - clamps at all floor levels of approved design to C.I. S.C.I. or PVC pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm dia as per architect instructions. (M.R.)  (A) 40 to 50 mm dia  (B) 75 to 90 mm dia  0.00 30.00 No.	100.00
Providing & fixing G.I./Aluminum Patti clamps at all floor levels of approved design to C.I. Or S.C.I pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm. dia. (M.R.)  Providing & fixing Z - clamps at all floor levels of approved design to C.I. S.C.I. or PVC pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm dia as per architect instructions. (M.R.)  (A) 40 to 50 mm dia 0.00 62.00 No.  (B) 75 to 90 mm dia 0.00 75.00 No.	0.00
Providing & fixing Z - clamps at all floor levels of approved design to C.I. S.C.I. or PVC pipes including the cost of cutting holes & making good the wall etc. Complete - 100 mm dia as per architect instructions.  (M.R.)  (A) 40 to 50 mm dia  (B) 75 to 90 mm dia  0.00  75.00  No.	0.00
(A) 40 to 50 mm dia 0.00 62.00 No. (B) 75 to 90 mm dia 0.00 75.00 No.	0.00
(B) 75 to 90 mm dia 0.00 75.00 No.	0.00
I I/C) 110 mm dia to unto 150 mm dia I 0.00I 00.00I No I	0.00
(C) 110 mm dia to upro 150 mm dia 0.00 90.00 No.	0.00

Sr. No.	ITEM	Qty.	Rate	Per	Amount
104	Providing & Fixing <b>Kathi around the vertical PVC drainage pipes</b> for concealing with cement plaster 20 mm avg thickness(CM 1:3 [1 cement :3 coarse sand]) finishing as per instruction given by Eng. incharge. for (M.R.)				
	(A) 75 mm PVC PIPE (B) 100 mm /110 mm PVC PIPE	10.00 10.00	173.00 180.00		1730.00 1800.00
105	(ISI) mark water tank of required capacity each with all necessary fittings & connection etc. complete on terrace.	10.00	100.00	IX.IVI.	1000.00
		1000.00	3.95	Lit.	3950.00
106	Providing & laying ordinary C.C.1:1.5:3 mix for R.C.C. work incl. boxing, centering, vibrating, curing & mixed with approved water proofing cement compound or "CEMWET"or"PIDICRETE LW"integral water proofing admixture as water proofing agent to be mixed with 50 kg. cement bag shall be as recommended by the manufacture of the water proofing material, concrete work for top, bottom slab & side pardi for <b>Under ground Tank</b> & Item incl. Necessary excavation & refilling the available earth, 15 cm th' C.C 1:4:8 for bedding concrete, Half B.M. in C.M. 1:4 outside wall, inside R.C.C. pardi as per design, 10mm.th. water proofing cement plaster in C.M. 1:3 with smooth finishing,watering etc.Comp.to all inner face & bottom of tank curing etc. comp. incl. Locking arrangement, outlet, inlet, overflow & wash out pipe arrangement as necessary & C.I. Cover 0.60 x .045 weight not less then 35kg. etc. com. as per structural drawing excluding Steel & as directed by Engineer-in-charge				
	Underground tank	0.00	5.46	Lit.	0.00
107	Providing & Laying Commercial Quality white glazed tiles 6mm. th. in flooring laid on a bed of 20 mm. Av. Th.C.M.1:3(1cement :3 sand) & on wall Of R.C.C. Tank with necessary cement paste for fixing and joined with white cement slurry etc. complete. finished with flush pointing in white cement etc.com.  Providing and filling in depressions of Bath and W.C. At all floor levels, after completing plumbing work of pans, pipes,traps etc.with cinder or fly ash as directed by Engineer in charge etc. comp	0.00	0.90		0.00
109	NOTE:- (1) The whole work is to be executed through specialized agency with a guarantee of 10 (Ten) years given on a prescribed proforma duly stamped (2) The rate shall include for work at all floors & conducting water proof test as directed. (M.R.)				
	(A) Providing and laying water proofing treatment to vertical and horizontal surfaces of depressed portions of W.C.,kitchen and the like consisting of:  (a) I course of applying cement slurry @ 4.4 kg/sqm mixed with water proofing compound conforming to IS: 2645 in recommended proportions.  (b) Il course of a layer of plaster in C.M. 1:3 with water proofing compound confirming to IS:2645 about 25 mm. th' in the floor of the depression & about 18mm th' On the side walls of the depression up to the floor level, water proofing plaster about 18 mm. th' be continued on the walls above the floor level for a height of 600 mm. with surface suitable to receive further treatment  (c) Finishing top with stone aggregate 10mm to 12mm nominal size spreading @0.008 C.M./S.M., thoroughly embedad in plaster layer. as per specifications & instructions of Engineer in charge (Cement				
İ	consumption 0.316 Bags / S.M.)	0.00	296.00	S.M.	0.00

Sr. No.	ITEM	Qty.	Rate	Per	Amount
	(B) Providing and laying integral cement based water proofing treatment including preparation of surface as required for treatment of roofs, balconies, terraces etc. consisting of following operations.  (a) Applying and grouting a slurry coat of neat cement using 2.75 kg/sqm of cement admixed with proprietary water proofing compound comforming to IS:2645 over the R.C.C. slab including cleaning the surface before tratment.  (b) Laying cement concrete using broken bricks/brick bats 25 mm to 100 mm size with 50% of cement mortar 1:5 (1 Cement : 5 Coarse sand) admixed with proprietary water proofing compound conforming to IS:2645, brick bats is finally covered by jointless cement plaster 20mm th. in C.M. 1:4 added with special water proofing compound confirming to IS:2645 & top smooth finished with trowel with false chequered marking of 300 mm.size.The treatment is carried along the vertical surface of the parapet & other adjoining wall up to height of about 300 mm in a shape of quarter round vata Incl. curing etc. Comp. With average thickness of 120 mm and minimum thickness at khurra as 65 mm.				
	(c) The whole terrace so finished shall be flooded with water for a minimum period of two weeks for curing and for final test. All above operations to be down in order and as directed and specified by the engineer-in-charge. With average thickness of 120 mm and minimum thickness at khurra as 65 mm. (Cement consumption 0.511 Bags / S.M.)	0.00	511.000	S.M.	0.000
110	Proiding & laying water <b>proofing treatment to vertical</b> and horizontal surfaces like consisting of (a) I course of applying cement slurry 4.4 kg per sq.mt. mixed with water proofing compound confirming to IS:2645 in roommended proportions. (b) II corse of 20mm cement plaster 1:3 mixed with water proofing compound in recommended proportion (c) III course of applying blown or / resideal bitumen applied hot at 1.7 kg per sqm of area. (d) IV course of 400mm micron th. PVC sheet. (Overlaps at joints of PVC sheet should be 200mm wide and pasted to each other with bitumen about 1.7 kg./ sqm.)	0.00	505.00		0.00
111	Pro & Const. water Proofing Cement vata of 10 cm size in C.M 1:1				
112	etc complete.  Providing & fixing <b>G.I. Rain water spout</b> of 50 mm.dia & 30 cm length	0.00	23.68	R.M	0.00
	etc.	2.00	101.91	No.	203.82
113	Chemical treatment of DR.FIXIT brand for various required surfaces	0.00	232.92	S.M.	0.00
		TOTA	L AMOUI Below 3		293247.54 93839.2128

Below 32% 93839.2128
Total Amount 199408.33
SAY 199410.00

Signature of the Contractor:

Executive Engineer South West (Athwa) Zone Surat Municipal Corporation