

I/C Executive Engineer(Ele)
Heritage Cell



Surat Fort,
Heritage Cell,
Near Dakka ovara, Makkai Pull,
Chowk Bazar,
Surat-395003

Quotation

Fort/Out/No: 123.
Date: 18/07/2025

To,

.....
.....
.....
.....
.....

Sub: -"Quotations for shifting DG set along with all necessary items and equipments like connection - disconnection, cabling, crimping, terminations at Surat Fort, Chowk Bazar Surat."

You are requested to send your sealed quotation duly filled & super scribed as "Quotations for shifting DG set along with all necessary items and equipments like connection - disconnection, cabling, crimping, terminations at Surat Fort, Chowk Bazar Surat" & should reach at the office of "I/c Executive Engineer(Ele), C/O Fort, Opp. Andrews Library, Chowk bazaar, Surat-395003" on or before Dt. 29/07/2025 up to 05.00 pm.

Sr. No	Item Description	Qty	Per	Rate	Total Amount (in Rs.)
1	Shifting of 62.5 KVA DG set from Terrace to G.F. beside main HT substation area.	1	Job		
2	Disconnection and Reconnection of all Power cable and Control cable of 62.5 KVA DG Set.	1	Job		
3	Supply & Laying of 25x3 mm G.I Strip for Earth Connectivity.	20	Mtr.		
4	Supply & Laying of 25x3 mm Copper Strip for Earth Connectivity	20	Mtr.		
5	Supply, Laying and Termination of single core 16 sq.mm Copper cable for connectivity.	20	Mtr.		

6	Supplying & erecting in earth pit of minimum bore dia. 225mm size approved make Safe Earthing Electrode consisting Pipe-in-Pipe Technology as per IS 3043-1987 made of corrosion free hot dipped G.I. Pipes having Outer pipe dia of 80 mm having 80-200 Micron galvanizing, Inner pipe dia of 40 mm having 200-250 Micron galvanizing, connection terminal dia of 14 mm with constant ohmic value. For, Electrical installation up to 11 KV located in other than normal soil i.e. Soft Rock, Marshy Soil etc. -Length of Pipe : 2 mtr. -Back filling Compound : 1 no. Bag of 25 Kg.	4	Nos.		
7	Top up of Coolant Water in above mentioned 62.5 KVA DG Set.	1	Job		
8	Supply and installation new Energy meter with necessary lab testing.	1	Job		
9	Consulting Charges and DG passing processing fees in office of electrical inspector.	1	Job		
	Grand Total				

Condition of work :-

1. It is presumed that the offer is given after site inspection and keeping in view the scope of work. Site visit should be done and necessary technical specification/information should be collected before quoting the rates. No dispute at later date shall be entertained.
2. Quotation once offered shall not be withdrawn, except with the permission of the competent authority.
3. Quotation once accepted shall be binding to the contractor.
4. Rate must be filled in this quotation paper only and returned duly sealed & signed otherwise offer will be rejected. No escalation in price during the contract period shall be allowed.
5. The bidder must attach GST registration certificate, PAN Card etc. The contractor shall have an active experience in DG Set Erection and Maintenance in any government organization. He must submit necessary evidence viz. work order/work completion certificate etc. for the same.
6. The rates for shifting DG set along with all necessary items and equipments like connection - disconnection, cabling, crimping, terminations at Surat Fort & inclusive of all duties, GST & any other govt. levies if any.

7. SMC will not pay any transportation charges & all accessories/spares required for Shifting of above mentioned listed in annexure A are in contractor's scope.
8. Successful Contractor shall be required to deposit an amount equal to 2% of total order value as Security Deposit in Cash/ by Demand Draft within 10 (Ten) days from date of work order, otherwise penalty @ 0.065% of the Security deposit Amount per day of delay shall be charged.
9. Successful bidder have to entering into contract agreement and furnishing undertaking to SMC supported by surety from local reputed contractor to be given on suitable Indian Non Judicial stamp paper worth Rs. 300 each purchased from Surat. However, the stamp duty at prevailing rate shall be applicable if revised by Government.
10. The decision of Dy. Commissioner shree shall be final in respect of disputes what so ever arise. Corporation reserve the right to accept or reject any or all the quotation without assigning any reason therefore.
11. SMC may terminate the contract at any point of time during contract period if it is not required.
12. In case of work is delayed, then penalty will be recovered at 0.2% of quoted rate per day of delay on particular job cost that will be maximum up to 10% of that job amount.
13. The offer shall remain valid up to 120 days from the date of receipt of the quotation.
14. The name of work i.e."Quotation for the work of..... "must be mentioned on the envelope without which quotation is likely to be rejected, which must be noted.
15. Any dispute will be subject to the court, falling under Surat jurisdiction.
16. Spare parts are used shall be genuine and of good quality. No second-hand/duplicate material will be tolerated.
17. Contractor shall be responsible to the accident/injury/Loss to any of the staff members of them. No compensation of any kind shall be paid by the corporation. The contractor shall observe latest Government rules regarding labour etc.
18. Payment will be released only after completion of work.

Seal & Signature of Contractor

S/D
I/c Executive Engineer(Ele)
Heritage Cell
Surat Municipal Corporation