# Executive Engineer South Zone-A(Udhana)



## Surat Municipal Corporation South Zone-A(Udhana) Opp. Satyanagar, Udhana, Surat.

**2**2770434 2278429.

#### **QUOTATION INQUIRY**

	SZ-A/Tech./No.4225
To,	Dtd.: 28/07/2025
,	
,	

Sub: - Supply, Installation, Testing and Commissioning of various capacities of Split type Air Conditioner Machine with Buyback offer of old AC Machine For Smart City Office at Admin building of South Zone-A(Udhna).

Dear Sir,

Sealed quotations duly super scribed the Subject Name and returnable on or before date 04/08/2025 to the office of the undersigned is invited following Work: -

### Quotation

	<u> </u>	uvia	шип				
Sr. No.	Description	Qty	Unit	Offered Make	Price per Unit (Without GST)	Total Amount (Without GST)	
SOR 2023- 24 8-3-1.	Providing and erecting approved make split air-conditioning unit consisting of copper condensing unit with fan motor, hermetically sealed rotary compressor with accessories etc. duly connected separately erected evaporating unit and blower motor with its accessories by means of extra supplied proper insulated copper tubing, drain PVC pipes suitable for (cost includes powder coated Stand, Eco Friendly green gas charging, 15Aplug top& Remote Control) with necessary core cutting.[a] For 1 Ton Capacity	2	Ea.				
	" As above " (b) for 1.5 ton capacity	1	Ea.				
8-3-5.	Supplying and erecting insulated pair of soft copper tubing open or concealed including power and control cable, necessary PVC drain pipes for Split AC machine up to 4 TR capacity (Extra Copper Piping)	90	Rmt				
8-8-4.	Rigid UPVC drain pipe of 10 Kg/cm2. rating with 9 mm thick. nitrile rubber insulation. (D) 25 mm dia. (Extra Drain pipe)		Rmt				
Total Amount for SITC (Without GST)							
Total Amount for SITC in Figures:							

Sr. No.	Description	Qty.	Unit	Buyback Offer	Total Amount
1	1 TR Split Air Conditioner Machine including Outdoor Unit, Stand & Copper Piping	2	No.		
2	1.5 TR Split Air Conditioner Machine including Outdoor Unit, Stand & Copper Piping	1	No.		

Note:- Applicable GST + TCS on Buyback shall be paid extra by Contractor/Agency

**☐** Technical Specification **☐** 

Tonnage	1.0 TR	1.5 TR	
Cooling Capacity (Watt) (Min~Max)	3517	5130	
No. of Compressor	as per Company Model	as per Company Model	
Compressor Type	Tropical Rotary/Rotary	Tropical Rotary/Rotary	
Rated Cooling Capacity (BTU/Hr)	12000	17500	
Refrigerant	Latest	Latest	
Power Supply	230V, 50Hz, Single Phase	230V, 50Hz, Single Phase	
Remote Control	Yes	Yes	
Cooling coil Condenser	Copper	Copper	
Mounting Type	Wall Mounted	Wall Mounted	
Make	O General, Daikin, Mitsubishi Heavy duty, Toshiba, Hitachi, Bluestar	O General, Daikin, Mitsubishi Heavy duty, Toshiba, Hitachi, Bluestar	

- Bidder must offer 1 year manufacturer warranty for the supplied items.
- Contractor has to get approval of the make/ material out of list mention above before supply.

#### Other Terms & Condition

- The Rates mentioned in BOQ are excluding GST & Including of other taxes/duties/loading-unloading/Labour including Transporting. GST will be reimbursed separately (if applicable as per the opinion of Account department of SMC / GST Consultant of SMC) as per the prevailing GST Rates decided by the Government. The contractor is invariably bound to any changes in GST Rates made during the course of the work. The payment (if applicable) for GST will be only released only after the applicable Amount reflects on Government portal. Decision of Account Department of SMC regarding applicable GST Rates will be final.
- Validation of Quotation will be 120 days from the last date of submission of Quotation.

- Bidders are suggested to visit the site location before quoting this quotation and for any further query, bidder can contact Light department of South Zone, SMC.
- Work Completion period will be 15 Days from the date of work order. If contractor fails to complete above work than penalty @ 0.2% of amount unexecuted work per day delayed should be recovered from your bill. Maximum delay penalty shall be recovered 10% of unexecuted amount of work order.
- Contractor will have to submit Security deposit at the rate of 2 % of work order value within 10 days from the date of work order otherwise; penalty @ 0.065% of the amount of security deposit per day of delay shall be levied.
- Successful Contractor have to do Agreement, Surety & Undertaking on the non judicial stamp paper of Rs.300/- each purchased from Surat city only.
- Any "price variation clause" shall not be accepted.
- It is to be clearly noted that advance planning must be done with the department before installation work.
- Miscellaneous items to complete the installation in all respect & as described in specification.
- All required materials, tools, tackles and men power for the job shall be brought by the Contractor.
- Contractor shall be responsible to the accident/injury/Loss to any of the staff members of them. He shall follow all the applicable rules & regulations as per Government norms for the Same.
- It shall contractor responsibility to get acquainted type of acts rules, regulations, and general rules, Procedure of corporation.
- Payment shall be made after satisfactory Completion of whole SETC work in all respect and submission of required documents and invoices of the work.
- All The Central, State and Local government rules and regulations including Safety shall be strictly followed by the Contractor.
- The name of work i.e." **Quotation for the work of ......**" must be mentioned on the envelope.

Thanking You,

-Sd-Executive Engineer, South Zone-A(udhna) Surat Municipal Corporation.

\*SIGNATURE & SEAL OF CONTRACTOR\*