



નં. ઈએડ-બી/ ૬૧૩૧
તા. ૧૫/ ૧૧/૨૦૨૫

પ્રતિ,

.....
.....
.....
.....
.....
.....


વિષય :- નવો પૂર્વ (સરથાણા) ઝોન વિસ્તારમાં સમાવિષ્ટ ભરથાણા, ઉમરા અને ગોથાણ (રેલ્વે લાઈન સુધી) ગામતળમાં આવેલ સોસાયટીઓમાં ડ્રેનેજનાં મશીનહોલમાં ઉર્તાયા વગર પાવડીથી ડીસીલ્ટીંગ કરવાનું કામ.

સંદર્ભ :- ગટર સમિતિનો ઠરાવ નં. ૩/૨૦૨૪, તા. ૧૬/૦૧/૨૦૨૪ ભાવો, શરતો અને સ્પેસીફિકેશન મુજબ.

મહાશય,

ઉપરોક્ત વિષય તેમજ અનુસંધાનની વિગતથી મંજૂર ભાવો, શરતો અને સ્પેસીફિકેશન આધિન અંદાજીત રકમ રૂ. ૪,૯૯,૪૦૪.૦૦ પૈ. થી ૨૭.૦૦% નીચા ભાવે એટલે કે રૂ. ૩,૬૪,૫૬૪.૯૨ પૈ. નું કામે ભરવા પાત્ર બાનાની રકમ રૂ. ૩૬૪૬.૦૦ પૈ. (ત્રણ હજાર છેતાલીસ રૂપીયા) સાથેનું તમારું સંમતિપત્ર તા. ૧૧/૧૧/૨૦૨૫ સાંજે ૬:૦૦ કલાક સુધીમાં નીચે સહિ કરનારને પહોંચતું કરવા ઘટતું કરશો. કામ તથા ભાવો અંગેની વિસ્તૃત સમજ માટે સંબંધિત જુની. ઈજનેરશ્રીનો સંપર્ક કરવો.

ઉપર જણાવેલ કામ અંગે ઈજારદારોએ બાનાની રકમ, જી.એસ.ટી નંબર, રજીસ્ટ્રેશનની પ્રમાણીત નકલ આપવાની રહેશે. રજીસ્ટ્રેશનની પ્રમાણીત નકલ, જી.એસ.ટી નંબર વિના આવેલ સંમતિપત્રકો માન્ય રાખવામાં આવશે નહીં.


કાર્યપાલક ઈજનેર,
નવો પૂર્વ (સરથાણા) ઝોન,
સુરત મહાનગરપાલિકા.

SURAT MUNICIPAL CORPORATION**NEW EAST(SARTHANA) ZONE**

NAME OF WORK:- DESILTING AND CLEANING OF SEWER DRAINAGE MACHINEHOLE OF EXISTING DRAINAGE LINE IN DIFFERENT SOCIETY BHARTHANA, UMRA AND GOTHAN(REST PART OF RAILWAYLINE) VILLAGE IN NEW EAST(SARTHANA) ZONE, SURAT

SR. NO.	ITEMS	QTY.	RATE Rs.	PER	AMOUNT
					Rs.
1	Desilting of garbage, rubbish, clay, silt, grit, industrial waste and any kind of waste from wet sump, screen chamber, inlet chamber etc of drainage pumping stations/ sewage treatment plants of any size and shape up to 3.00 mt. depth from G.L.by any means in dry or wet conditions in different areas of surat city as directed by the Engineer in charge including stacking and disposing of the desilted materials and other waste materials brought from silt chamber wet sumps, screen chamber etc. as per instruction and strictly directed by the Engineer in charge including dewatering required if any and taking all necessary precautions and safely measures against accident hazards such as test for gases, safety belt, breathing apparatus with air cylinder / blow man's breathing apparatus with blower , dry cells, torches generating set for lighting in side the areas etc. complete as directed during day.	1548.00	298.00	CM	461304.00
1 b	Desilting of garbage, rubbish, clay, silt, grit, industrial waste and any kind of waste from wet sump, screen chamber, inlet chamber etc of drainage pumping stations/ sewage treatment plants of any size and shape 3.10 MT. to 6.00 mt. depth from G.L. by any means in dry or wet conditions in different areas of surat city as directed by the Engineer in charge including stacking and disposing of the desilted materials and other waste materials brought from silt chamber wet sumps, screen chamber etc. as per instruction and strictly directed by the Engineer in charge including dewatering required if any and taking all necessary precautions and safely measures against accident hazards such as test for gases, safety belt, breathing apparatus with air cylinder / blow man's breathing apparatus with blower , dry cells, torches generating set for lighting in side the areas etc. complete as directed during day.	100.00	381.00	CM	38100.00
1 c	Desilting of garbage, rubbish, clay, silt, grit, industrial waste and any kind of waste from wet sump, screen chamber, inlet chamber etc of drainage pumping stations/ sewage treatment plants of any size and shape 6.10 MT. and more depth from G.L by any means in dry or wet conditions in different areas of surat city as directed by the Engineer in charge including stacking and disposing of the desilted materials and other waste materials brought from silt chamber wet sumps, screen chamber etc. as per instruction and strictly directed by the Engineer in charge including dewatering required if any and taking all necessary precautions and safely measures against accident hazards such as test for gases, safety belt, breathing apparatus with air cylinder / blow man's breathing apparatus with blower , dry cells, torches generating set for lighting in side the areas etc. complete as directed during day.	0.00	452.00	CM	0.00
TOTAL AMOUNT				RS.	499404.00

Junior Engineer
New East (Sarthana) Zone
Surat Municipal Corporation

Deputy Engineer
New East (Sarthana) Zone
Surat Municipal Corporation

Executive Engineer
New East (Sarthana) Zone
Surat Municipal Corporation

સુરત મહાનગરપાલિકાની ગટર સમિતિની તા.૧૬-૧-૨૦૨૪ ના

રોજ મળેલ સભામાં નીચે મુજબનો ઠરાવ પસાર થયો હતો :-

મ્યુ.કમિશનરશ્રીના તા.૨૨-૧૨-૨૦૨૩ ના પત્ર નં.સીમીસ/૩/૧૭૧ થી વિદિત થઈ,
સાઉથ ઈસ્ટ ઝોન, સબઝોન-૨ (બી) (પરવત-ગોડાદરા) માં ઉપાત ડ્રેનેજ લાઈનના મશીનહોલ
ડીસીલ્ડીંગ કરવાના કામે ટેન્ડર નોટીસ પ્રસિધ્ધ કરી માંગવામાં આવેલ ટેન્ડરોના સંદર્ભમાં નિયત
સમયમર્યાદામાં આવેલ અને ક્વોલીફાય થયેલ કુલ-૨ ટેન્ડરો પૈકી નીચા ભાવ ભરનાર ટેન્ડરના
ટેન્ડર-વિરેન્દ્ર એમ. શાહજી ટેન્ડરની અંદાજી રકમ રૂ.૨૧,૪૫,૬૦૦/- થી ૨૭% નીચું એટલે કે
રૂ.૧૫,૬૬,૨૮૮/- નું બિનશરતી ટેન્ડર વ્યાજબી જણાતુ હોય કબુલ રાખવાનું તથા તેઓ સાથે
કારનામું કરવા મ્યુ.કમિશનરશ્રીને અધિકૃત કરવાનું ઠરાવવામાં આવે છે.

ઠરાવ નં.૩/૨૦૨૪ સર્વાનુમતે મંજુર

સ.ર.મ્યુ.કમિશનરશ્રી પ્રતિ,

Received On

૨૫/૧/૨૪

DMC

૩૧-૧-૨૪

સીમીસ ૩ ૧૮/૧૦૫
૨૫/૧/૨૦૨૪

૨૧.૨.૫૨૬
ઈ.ચા.મ્યુ.સેક્રેટરી,
સુરત મહાનગરપાલિકા,
તા.૨૨-૧-૨૦૨૪.

A. K. DESAI

(RAC) WIOS

Ex Engg (SE2)

૨૫/૧/૨૪

આર.ઓ.સી. ૧/૬/૮
૧૯૬-૫
તા. ૨૫/૦૧/૨૪

સુરત મહાનગરપાલિકા
સી.ઈ.ઓ. (પાલિકા)
૨૫/૧/૨૪

A.E. S.
Karm Nid
૨૫/૧/૨૪

UE (M/O) (M/O) ૨૫/૧/૨૪/૨૦/ડી. ૬૦૦

Exe. Engg
૨૫/૧/૨૪

SOUTH EAST ZONE (LIMBAYAT)

OF WORK:- DESILTING AND CLEANING OF SEWER DRAINAGE MACHINEHOLE OF EXISTING DRAINAGE LINE
FERENT AREA OF SUB ZONE -2B (PARVAT-GODADARA) IN SOUTH EAST ZONE (LIMBAYAT), SURAT

ITEMS	QTY.	RATE Rs.	PER	AMOUNT Rs.
Desilting of garbage, rubbish, clay, silt, grit, industrial waste and any kind of waste from wet sump, screen chamber, inlet chamber etc of drainage pumping stations/ sewage treatment plants of any size and shape up to 3.00 mt. depth from G.L. by any means in dry or wet conditions in different areas of surat city as directed by the Engineer in charge including stacking and disposing of the desilted materials and other waste materials brought from silt chamber wet sumps, screen chamber etc. as per instruction and strictly directed by the Engineer in charge including dewatering required if any and taking all necessary precautions and safely measures against accident hazards such as test for gases, safety belt, breathing apparatus with air cylinder / blow man's breathing apparatus with blower , dry cells, torches generating set for lighting in side the areas etc. complete as directed during day.	7200.00	298.00	CM	2145600.00
Desilting of garbage, rubbish, clay, silt, grit, industrial waste and any kind of waste from wet sump, screen chamber, inlet chamber etc of drainage pumping stations/ sewage treatment plants of any size and shape 3.10 MT. to 6.00 mt. depth from G.L. by any means in dry or wet conditions in different areas of surat city as directed by the Engineer in charge including stacking and disposing of the desilted materials and other waste materials brought from silt chamber wet sumps, screen chamber etc. as per instruction and strictly directed by the Engineer in charge including dewatering required if any and taking all necessary precautions and safely measures against accident hazards such as test for gases, safety belt, breathing apparatus with air cylinder / blow man's breathing apparatus with blower , dry cells, torches generating set for lighting in side the areas etc. complete as directed during day.	0.00	381.00	CM	0.00
Desilting of garbage, rubbish, clay, silt, grit, industrial waste and any kind of waste from wet sump, screen chamber, inlet chamber etc of drainage pumping stations/ sewage treatment plants of any size and shape 6.10 MT. and more depth from G.L. by any means in dry or wet conditions in different areas of surat city as directed by the Engineer in charge including stacking and disposing of the desilted materials and other waste materials brought from silt chamber wet sumps, screen chamber etc. as per instruction and strictly directed by the Engineer in charge including dewatering required if any and taking all necessary precautions and safely measures against accident hazards such as test for gases, safety belt, breathing apparatus with air cylinder / blow man's breathing apparatus with blower , dry cells, torches generating set for lighting in side the areas etc. complete as directed during day.	0.00	452.00	CM	0.00
TOTAL AMOUNT			RS.	2145600.00

Executive Engineer
South East Zone (Limbayat)
Surat Municipal Corporation