

Executive Engineer
Public Infrastructure Cell



Surat Municipal Corporation,

School No.16, Near Soham Circle,
Althan Canal Road, Althan, Surat

P.I.Cell/Outward/No.1560
Date:28/01/2026

To,

Sub :- Supply, Installation, Testing and Commissioning of Stainless-Steel Equipment for Existing Central Hospital Kitchen on Ground Floor of G Block @ SMIMER Hospital Campus, Umarwada, Surat.

Quotation letter duly super scribed and returnable on or before **Dt.06/02/2026** up to 17.00 hrs.to the office of “Chief Accountant, Surat Municipal Corporation, Muglisara, Surat” in person or by Speed Post is invited to carry out the following.

Quotation Letter

Sr. No.	ITEM	Quantity	Unit	Rate Rs. Ps.	Amount Rs. Ps.
1	Supply, Installation, Testing & Commissioning of custom fabricated Stainless Steel CHAPATTI PLATE PUFFER WITH 1U/S of size 1220 mm X 686 mmX (850+150) mm having 1 Under shelve, Mild steel chapati plate of size 900 mm x 700 mm x 25 mm and Cast-iron puffer plate of size 300 mm X 700 mm 40mm. It shall have 2nos.V-burners (V-750 mm & V600mm long with pilot) compatible with PNG gas, 1 no under self ,Legs and frame work etc complete as per detail specificationsIt shall be provided complete with gas connection and all accessories.	1	SET		
2	Supplying and placing of custom fabricated stainless steel CHAPATTI COLLECTIONTABLE WIH 2 U/S of size 1220 mm X 686 mm X (850+150) mm with splash back,having 2 no under-Shelves, leg sand frame work etc complete as per the detail specifications.	1	SET		
3	Supply, Installation, Testing & Commissioning of custom fabricated stainless steel SINGLE BURNER GAS RANGE of size 764 mm X 764 mm X 550 mm with High pressure multi ring burner compatible with PNG gas, gas inlet on both rear sides,drip tray, legs and frame	3	SET		

	work etc complete as peras per detail specifications. It shall be provided complete with gas connection and all accessories.				
4	Supplying and placing of custom fabricated Stainless Steel Masala Trolley of size 500 mm X 800 mm X 850 mm with 9 nos.GN pans, 1no undershelf, castors with brakes- rubber bumpers and frame work etc complete as per detail specifications.	2	SET		
5	Supplying and placing of custom fabricated stainless steel SERVICE TABLE WIH 2 U/S & 2 OHS of size 1830 mm X 762 mm X (850+150)mm with splash back,having 2no under-Shelves, leg sand frame work etc complete as per detail specifications.	4	SET		
6	Supply, Installation, Testing & Commissioning of custom fabricated stainless steel WORK TABLE WITH SINK of size 1220 mm X 762 mm X (850+150) mm with splash back having sink of size 450 mm X450 mm X 300 mm deep, strainer basket, cross bracing, legs, frame works etc. complete as per detail specifications.	2	SET		
7	Supplying and placing of custom fabricated stainless steel GN PAN TROLLEY of size 570 mm X 790 mm X 1800 mm with 20 pair of angles which are at 75 mm clear distance from each other to hold 2 no.1/1 gn pans, castors with brakes etc complete as per detail specifications. The food distribution trolley should be of proper design and equipped with electric supply to maintain food temperature during bed-to-bed distribution packed meals to patients. a separate trolley should be used for the distribution of liquid diets.	5	SET		
8	Supplying and placing of custom fabricated POT RACK FOUR SHELVES of size 1200 mm X 600 mm X 1650 mm having four shelves made up of SS304 grade material with round pipes for intercross, supports and up right etc complete as per detail specifications.	5	SET		
9	Supplying and placing of custom fabricated Stainless Steel STORAGE RACK FIVE SHELVES of size1200 mm X 600 mm X 1800 mm with 5 no shelves of 18 SWG sheet equidistant fromeach other,uprightswith adjustable nylon bullet feetetccompleteasas per detail specifications.3	5	SET		

10	Supplying and placing of custom fabricated DUNNAGE RACK of size 900 mm X 600 mm X 300 mm with 14 SWG stainless steel cornerpieces (150mmX150mm) and 25mm X 25mm SS square pipes at 75 mm distance from each other, legs with nylon bullet feet etc as per detail specifications.	5	SET		
Total Amount (Incl.GST)					

I/We do hereby give quotation to execute above mentioned work in accordance with the accompanying specifications and conditions in considerations.

TERMS AND CONDITIONS:-

1. Bidder having experience of similar works is eligible to bid the quotation.
2. Technical Specifications for Quotation Items:

Item no. 1 :- Chapatti Plate cum puffer

Size- 1220 X 686 X (850 + 150)

Top : 14 Swg Stainless Steel With Splash Back. Chappati Plate : Of Size 900x700x25mm Thick Mild Steel.

Puffer Plate : 300x700x40mm Thick Cast Iron.

Front Panel : 18 Swg Stainless Steel With Ignition Window.

Grease Collecting Drawer : 18 Swg Ss (Removable).

Sides & Rear : 18 Swg Stainless Steel. Burners : 2 Nos., V- Burners, V-750 Mm Long With Pilots. 1 No. V- Burners, V-600 Mm Long With Pilots.

Under Shelf : Ø25mm Pipe @75mm Ctc Legs : 30x30mm Ss Square Pipes With Adj. Nylon Bullet Feet.

Frame Work : 35x35x3mm Thick Stainless Steel Angle

Item No. 2 :-Chapatti Collection Table

Size- 1220 X 686 X (850 + 150)

Top : 14 Swg Stainless Steel Top With Splash Back.

Undershelves : 2 Nos 16 Swg Stainless Steel All Sides Beeded Twice Downwards.

Legs : 30x30mm Ss Square Pipes With Adj. Nylon Bullet Feet.

Frame Work : 35x35x3mm Thick Stainless Steel Angle

Item No. 3 :- Single Burner Gas Range

Size- 764 X 764 X 550

Top : 14 Swg Stainless Steel With Cut Out To House Burner,

Vessel Rest Of Size : 500x500mm.

Burner : High Pressure Multi Ring Burner(Three Ring) With Individual Control & Pilot & Gas Inlet At Rear Both Sides.

Sides And Rear : 18 Swg Stainless Steel.

Drip Tray : 16 Swg S.S. With Integrated Handle.

Legs : 30x30mm Ss Square Pipes With Adj. Nylon Bullet Feet.

Frame Work : 35x35x3mm Thick Stainless Steel Angle.

Item No. 4 :- Masala Trolley

Size- 500 X 800 X 850

Top : 14 Swg Stainless Steel With Cutout To Hold, 9 Nos, 1/6 Size X 150mm Deep Gn Pans.

*** Unit To Be Supplied With 9 Nos. 1/6th Gn Pans.**

Under Shelf : 16 Swg Stainless Steel. Castors : 4 Nos. Dia 100mm Rubberised Swivel Castors With 2 Nos. Breaks. With Rubber Bumpers At All 4 Corners.

Framework : 35x35x3mm Thick Stainless Steel

Item No. 5 :- Service Table Wih2 U/S & 2 OHS

Size- 1830 X 762 X (850 + 150)

Material: Food-Grade Stainless Steel (SS304 For High Corrosion Resistance For Standard Duty).

Under Shelves (U/S): 2 Stainless Steel Undershelves For Storage Of Utensils, Pots, And Food Items.

Overhead Shelves (OHS): 2Overhead Racks (Double Deck) Designed For Spices, Containers, And Plating Equipment.

Structure: Reinforced With Stainless Steel Pipes (Approx. 38mm Dia) And Angle Frames For Heavy-Duty Support.

Finish: Matt, Hairline, Or Polished Finish.

Features: Adjustable Bullet Feet For Uneven Flooring And Often Fully Welded For Durability.

Top Sheet Thickness: 16 Gauge (1.5 Mm - 1.6 Mm) Or 18 Gauge.

Frame: Square Or Round Pipe Frame (38mm/40mm).

Load Capacity: Up To 150 Kg On Top And 75 Kg Per Under Shelf.

Backsplash (4-Inch) To Prevent Spills, Drawers.

Item No. 6 :- Work Table With Sink

Size- 1220 X 762 X (850 + 150)

Top : 14 Swg Stainless Steel Sunk In Top With Splash Back.

Sink : Of Size 450x450x300mm Deep With Drain Coupling, & Single Swivel Faucet. Drain Towards Rear Side. Sink With Strainer Basket.

*** Unit To Be Supplied With Faucet.**

Strainer Basket : 18 Swg Stainless Steel Strainer Basket 40 Mm Deep. (Of 3mm Hole Ready Perforated Sheet Compatible ToThe Sink.)

Cross Bracing : 25x25mm, Stainless Steel Square Pipes.

Legs : 30x30mm Ss Square Pipes With Adj. Nylon Bullet Feet.

Framework : 35x35x3 Mm Thick Stainless Steel Angle.

Item No. 7 :- GN Pan Trolley

Size-570 X 790 X 1800

Angle : 35x35x14 Swg Ss 20 Pairs Of Angles Rear End Closed To Hold 2 Nos. 1#1 Gn Pans Each Angle @ 75 Mm Clear Distance From Each Other.

Wheel : Ø125mm , Plate Fitted Heavy Duty All Swivel - 2 With Brakes Castors Of 'Rexello' Or Equivalent Make With Weight Capacity Of 250 Kg Per Wheel. -With Rubber Bumpers At All 4 Corners

Item No. 8 :- Pot Rack

Size-1200 Mm X600 Mm X1650 Mm

Outer Frame Inner Cross : Dia 30 Mm 16 Swg Stainless Steel Round Pipes.

Supports : Dia 20 Mm 16 Swg Stainless Steel Round Pipe Inserted Into The Outer Frame Width Wise At 75mm Ctc.

Uprights : Dia 38 Mm Stainless Steel Round Pipe With Adjustable Nylon Bullet Feet..

Item No. 9 :- Storage Rack

Size- 1200 Mm X 600 Mm X1800 Mm

Shelves : 5 Nos. Of 18 Swg S.S. Sheet Equidistant From Each Other, Duly Strengthened With Stainless Steel Stiffeners From Beneath.

Uprights : 30x30mm Stainless Steel Square Pipes With Adjustable Nylon Bullet Feet

Item No. 10 :- Dunnage Rack

Size- 900 Mm X 600 Mm X 300 Mm

Corner Piece: 14 Swg Stainless Steel (150x150 Mm) Corner Pieces, For Additional Strengthening.

SSPipe : 25x25mm S.S. Square Pipes @ 75mm Clear Distance From Each Other.

Legs : 25x25mm Ss Square Pipes With Adj. Nylon Bullet Feet

3. The quotation complies in 1 cover.

Sealed Cover -Technical documents, experience Certificate of similar works, GST Registration Certificate and EMD of Rs. 5,000/- in the form of Crossed Demand Draft / Pay order/ Cheque of Local Nationalized Bank with duly sealed financial quotation letter.

Cover shall mention on top name of work, name of agency and duly sealed.

4. Bidder has to deposit EMD of Rs. 15,000/- in the form of Crossed Demand Draft / Pay order/ Cheque of Local Nationalized Bank, acceptable to Surat Municipal Corporation, drawn in favor of the Municipal Commissioner, SURAT MUNICIPAL CORPORATION payable which shall be refunded after sanction of work.
5. Quotation once offered shall not be withdrawn by Vendor.
6. Quotation once accepted shall be binding to the Vendor/Contractor.
7. The rates quoted must include all taxes, duties/ levies, GST (Goods and Service Taxes), freight, insurance, transportation, delivery and loading/unloading at the site etc. complete.
8. The decision of Deputy Municipal Commissioner, Public Infrastructure Cell, SMC shall be final in respect of disputes what so ever arise.
9. Right to accept any or to reject any or all the quotations without assigning any reason thereof is reserved by the competent authority of Surat Municipal Corporation, Surat.
10. The Intended Bidders has to contact Deputy Engineer/Asst. Engineer /Junior Engineer, Public Infrastructure Cell, SMIMER on working days between 9.00 AM to 12.30 PM at D-Block, SMIMER Hospital & visit the site and gather information before quoting rates.

11. Accordingly, Bidder have to quote and submit in the above said time limit.
12. All necessary safety measures and precautions (including those laid down in the various relevant Indian Standards) shall be taken to ensure the safety of men, materials and machinery on the works as also of the work itself.
13. The Vendor/Agency's rate of the item of work shall be for the work completed in all respects.
14. Approval of the samples of various materials given by the Engineer-in-charge shall not absolve the Vendor from the responsibility of replacing defective material brought on site or material used in the work found defective at a later date. The Vendor shall have no claim to any payment or compensation what-so-ever on account of any such materials being rejected by the Engineer-in-charge.
15. Conditional quotation letter shall not be accepted.
16. The contract shall be constituted according to and subject to laws in India and state of Gujarat and under the jurisdiction of Courts of Gujarat at Surat City only.
17. Bidder to whom the award is made shall furnish a performance guarantee (Initial Security Deposit) for amount equal to Two percent (2.00%) of the contract amount by a demand draft of a Scheduled Nationalized Bank acceptable to owner on the Surat Branch. Security Deposit shall be paid in time and if it is paid after Ten (10) days from the date of work order, then the penalty of 0.065 % per day of the amount of Security Deposit shall be recovered from the contractor. The performance guarantee (Security Deposit) will be returned to the contractor after the defect liability period (one year after completion of work) and on completion of audit related procedure.
18. Time limit of the work is 02 (Two) months. If the bidder fails to complete the work within the stipulated completion date for the work, he shall pay liquidated damages 0.20% of contract value per day in completion or part thereof as the case may however be, Subjected to a maximum of 10% (Ten Percent) of the contract value.

--sd--
Executive Engineer
Public Infrastructure Cell
Surat Municipal Corporation

Seal & Signature of the Contractor

Name :-

GST No. :-

Address :-

Date :-

Copy to: Chief Accountant Shri,

Surat Municipal Corporation,

Muglisara, Surat... for necessary action