

સુરત મહાનગરપાલિકા

ટ્રાફિક - બી.આર.ટી.એસ.
પ્રોજેક્ટ સેલ



ગ્રાઉન્ડ ફ્લોર, અલધાણ સ્વીમીંગપુલ,
ડી.આર.બી. કોલેજની સામે,
ન્યુ સીટી લાઈટ રોડ, સુરત-૩૯૫૦૧૭
મો.નં. : ૭૦૧૬૫૫૫૭૮૪

E-mail: exen.traffic@suratmunicipal.org

—:સંમતિ પત્રક:—

પ્રતિ,

.....
.....
.....
.....

સ્થા.સ.ઠ.નં. ૨/૨૦૨૩, તા.૧૮/૦૧/૨૦૨૩

વિષય :- સુરત મહાનગરપાલિકા સંચાલિત સીટીલીકની જાહેર પરિવહન બસ સેવાનાં નવા/એક્સટેન્ડેર કરેલ સીટી બસ રૂટમાં મુસાફરોની સગવડતા હેતુસર માર્કર પોલની સુવિધા આપવા બાબત.

મહાશય,

ઉપરોક્ત વિષયના અનુસંધાને જણાવવાનું કે, સુરત મહાનગરપાલિકાનાં જુદા જુદા ઝોન વિસ્તારમાં નવા માર્કર પોલ લગાવવાના કામે સ્થા.સ.ઠ.નં. ૨/૨૦૨૩, તા.૧૮/૦૧/૨૦૨૩ થી મંજૂર થયેલ ઠરાવના ભાવે અને શરતોને આધીન ઠરાવવામાં આવેલ વિગતોએ રૂ.૫,૦૦,૦૦૦.૦૦ ની મર્યાદામાં આગામી ૦૬ (છ) માસ માટે કામગીરી કરવા જો આપશ્રી રસ ધરાવતા હોવ, તો આપશ્રીનું સંમતિપત્રક તા.૦૬/૦૩/૨૩ સુધીમાં નીચે સહી કરનારને ખુલ્લા કવરમાં ટ્રાફિક-બી.આર.ટી.એસ. પ્રોજેક્ટ સેલની કચેરીમાં મોકલવા ઘટતુ કરશો.

બિડાણ :- (૧) સ્થાયી સમિતિ ઠરાવ નં.૨/૨૦૨૩, તા.૧૮/૦૧/૨૦૨૩
(૨) શીડયુલ -બીની નકલ

કાર્યપાલક ઈજનેર
ટ્રાફિક સેલ
સુરત મહાનગરપાલિકા

ટ્રાફિક BRTS પ્રોજેક્ટ સેલ

રજીસ્ટ્રેશન નં. :- ૨૦૩૧

તારીખ :- ૨૬/૨/૨૬

Name of Work :- Providing & Fixing Marker pole including city bus route detail on marker pole/ bus stops at different location of city bus service in South East (Limbatat) Zone, Surat.

Abstract sheet

Item No.	Particulars	Qty.	RATE SOR (2021-22), Market Rs. Ps.	Unit	Amount Rs. Ps.
1	2	3	4	5	6
1	Demolition and disposal of unserviceable materials with all lead and lift				
	(i) Unreinforced cement concrete	1.00	406.17	C.M	406.17
	(ii) RCC work	1.00	705.23	C.M	705.23
2	Demolition of brick work and stone masonry including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift.				
	(i) in cement mortar	1.00	366.93	cumt	366.93
3	Excavation for foundation include. Sorting out & stacking of useful materials & disposing of the excavated stuff upto 50 mt. Lead & all lift, watering etc. Comp.(With Manual Labour)				
	(A) Loose or soft soil				
	(1) Up to 1.5 Mt. depth	14.00	150.24	C.M	2,103.36
4	Providing & laying cement concrete 1:1.5:3 (1 cement:1.5 sand:3 graded stone agg. 20 mm nominal size)& curing comp. Including cost of form work but excluding cost of reinforcement for reinforced concrete work in : (A) Foundation, footing, Base of columns and Mass concrete.				
	A) Foundation and plinth	14.00	4,127.14	C.M	57,779.96
5	Providing erecting and fixing in position structural steel sections of Yst 310 grade of TATA, Kamdhenu, Jindal or Asian confirming to IS:4923 purlins, roof trusses, columns, side runners, ties bracing, framing etc, including all types of base plate, gusset plate, cap plate, bearing plate, stiffner, cleats etc. complete and structural steel confirming to IS:226 including necessary pipes, rolled joists, channels, angles, tees, MS flats, angle cleats, gusset plate, bright bars, chequered plates, criss cross plates as per required thickness including cutting, welding, riveting as per structural details and good engineering practice grinding and cleaning the members as secified by Engineer in charge. (only finihed measurements will be paid for billing purpose). No extra payment shall be made for grouting that has to be done under the base plate to get full bearing on supporting sub statra. The paint shall be oil paint in three coats to get an even look over a coat of red lead paint as per the instruction of the engineer incharge. The rate shall also be inclusive of screw, bolts, nuts,washers, hindges, pivots.	1210.00	81.86	kg	99,050.60

Item No.	Particulars	Qty.	RATE SOR (2021-22), Market Rs. Ps.	Unit	Amount Rs. Ps.
6	Fabricating, supplying, cutting, bending and fixing GI plain sheet JINDAL/HINDALCO make or equivalent of 1mm /2mm/3mm thickness fixed to MS framing with S.S.screws in counter sunk/ S.S. rivets, S.S washers, necessary accessories and hardware complete as per detailed drawing and design. (Only finished measurements will be paid for, M.S. framing shall not be part of this item.) The sheet type will be finalised by the Engineer in charge.	14120.00	83.00	kg	11,71,960.00
7	Providing, Designing and Sticking Vinyl with eight color eco solvent epson printing. The Vinyl to be of 100 microns 3M media . The vinyl to be laminated by 80 microns film after the printing and before sticking. The sample of the same needs to be approved by the consultant. To be stuck in line and level without any crease or bubbles on the prelaminated board / acrylic sheet using 3M adhesives surface. The graphics shall be provided by the consultant. The contractor to check the graphic size and the available surface before printing. The 3M vinyl signage shall be stuck firmly on 3mm thick SS 304L grade sheet as per designs. The sheet shall be firmly fixed using SS 20mm dia studs as per the designs of the consultants fixed in correct line, level and plumb. The rates shall be excluding SS sheet but including signage material including fixing and other related costs like transportation, electricity etc.	410.00	920.00	SM	3,77,200.00
8	Providing, Designing and fixing of flex signage with printing for external use and with uniformity so that the same can be backlit. The flex is to be fixed neatly with adhesive to M.S. frame, stretched in line and level. The flex to be 15 ounce of LG Media for backlit and printed on vienteck machine. The graphic size is to be cross checked with the area available before printing. The graphic shall be prepared as per instruction of Engineer In-Charge.	4.00	700.00	SM	2,800.00
9	Eco Vinyl Remove from Existing Marker pole	750.00	11.20	Sq.Ft.	8,400.00
Total Rs.					17,20,772.25