

Surat Municipal Corporation

Praveen R. Prasad
I/c. Assistant Commissioner
& General Manage (O&A-SSL)



Surat Sitilink Ltd
Room no.95, 2nd floor
Shree Tapi Bhavan
Tapipura,
Surat-395003

Quotation for various items for Sliding doors and its system

Surat Sitilink Limited Invites Quotation for supply, installation, testing and commissioning (SITC) of various items of Sliding door and its system (including Removal of Existing damaged/non functional items) for Sliding doors of B.R.T.S Bus shelters at Surat Sitilink Limited for various BRT Corridor. Following are the details.

Attachment :- (1) Technical Specifications

(2) List of Bus shelters

Sr. No.	Item Description	Quantity (nos)	Rate (Per Unit – (Excluding GST, but including levies, transportation, labour etc) (Rs)
1	Supply, Installation, Testing and Commissioning (SITC) of Sliding door system of Dortex installed at above door (Material included: Micro Controller, Motor, Door power supply, Pulley, Hanger with wheels, door hardware, belt hardware, Reader power supply.	101	
2	Supply, Installation, Testing and Commissioning (SITC) of Individual Components for the Door tax Sliding door system .	Not Defined	
	1. Micro Controller		
	2. Motor		
	3. Door Power Supply		
	4. Pulley		
	5. Hanger With Wheels		
	6. Belt		
	7. Other Hardware(Include Reader Power Supply) (Rate to be filled as per Sr no)		
3	SITC of 4mm Thick Toughened Glass+1.5 mm PVB film (poly Vinyl Butyl film)+4mm thick toughened glass confirming to Relevant IS of exterior glass work. (As per designed and measurement of each corridor)	112	
4	SITC of Toughened Laminated Glass 4mm glass + 1.5mm PVB+4mm glass, EPDM Rubber, Glass Fitting with frame, Alu. Frame.	12	
5	Supply, Installation, Testing and Commissioning (SITC) of Controller for Sliding door system installed at various BRT bus shelter	88	
6	Supply, Installation, Testing and Commissioning (SITC) of GP 90 Rf Reader for Sliding door system installed at various BRT bus shelter	108	

7	Supply, Installation, Testing and Commissioning (SITC) of GP 90 Rf Reader' Acrylic Cover (IP 65) for Sliding door system installed at various BRT bus shelter	330	
8	Supply, Installation, Testing and Commissioning (SITC) of emergency switches for Sliding door system installed at various BRT bus shelter	288	
9	Track Cover to be used for Sliding door systems protection	44	
10	Bus arrival Indicator Yellow Blinker (as per present installation at bus shelters) 12 V DC	130	

Note:-

- Contractor has to visit the Site, check all conditions and take measurement of apparatus installed at bus shelters before filling Quotation invited for. No excuse will be accepted afterwards.
- Proposer must have experience of at least 07 years in SITC and/or O & M of Sliding doors in various projects. Proposer must have completed at least completed Maintenance/continue in maintenance of 300 nos sliding doors for Govt, Semi Govt, Municipal Corporation and/or its organization. Work order/Completion certificate to be attached as proof.
Work as sub subcontractor will not be considered for evaluation
- Scope of work includes Removal of Existing damage items from site, supply, installation, testing and commissioning (SITC) of items for Sliding doors of B.R.T.S Bus shelters as provided in detail specifications. Contractor has to quote per glass only for deciding L1 bidder and Surat Sitalink Limited will offer items as per damages occurs.
- The Quotation is to be sent in the name of I/c Assistant Commissioner & General Manager (O & A -SSL), Room no 95,96 Surat Sitalink Limited, Surat Municipal Corporation, Tapiपुरa, Surat -395003 in Sealed Envelope on or before 01/04/2026 17.00 Hrs via Speed post/RPAD or by hand only.
- The rate must include all cost i.e. Supply, installation, Testing & Commissioning of glasses in frame including all materials, transportation, labour etc but Excluding GST. Contractor has to submit Chartered Accountant (CA) Certificate for GST rate. No additional cost will be given for any material to be used for fixation of glasses.
- Contractor has to give doors in working conditions after fitting of glasses.
- No Advance Payment will be given. 95 % Payment will be given after successful Installation & Commissioning and remaining 5 % payment will be released after 06 months.**
- Time limit for commissioning of work within 45 (Forty five days) of work order/Part Work order given, beyond that penalty @Rs.250/- day will be charged for delaying.

