



**SURAT MUNICIPAL CORPORATION  
CENTRAL ZONE  
QUOTATION FORM  
TECHNICAL PART-1**

<b>QUOTATION No.CZ-Light-Q-01-2026-27</b>		DATE : 13/05/2026
<b>Name of work</b>	<b>Quotation for the Supply, Installation, testing &amp; commissioning of LT Power Cable at Main Office Building of Surat Municipal Corporation.</b>	
<b>Agency Category</b>	Experience, Electrical Licence Contractor	
<b>Required Documents</b>		
1. GST Registration		
<b>Issuing Authority</b>	Executive Engineer, Central Zone, Surat.	
<b>Issuing Office</b>	New Admin Building, Central Zone, Tapiपुरa, Surat - 395003	
<b>Inviting Authority</b>	Executive Engineer, Central Zone, Surat.	
<b>Submission Date</b>	TILL : 26/05/2026 UP TO 18:00 P.M.	
<b>Submitted To,</b>	EXECUTIVE ENGINEER, NEW ADMIN BUILDING, CENTRAL ZONE, TAPIPURA, SURAT - 395003	
<b><u>GST CLAUSE FOR CONSTRUCTION/ ERECTION/ COMMISSIONING/ INSTALLATION/ REPAIRS/ MAINTENANCE/ RENOVATION/ FABRICATION OF STRUCTURE INCLUDING BUILDING (MEANS ALL WORKS CONTRACT/ TURN KEY PROJECT/ SUPPLY OF MATERIAL/ GOODS)</u></b>		
<p>GST (Goods and service tax has come in existence from 1st July, 2017. Contractor/ Successful Bidder is bound to pay any amount of GST prescribed by the govt. of India as per the terms of contract agreed upon during the course of execution of this contract.</p> <p>During the course of execution of contract, if there is any change in rate if GST (Goods and Service Tax) by the Government, the same shall be reimbursed/ recovered separately by SMC. subject to the submission of original receipt/proof for the amounts actually remitted by the contractor/ successful Bidderer to the competent Authority along with a certificate from Chartered Accountant of contractor/ successful Bidderer certifying that the amount of GST paid to the government and the same shall be intimated/ submitted/ claimed within 30 (Thirty) days from the date of payment. Remittance of GST within stipulated period shall be the sole responsibility of the successful contractor/ Bidder, failing which SMC may recover the amount due, from any other payable dues with SMC and decision of Municipal Commissioner shall be final and binding on the contractor/ successful Bidder in this regard. Further, the non-payment of GST to the government may lead to the termination of contract.</p> <p>If imposition of any other new taxes/ Duties/ levies/ Cess or any other incidentals etc. or any increase in the existing taxes/ Duties/ Levies/ Cess or any other incidentals etc. (Excluding GST) are imposed during the course of the contract, the same shall be borne by the successful contractor/Biderer only; in no case SMC shall be liable for the same.</p>		
SIGNATURE OF ISSUING AUTHORITY		
<p>S/D EXECUTIVE ENGINEER CENTRAL ZONE SURAT MUNICIPAL CORPORATION</p>		

Executive Engineer Central Zone		Surat Municipal Corporation, Central Zone, New Administration Building, Tapipura, Surat - 395 003. Ph. No.: 0261-2432751-56.
------------------------------------	---	--

QUOTATION INQUIRY

CZ/Tech./No. : - 758

Dtd. - 13/05/2026

To,

.....  
.....  
.....  
.....  
.....

**Subject: - Quotation for the Supply, Installation, testing & commissioning of LT Power Cable at Main Office Building of Surat Municipal Corporation.**

Dear Sir,

Central Zone, Surat Municipal Corporation hereby inviting quotation for the Supply, Installation, testing & commissioning of LT Power Cable at Main Office Building of Surat Municipal Corporation.

Therefore, you are requested to submit your offer in given format to "Executive Engineer, Central Zone, Surat Municipal Corporation, Surat" in a sealed cover with mentioned subject & within last date of receiving. So as to reach in the office of under signed on or before Dtd. 26/05/2026.

**Notes:-**

1. Rates must be filled in this quotation paper only and returned duly sealed & signed.
2. The name of work i.e. "Quotation for the Supply, Installation, testing & commissioning of LT Power Cable at Main Office Building of Surat Municipal Corporation." must be mentioned on the envelope without which quotation is likely to be rejected, which must be noted.
3. Contractor must have to submit the Quotation with two separate covers. In Cover-I Technical parts of Quotation papers, EMD receipt, Experience documents, technical documents is to be attached and in Cover-II only Price Schedule is to be attached and also note that these both cover must be submitted in Cover-III which is to be mentioned the Name of Work on the Envelope.
4. While opening of quotation, Technical Bid shall be opened first, after evaluating technical bid document, Price bid of technically qualified contractor shall be opened only.

S/D  
Executive Engineer  
Central Zone  
Surat Municipal Corporation

**Encl.: - Terms & Condition & Price Schedule**

## **Detailed Scope of Work**

### **Item No.1 (A): LT Power cable (50 SQ MM)**

Supplying, laying, testing and commissioning of 1.1 kV, 3.5 core, 50 Sq.mm multistrand Aluminum conductor XLPE insulated armoured cable as per IS7098. Cable shall be laid on Surface wall between LT panels at New Annexy building to Commissioner Office main Panel. The item includes Clamping on wall and laid on cable tray etc, as per standard practices, breaking of wall and reinstate the same after completing the work is in scope of contractor. The cable length may vary depending on site condition and contractor should take actual measurement and supply the cable accordingly with prior approval. Cable shall be laid in single length. No straight joint shall be allowed under any circumstances.

### **Item No.1 (B): LT Power Cable (185 SQ MM)**

Supplying, laying, testing and commissioning of 1.1 kV, 3.5 core, 185 Sq.mm multistrand Aluminum conductor XLPE insulated armoured cable as per IS7098. Cable shall be laid underground & on Cable tray between LT main panels room central Zone to main panel room of New Annexy building. The item includes excavation and refilling using bricks/ Half round RCC, sand etc, as per standard practices, breaking of wall and restating the same after completing the work is also included. Please note that RCC Hume pipe already laid for road crossing. The cable length may vary depending on site condition and contractor should take actual measurement and supply the cable accordingly with prior approval. Cable shall be laid in single length. No straight joint shall be allowed under any circumstances.

### **Item No.2 & 3: Cable Glanding & Termination (LT cable (50 & 185 SQ MM))**

#### **Cable termination**

The item includes supply, installation, termination, testing and commissioning of cable termination. Termination includes double compression cable gland, lugs, tape, etc. All material and labour required for termination shall be in the scope of contractor.

#### **A. Termination**

Aluminium metal lugs shall be of suitable size according to Cable Size make conductivity grease to be used while using crimping type cable lugs. The cable lugs shall fit the conductor to which it shall be connected. The compression tool shall be used to assure proper crimping pressure on the lugs. Connections shall be made tight and insulated with PVC electrical tape of colour as per I.S.

Provide double compression type cable glands at each end of the cable. Glands should be of nickel-plated brass, with PVC shrouds over it. Before applying a PVC shroud, all bare metal shall be wrapped with pressure-sensitive adhesive PVC tape.

Cable termination shall include the following:

- a. Making necessary holes in the bottom/top plates for fixing cable gland/box.
- b. Fixing double compress cable gland/box, connecting armour clamp to cable armour.
- c. Dressing of cables wherever necessary to make termination complete.
- d. Putting cable lugs, crimping them on to cores of cables, taping bare conductors upto lugs, wherever necessary.
- e. Terminating to equipment terminals.

## **Terms and Conditions:-**

1. The rate should be inclusive of GST, all taxes, duties, labor charges, and transportation, loading unloading for the site basis.
2. EMD shall be submitted in form of Demand Draft / Pay order.
3. Bidder must offer 01 year manufacturer warranty from the date of Install.
4. Rates should be filled in this quotation paper only and returned duly sealed & signed.

5. The above work to be completed within 30 days from the date of work order / LOI otherwise penalty @ 0.2% of amount unexecuted work per day for delayed work should be recovered from your bill. The amount of maximum delay penalty shall be equal to 10% of unexecuted amount of work order.
6. No payment shall be made in advance. 100% payment shall be released after Supply Installation, testing & commissioning of Cable Laying work satisfactorily.
7. Payment shall be made as per prevailing practices/ processes/ circulars related to payments in SMC & actual work done at site.
8. The offer shall be submitted in a sealed cover to **“Executive Engineer, Central Zone, Surat Municipal Corporation, New Admin Building, Tapipura, Surat - 395 003”**.
9. SMC reserves its right to accept or reject any orall quotation without giving any reason.
10. Corporation will not issue any ‘C’ or ‘D’ form.
11. Successful contractor shall be required to deposit an amount equal to 2% of total order value as Security Deposit in Cash/ by Demand Draft/pay order within 10 (Ten) days from date of work order, otherwise penalty @ 0.065% of the Secuirity Deposit Amount per day of delay shall be charged.
12. Calculation of applicable GST, TDS deduction etc. shall be done as per prevailling GST act/rules/regulation.
13. **The name of work i.e. “Quotation for the Supply, Installation, testing & commissioning of LT Power Cable at Main Office Building of Surat Municipal Corporation.” must be mentioned on the envelope without which quotation is likely to be rejected, which must be noted.**

#### **Technical Bid & Price Bid:-**

1. Rates must be filled in this quotation paper only and returned duly sealed & signed.
2. The name of work i.e. **“Quotation for the Supply, Installation, testing & commissioning of LT Power Cable at Main Office Building of Surat Municipal Corporation.”** must be mentioned on the envelope without which quotation is likely to be rejected, which must be noted.
3. Contractor must have to submit the Quotation with two separate covers. In Cover-I Technical parts of Quotation papers, EMD receipt, GST Certificate, EC, RC, valid Electrical Contractor Licence Experience documents, technical documents is to be attached and in Cover-II only Price Schedule is to be attached and also note that these both cover must be submitted in Cover-III which is to be mentioned the Name of Work on the Envelope.
4. While opening of quotation, Technical Bid shall be opened first, after evaluating technical bid document, Price bid of technically qualified contractor shall be opened only.

#### **📄 Terms/Conditions of Quotation 📄**

*	All Taxes/ Duties, Transportation, GST, levies, duties, transportation and labour charges etc. :-	Included
*	Validity of Quotation :-	120 Days
*	Estimated Amount :-	Rs.2,22,500.00/-
*	EMD Amount: -	Rs.2,225/-
*	Payment condition: -	100% payment after completion of work and submission of invoice.
*	Note: -	The successful Contractor shall also be required to enter into contract agreement along with undertaking and local surety on Gujarat Stamp Paper purchased from Surat worth Rs. 300.00 for Each (To be brought by the contractor) on getting the order.

**Vendor's List:-**

ARMOURED POWER CABLES	UNISTAR, GLOSTER, CCI, INCAB, TORRENT, FINOLEX, HAVELLS, AVOCAB, KEI, RR KABEL
CABLE (LUGS & GLANDS)	DOWELLS, JENSON, HEX, 3D, HMI
Double walled corrugated pipes (DWC)	REX, GEMINI, DURALINE, SY-ARON (VARAHI POLYMERS)

S/D  
Executive Engineer  
Central Zone  
Surat Municipal Corporation

\* SIGNATURE & SEAL OF CONTRACTOR \*

**SURAT MUNICIPAL CORPORATION**  
**Central Zone**  
**Part-II**  
**PRICE SCHEDULE**

**Name of Work:** - Quotation for the Supply, Installation, testing & commissioning of Cable laying work at Main Office Building of Surat Municipal Corporation.

Sr. No.	Sor 2025-26 Item No.	Item Description	Unit	Qty.	Price per Unit (Incl. GST)	Total Amount (Incl. GST)
1.	4-3-3.	Supply, erecting, testing and commissioning of 1.1 kV grade, multistrand Aluminium conductor armoured cable as per (IS:7098) to be laid on wall, cable tray with necessary clamps or in existing trench / pipe of following size cables as per detailed specification.				
		(C) 3 1/2 core 50 Sq. mm	Mtr.	100	330.27	33027.00
		(H) 3 1/2 core 185 Sq. mm	Mtr.	160	1060.50	169680.00
2.	4-6-3.	Supply, erecting, testing and commissioning of cable termination as per detailed specification for following size of cable.				
		(B) 3 & 1/2 core 35/50 Sq. mm	Ea.	4	87.87	351.48
		(G) 3 & 1/2 core 185 Sq. mm	Ea.	4	279.77	1119.08
3.	4-7-1.	Solder less crimping type Aluminium lugs conforming to IS suitable for cable of following size evenly crimped with high pressure tool & connected to switchgear terminals with brass/cadmium plated nut bolts in an approved manner.				
		(D) 35/50 Sq.mm.	Ea.	20	20.20	404.00
		(I) 185 Sq.mm.	Ea.	16	93.93	1502.88
4.	4-5-1.	Making trench in soft soil of suitable width of 90 cm deep for laying cable or locating the fault all over the run and back filling the same and making the surface as normal ground.	Mtr.	25	54.54	1363.50
5.	4-5-2.	Making trench in Hard Murrum / Tar Road of suitable width of 90 cm or required depth for laying any size of cable or locating the fault all over the run and back filling the same and making the surface as normal ground.	Mtr.	25	72.72	1818.00
		(B) If additional machinery like hammer driller or JCB use [Add]	Mtr.	25	351.48	8787.00

Sr. No.	Sor 2025-26 Item No.	Item Description	Unit	Qty.	Price per Unit (Incl. GST)	Total Amount (Incl. GST)
6.	4-5-8.	Providing & laying approved make Double walled corrugated pipes (DWC) of polyethylene (conforming to IS 14930 II) with necessary connecting accessories of same material at required depth in existing trench for laying of cable. Below ground / road surface for enclosing cable				
		(D) 120 mm outer dia.	Mtr.	25	160.59	4014.75
<b>Total Amount with GST</b>						<b>222067.69</b>

I/We hereby tendered to execute the above mentioned description of work in accordance with the accompanying specification and conditions in consideration of payment being made for the quantity of work to be executed at PAR i.e. at the estimated rate/at \_\_\_\_\_ % (Percentage) in words \_\_\_\_\_ percentage BELOW/ABOVE the Amount shown in Price Schedule.

S/D  
Executive Engineer  
Central Zone  
Surat Municipal Corporation

\* SIGNATURE & SEAL OF CONTRACTOR \*