


**Surat Municipal Corporation  
New East (Sarhana) Zone  
Quotation Inquiry form**

QUOTATION NO. DC(D)/EZ-B/ /2026-27		DATE: / /2026
NAME OF WORK	Quotation for SETC of new ceiling fans, point wiring and replacing the down rod of the existing ceiling fans at Lata Mangeshkar Primary School-355, run by the Nagar Primary Education Committee, falling under New East (Sarhana) Zone.	
ESTIMATED AMOUNT:	EMD AMOUNT:	Rs.3500 /-
VALIDITY PERIOD :	120 Days	Agency Category : Supplier/Dealer/Distributor
REQUIRED DOCUMENTS	(1) Permanent Account Number (PAN) Copy (2) GST registration Certificate (3) Experience Certificate	
TENDER AVAILABILITY	120 Days	
ISSUING AUTHORITY	Executive Engineer, New East (Sarhana) Zone, Surat	
ISSUING OFFICE	Administrative office, New East (Sarhana) Zone, Beside Sankalp Residency, Behind Syamdham Mandir Char Rasta, Sarhana, Surat.	
INVITING AUTHORITY	Executive Engineer, New East (Sarhana) Zone, Surat	
SUBMISSION DATE	Last date: <u>25/05</u> /2026 Time : 06.00 P.M.	
SUBMITTED TO,	EXECUTIVE ENGINEER NEW EAST (SARTHANA) ZONE, Beside Sankalp Residency, Behind Syamdham Mandir Char Rasta, Sarhana, Surat.	
G.S.T. WILL BE APPLICABLE IN ACCORDANCE WITH THE PREVAILING NORMS OF GOVERNMENT.		
GST clause for construction/ erection/ commissioning/ installation/ pairs/maintenance/ renovation/ fabrication of structure including building (means all works contract/ turnkey project/supply of material/goods)		
<p>GST(Goods &amp; Service Tax) has come in existence from 1st July 2017 Contractor / Successful Bidder is bound to pay any amount of GST prescribed by the Govt. of India as per the Terms of Contract agreed upon during the course of execution of this Contract.</p> <p>During the course of execution of Contract if there is any change in Rate of GST (Goods &amp; Service Tax) by the Government the same shall be reimbursed / recovered separately by SMC, subject to the submission of Original Receipt / Proof for the amounts actually remitted by the Successful Tenderer / Contractor to the Competent Authority along with a Certificate from Chartered Accountant of Contractor / Successful Bidder certifying that the amount of GST paid to the Government and the same shall be intimated / submitted / claimed within 30(Thirty) Days from the date of payment Remittance of GST within stipulated period shall be the sole responsibility of the Successful Bidder / Contractor, failing which , SMC may recover the amount due, from any other payable dues with SMC and decision of Municipal Commissioner shall be final and binding on the Contractor/ Successful Bidder in this regard Further, the nonpayment of GST to the Government may lead to the termination of contract and forfeiture of Security Deposit / Performance Guarantee Amount.</p> <p>If imposition of any other new Taxes/Duties/Levies/Cess or any other incidentals etc. or any increase in the existing Taxes/Duties/Levies/Cess or any other incidentals etc. (Excluding GST) are imposed during the course of the contract. the same shall be borne by the Contractor/ Successful Bidder only, in no case SMC shall be liable for the same.</p>		
	SIGNATURE OF ISSUING AUTHORITY	
		
	Executive Engineer New East (Sarhana) Zone Surat Municipal Corporation	

નવો ઈસ્ટ ઝોન (બી) - ઈલેક્ટ્રીસિટી વિભાગ  
અધિક વડ નં. ૩૨  
તારીખ ૨૫/૦૫/૨૬



Executive Engineer

New East(Sarthana)Zone

Surat Municipal Corporation

New East (Sarthana) Zone, Beside Sankalp Residency, Behind Syamdham Mandir  
Char Rasta, Sarthana, Surat.

Ph. : 6359909506 - 6359909606

**QUOTATION INQUIRY**

To,

.....  
.....  
.....  
.....  
.....

નવો ઇસ્ટ ઝોન(બી)-ઇન્જનેરી વિભાગ  
આઉટ ઓફ ઓફિસ  
તારીખ ૨૫/૦૫/૨૦૨૬

**SUB :-** Quotation for SETC of new ceiling fans, point wiring and replacing the down rod of the existing ceiling fans at Lata Mangeshkar Primary School-355, run by the Nagar Primary Education Committee, falling under New East (Sarthana) Zone.

You are requested to send your offer in a sealed cover with **E.M.D of Rs. 3500/-** in the form of demand draft / banker's cheque in favour of the "Municipal Commissioner, Surat Municipal Corporation" payable at Surat. So as to reach in the office of Executive Engineer [New East(Sarthana)Zone] **on or before Dt. 25 / 05 /2026 up to 6.00 pm.** Please note that the sealed cover shall be super scribed with the name of work " SETC of new ceiling fans, point wiring and replacing the down rod of the existing ceiling fans at Lata Mangeshkar Primary School-355, run by the Nagar Primary Education Committee, falling under New East (Sarthana) Zone " The terms & conditions for this offer are as follow, failing which the quotation shall be rejected out rightly.

SR. NO.	ITEM DISCRIPTION	QTY	UNIT	RAT (WITHOUT GST)	AMOUNT (WITHOUT GST)
1	Point wiring for FAN with 2-1.5 sq.mm & earth wire of 1.5 sq.mm (Green) both are of .ISI marked 1.1 KV Grade FRLS PVC insulated multi strand copper wires up to 10 mtr length, in below type of pipe erected with 6A Modular type switch and hum free EME step type electronic fan regulator mounted and accessories with earth continuity of following type erected on PVC/Metallic/ Wooden box, single mounting base frame covered with textured/ metallic/white front plate modules erected on / in wall / ceiling as per pipe erected. with necessary ceiling rose / H.D.Connector as directed.				
	(a) with medium class Rigid PVC pipe and accessories erected flushed on wall/ceiling complete. Cat. III	80	Pt.		
	(f) with medium class Rigid PVC pipe and accessories erected concealed in wall/ceiling complete. Cat. III	0	Pt.		
2	Point wiring for on board Looped Plug with 6A Modular type switch & 5 pin socket erected on PVC / Metallic/Wooden box, single mounting base frame covered with textured / metallic/white front plate modules erected on / in wall / ceiling with following type accessories				
	Cat. III	10	Pt.		
3	Providing following type of Modular Type Accessories mounted with PVC / metallic/Wooden box, single mounting base frame covered with textured / metallic/white front plate , modules erected with necessary connections as per site situation directed by Engineer In charge.				
	(7) Blank Plate Single. Cat.III	20	Ea.		
4	Providing and erecting Mains with 1.1 KV grade FRLS				

	PVC insulated ISI marked stranded Copper conductor wire in following type of pipe to be erected concealed in /flushed on wall/ceiling, with 1.5 sq. mm copper conductor FRLS PVC insulated stranded wire of green colour for earth continuity of following size				
	(A) With medium class Rigid PVC pipe and accessories				
	(a) 2 wire 1.5 sq. mm	200	Mtr.		
	(b) 2 wire 2.5 sq. mm	200	Mtr.		
5	providing and erecting Miniature circuit breaker single pole 6A to 25A suitable to operate on 240 V A.C. system and having breaking capacity 10 KA to be erected in existing box. confirming to IS 8828/1996 with ISI Mark. Cat.III	10	Ea.		
6	Providing & erecting 240 V MCB double pole switch for motor & inductive load (C Curve) having 10 KA breaking capacity & confirms to IS : 8828 in existing box having following capacity				
	(A) 6 to 32 Amp. Cat.III	5	Ea.		
	(B) 40 Amp. Cat.III	0	Ea.		
7	Sheets steel powder coated enclosure suitable for incorporating One/Two nos. MCB.	10	Ea.		
8	providing and erecting Approved make RCCBs conforming to IS: 12640 and having sensitivity of 30 mA and Short Circuit withstand capacity of 10 KA and suitable for operation on single phase 240 V,50Hz. having characteristic of quick action & tripping with all advance feature & do not incorporate any electronic component. for following Max. rating erected as directed				
	(i) 25 Amps.DP, Cat. III	5	Ea.		
9	Providing & erecting Approved make Power Saving 50 Watt Ceiling Fan with double ball bearing ISI mark with Condenser 230 volt A.C. 50 Hz 1200 mm sweep complete having 3blades with aluminium blades with , canopy & 30 cm. down rod erected with earthing.(Make shall be approved by Engineer in charge)	80	Ea.		
10	Removing existing ceiling fan Down Rod and supplying and erecting 19 / 20 mm. nominal bore Medium Class M.S. Pipe 18 inch down rod erected duly painted for fan complete with proper insulation without leakage and earthing	0	Ea.		
11	Removing existing ceiling fan Down Rod and supplying and erecting 19 / 20 mm. nominal bore Medium Class M.S. Pipe 24 inch down rod erected duly painted for fan complete with proper insulation without leakage and earthing	284	Ea.		
12	Removing existing ceiling fan Down Rod and supplying and erecting 19 / 20 mm. nominal bore Medium Class M.S. Pipe 30 inch down rod erected duly painted for fan complete with proper insulation without leakage and earthing	0	Ea.		
<b>NET AMOUNT (Without GST)</b>					
SGST 9 %					
CGST 9 %					
<b>NET AMOUNT (With GST)</b>					

- Bidder must be use materials as per vendor list.
- Vendor List

Sr.No.	Item	Approved Make	Make Offered By Contractor
1	PVC CONDUITS AND ACCESSORIES, UPVC TRUNKING	PRECISION / ANCHOR / POLYCAB/NIHIR	
2	MODULAR SWITCHES, SOCKETS & OTHER	MK / LEGRAND / HAVELLS / GM / ANCHOR, ALEX	
3	MEDIUM VOLTAGE CABLE & WIRE	FINOLEX / POLYCAB / KEI / HAVELLS	
4	Fan Accessories	Havells , Bajaj , Orient,	

### Other Terms & Condition

- The rates should be excluding of GST & including of other taxes/duties/loading-unloading/Labor including Transporting.
- Validation of Quotation will be 120 days from the last date of submission of Quotation.
- Bidders are suggested to visit the site location before quoting this quotation and for any further query, bidder can contact Light department of New East (Sarothana) Zone, SMC.
- The Offer shall be submitted for the makes as mentioned in the quotation. The offer for the makes/s other than shown in the quotation will be rejected out rightly.
- Contractor will have to submit **Security deposit at the rate of 2.0 %** of work order value within 10 days from the date of work order otherwise; penalty @ 0.065% of the amount of security deposit per day of delay shall be levied.
- Successful Contractor have to execute Agreement, Surety & Undertaking on the non judicial stamp paper of Rs.300/- each purchased from Surat city only.
- Any "price variation clause" shall not be accepted.
- If contractor fails to complete above work than penalty @ 0.2% of amount of unexecuted work per day delayed should be recovered from bill. Maximum delay penalty shall be recovered 10% of unexecuted amount of work order.
- Any Other Miscellaneous items, which are necessary to complete the work should also be considered into the scope of work and needs to carry out by bidder/contractor free of cost.
- All required materials, tools, tackles and men power for the job shall be brought by the Contractor.
- Payment shall be made after satisfactory Completion of whole work in all respect and submission of required documents and invoices of the work.
- All The Central, State and Local government rules and regulations including Safety shall be strictly followed by the Contractor.
- The name of work i.e. "**Quotation for the work of .....**" must be mentioned on the envelope.

Thanking You,



Executive Engineer  
New East(Sarothana)Zone  
Surat Municipal Corporation

**\*SIGNATURE & SEAL OF CONTRACTOR\***