

કાર્યપાલક ઈજનેર
સાઉથ ઝોન-એ(ઉધના)



સુરત મહાનગરપાલિકા,
સાઉથ ઝોન-એ (ઉધના)
સત્યનગરની સામે, ઉધના, સુરત
☎ ૨૨૭૭૦૪૩, ૨૨૭૮૪૨૯

ઈન્કવાયરી ફોર ક્વોટેશન

પ્રતિ,

.....
.....

સા.ઝોન-એ/ટેક/નં. ૧૯૫૩

તા.૦૫/૦૬/૨૦૨૬

વિષય:—સાઉથ ઝોન-એ(ઉધના)ના કાર્યક્ષેત્રમાં આવેલ બમરોલી અર્બન હેલ્થ સેન્ટર કમ હોસ્પિટલ ખાતેના પેથોલોજીકલ લેબોરેટરી માટે ૧.૫ ટન કેપેસિટીના એ.સી. મશીન પુરા પાડી, ફિટ કરી, કાર્યરત કરવાનું કામ (ત્રીજો પ્રયાસ)

મહાશય,

સાઉથ ઝોન-એ(ઉધના)ના કાર્યક્ષેત્રમાં, બમરોલી અર્બન હેલ્થ સેન્ટર કમ હોસ્પિટલ ખાતેના બીજા માળે આવેલ પેથોલોજીકલ લેબોરેટરી માટે ૧.૫ ટન કેપેસિટીના એ.સી. મશીન સેટ-૦૫ પુરા પાડી, ફિટ કરી, કાર્યરત કરવાની કામગીરી અન્વયે આ સાથે સામેલ પ્રાઈસ શિડયુલમાં જણાવેલ ભાવોથી ઉચા/નીચા % મુજબ ઓન લાઈન ભાવપત્રક બંધ ક્વરમાં મંગાવવામાં આવે છે. જે ભાવપત્રક ભરી, આ સાથે સામેલ ડોક્યુમેન્ટસ પર જરૂરી સહી સિકકા સહિત તા. ૧૫/૦૬/૨૦૨૬ સુધીમાં સાઉથ ઝોન-એ(ઉધના) કચેરી ખાતે નીચે સહી કરનારને મળે તે રીતે પહોંચાતું કરશો. સમય મર્યાદા બાદ આવેલ ભાવપત્રકને ધ્યાને લેવામાં આવશે નહીં જેની નોંધ લેશો.

-Sd-

કાર્યપાલક ઈજનેર,
સાઉથ ઝોન-એ(ઉધના)
સુરત મહાનગરપાલિકા.

બિડાણ:— ટર્સ કન્ડીશન અને પ્રાઈસ શિડયુલ/ક્વોટેશન

SURAT MUNICIPAL CORPORATION

South Zone-A(Udhna), Light Department

Part-1

■ Technical Specification ■

Tonnage	1.5 TR
Cooling Capacity (Watt) (Min~Max)	5130
No. of Compressor	as per Company Model
Compressor Type	Tropical Rotary/Rotary
Rated Cooling Capacity (BTU/Hr)	17500
Refrigerant	Latest
Power Supply	230V, 50Hz, Single Phase
Remote Control	Yes
Cooling coil Condenser	Copper
Mounting Type	Wall Mounted
Make	O General, Daikin, Mitsubishi Electric, Toshiba, Hitachi, Bluestar

- Bidder must offer 1 year manufacturer warranty for the supplied items.
- Contractor has to get approval of the make/ material out of list mention above before supply.

■ Other Terms & Condition ■

- The Rates mentioned in BOQ are excluding GST & Including of other taxes/duties/loading-unloading/Labour including Transporting. GST will be reimbursed separately (if applicable as per the opinion of Account department of SMC / GST Consultant of SMC) as per the prevailing GST Rates decided by the Government. The contractor is invariably bound to any changes in GST Rates made during the course of the work. The payment (if applicable) for GST will be only released only after the applicable Amount reflects on Government portal. Decision of Account Department of SMC regarding applicable GST Rates will be final.
- Validation of Quotation will be 120 days from the last date of submission of Quotation.
- Bidders are suggested to visit the site location before quoting this quotation and for any further query, bidder can contact Light department of South Zone, SMC.
- Work Completion period will be 15 Days from the date of work order. If contractor fails to complete above work than penalty @ 0.2% of amount unexecuted work per day delayed should be recovered from your bill. Maximum delay penalty shall be recovered 10% of unexecuted amount of work order.

(P.T.O.)

- Contractor will have to submit Security deposit at the rate of 2 % of work order value within 10 days from the date of work order otherwise; penalty @ 0.065% of the amount of security deposit per day of delay shall be levied.
- Successful Contractor have to do Agreement, Surety & Undertaking on the non judicial stamp paper of Rs.300/- each purchased from Surat city only.
- Any "price variation clause" shall not be accepted.
- It is to be clearly noted that advance planning must be done with the department before installation work.
- Miscellaneous items to complete the installation in all respect & as described in specification.
- All required materials, tools, tackles and men power for the job shall be brought by the Contractor.
- Contractor shall be responsible to the accident/injury/Loss to any of the staff members of them. He shall follow all the applicable rules & regulations as per Government norms for the Same.
- It shall contractor responsibility to get acquainted type of acts rules, regulations, and general rules, Procedure of corporation.
- Payment shall be made after satisfactory Completion of whole SETC work in all respect and submission of required documents and invoices of the work.
- All The Central, State and Local government rules and regulations including Safety shall be strictly followed by the Contractor.
- The name of work i.e.“ **Quotation for the work of**” must be mentioned on the envelope.

Thanking You,

-Sd-

Executive Engineer,
South Zone-A(udhna)
Surat Municipal Corporation.

SIGNATURE & SEAL OF CONTRACTOR

SURAT MUNICIPAL CORPORATION
South Zone-A(Udhna), Light Department
Part-2

Quotation

Sr. No.	Description	Qty.	Unit	Sanctioned Rate per Unit	Total Amount (GST Extra)
1	Providing and erecting approved make split air-conditioning unit consisting of copper condensing unit with fan motor, hermetically sealed rotary compressor with accessories etc. duly connected separately erected evaporating unit and blower motor with its accessories by means of extra supplied proper insulated copper tubing, drain PVC pipes suitable for (cost includes powder coated Stand, Eco Friendly green gas charging, 15A plug top& Remote Control) with necessary core cutting. (b) for 1.5 ton capacity	5	Ea.	₹33,050.00	₹ 1,65,250.00
2	Supplying and erecting insulated pair of soft copper tubing open or concealed including power and control cable, necessary PVC drain pipes for Split AC machine up to 4 TR capacity (Extra Copper Piping)	1	Rmt	₹ 780.00	₹ 780.00
3	Rigid UPVC drain pipe of 10 Kg/cm ² . rating with 9 mm thick. nitrile rubber insulation. (D) 25 mm dia. (Extra Drain pipe)	1	Rmt	₹ 42.00	₹ 42.00
Total Amount for SITC (GST Extra)					₹ 1,66,072.00

I/We here by tendered to execute the above mentioned description of a work in accordance the accompanying specification and condition in consideration of the quantity of the work to be executed AT PAR rate i .e. same cost / at _____ % (Percentage) in word _____ Percentage Below / Above amount shown in Schedule.

-Sd-

Executive Engineer,
South Zone-A(udhna)
Surat Municipal Corporation.

SIGNATURE & SEAL OF CONTRACTOR