

Executive Engineer
South Zone-B(Kanakpur)



Surat Municipal Corporation
South Zone-B(Kanakpur)
Beside Swaminarayan Tample, Gujarat
Housing board, C.O.P No.5, Kanakpuar,
Surat.
☎ 6359905030, 6359905031

QUOTATION INQUIRY

SZ-B/Tech./No.2445

Dtd.: - 13/07/2026

To,

.....
.....
.....
.....

SUB:- SITC of 6 KVA Un-interruptible Power Supply (UPS) at the Civic Centre located at Pardi-Kande in the South Zone-B (Kanakpur).

Dear Sir,

South Zone-B (Kanakpur) of Surat Municipal Corporation is inviting quotation for the work of **SITC of 6 KVA Un-interruptible Power Supply (UPS) at the Civic Centre located at Pardi-Kande in the South Zone-B (Kanakpur).** Send your offer in a sealed cover So as to reach in the office of Executive Engineer [South Zone-B (Kanakpur)] **on or before Dt.22/07/2026 @ up to 6.00 pm.** Please note that the sealed cover shall be super scribed with the name of work. Details of material required are as following.

Sr. No.	Item Description	Unit	Qty	Rate per Unit (Without GST) (SOR 2026-27)	Total Amount Rs. (Without GST)
1	Supplying and erecting approved make online Un-interruptible Power Supply system comprising flat cum-boost charger with IGBT base rectifier & Inverter & sealed maintenance free SMF batteries for min. 1 Hour Backup. The charger having operating capacity for input 160-270V AC & inverter having output 230V,50 Hz Ac with Inbuilt Isolation transformer with 0.8 load power factor with battery, over/under voltage output with over load & short circuit protection equipment. The system housed in CRC sheet duly powder coated paint with following power backup. with MS painted batteries stand, 10% Overload capacity for momentary load. 6 KVA UPS	Ea.	02	1,78,983.11	3,57,966.22
Estimated Amount in Rs.					3,57,966.22
% Above/Below					 %
Total Amount in Rs.(Without GST)					

Terms and Condition

1. UPS Make:- TATA Libert, Merlin Gerin, Socomac, APC, BPE, Vertiv,Emerson
2. Battery Make:- Panasonic,Exide,Base,Prestolite, Rocket,Amron,Tata-Green

3. The UPS shall be floor mounted with stand; self contained and metal clad and shall be suitable for supplying a nonlinear load.
4. It shall be possible to open the enclosure front door when the Unit is in use without exposing any live contact touch.
5. The On-line UPS shall be min four -pulse rectifier & pulse width modulation inverter technology with microprocessor control type. It shall incorporate a static bypass switch that shall operate in event of UPS failure, overload or manual initiation in order to transfer the output supply to mains without disturbance to the output supply.
6. The UPS shall incorporate a DC under voltage trip circuit to Electro mechanically trip the UPS output in order to protect the batteries.
7. The batteries shall be housed(stand), within a separate matching battery cubicle suitable for location adjacent to the UPS. The batteries shall be of the rechargeable, sealed maintenance free lead acid type. The battery supply to the UPS shall be via a fused load break switch disconnected circuit breaker. The battery recharge time to 90% of full charge shall be approximately ten times the discharge time at full load.
8. Terminals shall be shrouded to prevent accidental contact.
9. Detail Technical brochure, catalogue, Literature of offered instrument must be attached in technical documents, without which offer will be out rightly rejected.
10. Contractor has to get approval of the make/ material out of list mention above before supply.
11. The rates should be excluding of GST and including of other taxes/duties/c.c./loading-unloading/ Labour Transporting, etc.
12. Validation of Quotation will be 120 days from the last date of submission of Quotation.
13. Work Completion period will be 15 Days from the date of work order. If contractor fails to complete above work than penalty @ 0.2% of amount unexecuted work per day delayed should be recovered from your bill. Maximum delay penalty shall be recovered 10% of unexecuted amount of work order.
14. Contractor will have to submit Security deposit at the rate of 2 % of work order value within 10 days from the date of work order otherwise; penalty @ 0.065% of the amount of security deposit per day of delay shall be levied.
15. Successful Contractor have to do Agreement, Surety & Undertaking on the non judicial stamp paper of Rs.300/- each purchased from Surat city only.
16. Any "price variation clause" shall not be accepted.
17. It is to be clearly noted that advance planning must be done with the department before installation work.
18. Miscellaneous items to complete the installation in all respect & as described in specification.
19. UPS shall carry guarantee/warranty of 12 months and Batteries shall carry guarantee/ warranty of min. 24 months from the date of commissioning.
20. All required materials, tools, tackles and men power for the job shall be brought by the Contractor.
21. Payment shall be made after satisfactory Completion of whole SETC work in all respect and submission of required documents and invoice of the work.
22. All The Central, State and Local government rules and regulations including Safety shall be strictly followed by the Contractor.
23. The name of work i.e.“ Quotation for the work of” must be mentioned on the envelope. Without which quotation is likely to be rejected, which must be noted.

Thanking You,

-Sd-
Executive Engineer,
South Zone-B(Kanakpur)
Surat Municipal Corporation

SIGNATURE & SEAL OF CONTRACTOR