

SURAT MUNICIPAL CORPORATION
Surat Municipal Institute of Medical Education and Research

Opp. Bombay Market, Umarwada, Surat – 395 010 (Guj.)-India.

Medical Superintendent-Extn.1600
SMIMER Hospital
Phone Nos. 2368040 to 43



FAX No.(0261) 2360306
GST No.24AAALS0678Q1ZE

SMIMER/Hosp/Out/ No.2651
Date: 27/07/2026

To,
M/s _____

Quotation

Sub : Quotation for dismantling of MGPS Copper Pipeline Network from G+4 Floors including valves, outlet points, transportation, stacking, documentation and handover complete as per tender specification at SMIMER Hospital, Surat.

Dear Sir,

Quotations are invited for dismantling of MGPS Copper Pipeline Network from G+4 Floors including valves, outlet points, transportation, stacking, documentation and handover complete as per tender specification at SMIMER Hospital, Surat as per following terms & conditions.

1. The rates should be F.O.R. destination inclusive of all taxes & charges i.e. freight, GST, packing and insurance etc.
2. Rate should be quoted as per serial number of list.
3. Items which are not found to our specifications will not be accepted.
4. During dismantling, if any items are damaged the same shall be repaired or replaced by the bidder at their own cost.
5. Overwriting, erasures or correction in quotations shall not be considered.
6. **Quotations are to be sent in sealed cover as above.**
7. Quotations received after due date will not be considered.
8. Dismantling work should be completed **within 7 working days from the** date of receipt of work order or time limit allowed which will be mentioned in Purchase order/work order failing which penalty will be imposed @ 0.2% per day of order amount maximum up to 10%.
9. The successful awardee will be required to place Security Deposit (SD`) @ 5% (Five percent) of the consideration of the contract amount by demand draft or Banker's Cheque of any scheduled / nationalized bank payable at Surat drawn in favour of "Commissioner, Surat Municipal Corporation". Security deposit must be submitted within 15 days or time limit allowed in work order/Purchase order from the date of notice of award of contract, failing which a delay penalty @ 0.065% of the amount of security deposit will be imposed for each day.
10. On awarding the contract, the awardee agency will have to enter into a written agreement using Stamp Paper value of Rs.300/-.
11. The Security Deposit will be returned after the completion of dismantling works are completed as per the satisfactory certification of Medical Gas pipeline Committee, SMIMER and after the fulfillment of obligation created under the contract awarded.

12. Quotations sent by post or courier or services or in person is preferable.

13. Guarantee/warranty should be mentioned in quotation.

14. Shop & Establishment registration certification should be submitted preferably.

15. GST CLAUSE FOR CONSTRUCTION/ ERECTION/ COMMISSIONING/INSTALLATION/ REPAIRS/ MAINTENANCE/RENOVATION/ FABRICATION OF STRUCTURE INCLUDING BUILDING(MEANS ALL WORKS CONTRACT/TURN KEY PROJECTS/SUPPLY OF MATERIAL/GOODS)

GST (Goods & Service Tax) has come in existence from 1st July, 2017. Contractor/Successful Bidder is bound to pay any amount of GST prescribed by the Govt. of India as per the Terms of contract agreed upon during the course of execution of this Contract.

During the course of execution of contract, if there is any change in Rate of GST(Goods & Service Tax) by the Government, the same shall be reimbursed / recovered separately by SMC, subject to **the submission of original Receipt/Proof for the amounts actually remitted by** the successful Tenderer /Contractor to the Competent Authority along with a Certificate from Chartered Accountant of Contractor / Successful Bidder certifying that the amount of GST paid to the Government and the same shall be intimated / submitted/claimed within 30 (Thirty) Days from the date of payment. Remittance of GST within stipulated period shall be the sole responsibility of the Successful Bidder/Contractor, failing which, SMC may recover the amount due, from any other payable dues with SMC and decision of Municipal Commissioner shall be final and binding on the Contractor / Successful Bidder in this regard. Further, the non-payment of GST to the Government may lead to the termination of the contract and forfeiture of Security Deposit / Performance Guarantee Amount.

If imposition of any other new Taxes /Duties /Levies / Cess or any other incidentals etc. or any increase in the existing Taxes / Duties / Levies / Cess or any other incidentals etc.(Excluding GST) are imposed during the course of the contract, the same shall be borne by the Contractor / Successful Bidder only, in no case SMC shall be liable for the same.

The contractor will submit the invoice to the SMC having GSTIN of SMC mentioned therein and the taxes shall be shown separately on the face of the invoice so as to claim as ITC by SMC.

Envelope should bear on top: "Quotation for dismantling of MGPS Copper Pipeline Network from G+4 Floors including valves, outlet points, transportation, stacking, documentation and handover complete as per tender specification at SMIMER Hospital, Surat".

Quotations are to be sent in sealed cover addressed to office of Medical Superintendent shree, SMIMER Hospital by post/courier/in person so as to reach on or before **Dt. 03/08/2026 up to 5:00 P.M.** Quotation received thereafter will not be accepted.

Medical Superintendent
SMIMER Hospital

TECHNICAL SPECIFICATIONS

1. Scope of Work

1.1 The work shall comprise dismantling of the existing Oxygen Medical Gas Pipeline System (MGPS) installed in the DCHC/Parking Block of SMIMER Medical Hospital from Ground Floor to Fourth Floor (G+4 Floors).

1.2 The scope shall include careful dismantling of:

- Copper Oxygen Pipes.
- Isolation Valves.
- Oxygen Terminal Outlet Points.
- Associated fittings, supports, clamps, connectors, and accessories, wherever applicable.

1.3 The dismantling shall be carried out in such a manner that all recovered materials remain suitable for future use as per applicable MGPS guidelines.

2. Site Visit

2.1 Bidders are requested to visit the site before submitting their bids in order to obtain a complete overview of the project.

2.2 The bidders shall satisfy themselves regarding the site conditions, accessibility, extent of work, quantity of materials involved, and any operational constraints before quoting.

2.3 No extra claim arising due to lack of site inspection or inadequate understanding of site conditions shall be entertained after submission of the bid.

3. Method of Dismantling

3.1 The contractor shall carefully dismantle the Copper Pipes, Isolation Valves, and Oxygen Terminal Outlet Points without causing any damage to the recovered materials.

3.2 Necessary cutting, disconnection, removal of supports, handling, lowering, shifting, and transportation within the hospital premises shall be included in the scope of work.

3.3 The contractor shall ensure that the dismantling activity is carried out in accordance with prevailing MGPS guidelines and safe engineering practices.

3.4 Adequate precautions shall be taken to prevent damage to the building structure, finishes, equipment, and other services during dismantling.

4. Storage and Handover of Dismantled Materials

4.1 All dismantled Copper Pipes, Isolation Valves, Oxygen Terminal Outlet Points, and associated accessories shall be transported to the designated storage location at the Ground Floor of DCHC Block.

4.2 The dismantled materials shall be properly stacked, segregated, and stored to avoid damage and facilitate future use.

4.3 Proper care shall be taken during handling, transportation, and storage of dismantled materials.

5. Documentation and Reporting

5.1 The contractor shall prepare and submit a detailed dismantling report upon completion of the work.

5.2 The report shall include floor-wise details of dismantled materials recovered from Ground Floor to Fourth Floor.

5.3 The report shall contain details of Copper Pipes, Isolation Valves, Oxygen Terminal Outlet Points, and other associated materials recovered during dismantling.

5.4 Photographic records before, during, and after dismantling shall be maintained and submitted, if required by the MGPS authorized members.

6. Handover Procedure

6.1 The dismantled materials shall be handed over to the hospital authorities after completion of the dismantling work.

6.2 The handover shall be carried out in the presence of:

- Authorized MGPS Personnel.
- Security Staff.
- Authorized representative of the contractor.

6.3 A proper handing-over and taking-over record shall be prepared and signed by all concerned personnel.

7. Contractor's Responsibility

7.1 The contractor shall arrange all necessary skilled and unskilled manpower required for execution and completion of the work.

7.2 The contractor shall arrange all tools, tackles, cutting equipment, ladders, scaffolding, lifting arrangements, transportation facilities, safety equipment, and consumables required for carrying out the dismantling work.

7.3 No manpower, tools, equipment, machinery, or consumables shall be provided by SMIMER Medical Hospital.

7.4 The contractor shall be solely responsible for execution of the work in a safe and efficient manner.

8. Safety Requirements

8.1 The contractor shall comply with all applicable safety regulations and statutory requirements during execution of the work.

8.2 Appropriate Personal Protective Equipment (PPE) shall be provided and used by all personnel engaged in the work.

8.3 The contractor shall take all necessary precautions for the safety of hospital staff, patients, visitors, workmen, and hospital property.

8.4 Any damage caused to the building, equipment, or services during dismantling shall be rectified by the contractor at his own cost.

9. Completion of Work

9.1 The work shall be considered complete only after:

- Successful dismantling of all specified MGPS components.
- Safe shifting and stacking of dismantled materials at the designated location.
- Submission of the dismantling report.
- Completion of documented handover of recovered materials to the hospital authorities.

9.2 The work area shall be cleaned and cleared of all debris and unwanted materials before final completion.

PRICE BID

Sr. No.	Description	Unit Rate Lump Sum (L.S.) in Rs.	GST in Rs	Total Amount with GST
1	Dismantling of MGPS Copper Pipeline Network from G+4 Floors including valves, outlet points, transportation, stacking, documentation and handover complete as per tender specifications			

Medical Superintendent
SMIMER Hospital
Surat Municipal Corporation