

કામિની દોષી

કાર્યપાલક ઈજનેર



સુરત મહાનગરપાલિકા

સાઉથ ઈસ્ટ ઝોન (લિંબાયત)

નં. સા.ઈ.ઝોન/આઉટવર્ડ/૪૫૭૮

તારીખ : ૦૫/૦૮/૨૦૨૬

—:ભાવપત્રક:—

પ્રતિ,

.....
.....
.....
.....

વિષય:— સાઉથ ઈસ્ટ ઝોન(લિંબાયત)માં આવેલ ટી.પી. સ્કીમ નં.૪૧(ડિંડોલી), ટી.પી. સ્કીમ નં.૬૧(પરવત-ગોડાદરા), ટી.પી. સ્કીમ નં.૬૨ (ડિંડોલી-ભેદવાડ-ભેસ્તાન) અને ટી.પી. સ્કીમ નં.૬૯ (ગોડાદરા-ડિંડોલી)વિસ્તારમાં આવેલ વિવિધ સુરત મહાનગરપાલિકાની હસ્તકની વિવિધ મિલ્કતોમાં ઉધર્ ટ્રીટમેન્ટ કરાવવાનું કામ.(બીજો પ્રયાસ)

સંદર્ભ :—મા.ડે.કમિશનરશ્રીની તા.૦૫/૦૮/૨૦૨૬ ની મંજૂરી.

મહાશય,

ઉપરોક્ત વિષયનાકામે સંદર્ભમાં જણાવેલ કામે સાઉથ ઈસ્ટ ઝોન(લિંબાયત)માં આવેલ ટી.પી. સ્કીમ નં.૪૧(ડિંડોલી), ટી.પી. સ્કીમ નં.૬૧(પરવત-ગોડાદરા), ટી.પી. સ્કીમ નં.૬૨ (ડિંડોલી-ભેદવાડ-ભેસ્તાન) અને ટી.પી. સ્કીમ નં.૬૯ (ગોડાદરા-ડિંડોલી) વિસ્તારમાં આવેલ વિવિધ સુરત મહાનગરપાલિકાની હસ્તકની વિવિધ મિલ્કતોમાં ઉધર્ ટ્રીટમેન્ટ કરાવવાના કામે રૂ.૫,૦૦,૦૦૦.૦૦પૈ. મર્યાદામાં કામગીરી કરવા માટે ભાવપત્રક મંગાવવા મા.ડે.કમિશનરશ્રીની તા.૦૫/૦૮/૨૦૨૬ ની મંજૂરી મેળવવામાં આવેલ છે. જેનું શીડયુલ-બી સામેલ કરેલ છે. જે અન્વયે સદર કામગીરી કરવા તમો રસ ધરાવતા હોવ, તો સામેલ શીડયુલ-બી માં આપના ભાવો ભરી રૂ.૫૦૦૦/- EMD સહિત સીલબંધ કવરમાં ભાવપત્રક તા.૨૧/૦૮/૨૦૨૬ સુધીમાં નીચે સહી કરનારને મોકલવા ઘટતુ કરશો. ઉપરોક્ત જણાવેલ તારીખ પછી કોઈ બંધ કવર સ્વીકારવામાં આવશે નહિ.

SD/-

કાર્યપાલક ઈજનેર

સાઉથ ઈસ્ટ ઝોન(લિંબાયત)

સુરત મહાનગરપાલિકા

Specification & Work Conditions

- 1.0. Materials : The chemicals used for the soil treatment shall be only one of the following with concentration shown against each in aqueous emulsion. Chemicals Concentration 1.Imidachloprid 30.5% SC 2.Chlorpyriphos 20% EC/ 50% EC 3.Bifenthrin 2.5%
- 2.0. Workmanship
- 2.1. The chemicals barrier shall be complete and continuous under whole of the structure to be protected.
- 2.2. The bottom and the sides of foundations up to a height of 30 cms from the bottom of excavation made for masonry foundation and for basement column pits shall be treated with the chemical emulsion at the rate 5 liters/ sq.mt. of the surface area. .
- 2.3. The chemical treatment shall be-carried out when the surfaces is quite dry. Chemical treatment shall not be carried out when it is raining or when the soil wet with rain or sub soil water.
- 2.4. Once formed, treated soil berries shall be not disturbed. If by chance, treated soil barriers are disturbed, immediate steps shall be taken to restore the continuation and compactness of the barrier system
- 2.5. The treatment against termite infection shall remain fully effective for a period not less than 05 years from date of issue of the final certificate to completion of work. If at any time during this period, any defects in treatment are revealed or any evidence of infection in any part of the building or structure is noticed, the contractor shall be rectify the concerned defects within 14 days on receipt of notice from Engineer-in-charge. On contractor's failure to do so, the Engineer-in-charge may get the same rectified through any other agency at contractor's risk and cost, and decision of Engineer-in-charge as to the cost payable by contractor for the same shall be final and binding to the contractor.
- 2.6. A guarantee bond on appropriately stamped paper shall be given by the contractor to the department in the manner and form prescribed below: FORM OF GUARANTEE BONDI/We (Contractor) hereby guarantee that work will remain unaffected and will not be any way dam+B17aged by termite or any other germs of similar types, for a period for 05 years after completion of the work of anti-termite as per the terms and conditions of the contract and or damage that might be caused on account of termite and or other similar type of germs and hereby Guarantees to make good any loss of damages suffered by the Government of Gujarat and further guarantee to redo effective work without claiming any extra cost.
- 2.7. This guarantee shall remain in force for the period of 05 years from the completion of the work under the contract and it shall remain binding to the contractor for period of 05 years.
- 3.0. Mode of measurements & payment
- 3.1. The length and breadth shall be measured correct to a Ft. as per the dimensions of sanctioned plans. No deduction shall be made nor extra paid for any opening for pipes etc. up to 1.0 sq.ft. The rate shall include the cost of all labor and materials required for the operation involved for satisfactory completion of this item. The sides of the trenches 12 in., each side and bottom shall be measured under this item.
- 3.2. The rate shall be for a unit of One square foot.
- 4.0. Quotation Fee & Security Deposit
- 4.1. Quotation including Rs. 5,000.00/- per set which is required for submission of tender towards the cost of Quotation documents in pay order or by demand draft of any nationalized bank, in favor of "Commissioner, Surat Municipal Corporation, Surat" payable at Surat and shall be submitted along with EMD and other documents. Surat Municipal Corporation shall not be liable for any postal delay in any case.
- 4.2. The successful quotationer will be required to furnish a performance bond (Security Deposit) of an amount equal to 2.0% (Two percent) of the quotationed amount.

SD/-

**ExecutiveEngineer
South East Zone (Limbayat)
Surat Municipal Corporation**



નં. SEZ/OUT/4578
Dtd :05/08/2026

To

.....
.....
.....

Subject:Quotation For Providing Treatment Service in Various Municipal NPSS School and Suman School BuildingsinTPS No.41 (Dindoli), TPS No.61 (Parvat-Godadara), TPS No.62(Dindoli-Bhedwad-Bhestan) and TPS No.69(Godadara-Dindoli)South East Zone (Limbayat), Surat. (Second Attempt)

You are Requested to send your Quotation Super Scribed As “Quotation ForProviding Treatment Service in Various Municipal NPSS School and Suman School BuildingsinTPS No.41 (Dindoli), TPS No.61 (Parvat-Godadara), TPS No.62(Dindoli-Bhedwad-Bhestan) and TPS No.69 (Godadara-Dindoli)South East Zone (Limbayat), Surat.” On Or **Before Dt.21/08/2026** Up to 04:00 P.M. Further Information If any Can be had From the office of under signed.

I/We here qutoe the following item rate & agreed to carry out the quoted rate the mentioned work.

No.	ITEM	QTY	Per	Rate With GST	Amount With GST
1	સાઉથઈસ્ટ ઝોન(લિંબાયત)માંઆવેલ ટી.પી. સ્કીમ નં.૪૧(ડિંડોલી), ટી.પી. સ્કીમ નં.૬૧ (પરવત-ગોડાદરા), ટી.પી. સ્કીમ નં.૬૨ (ડિંડોલી-ભેદવાડ-ભેસ્તાન) અને ટી.પી. સ્કીમ નં.૬૯ (ગોડાદરા-ડિંડોલી) વિસ્તારમાં આવેલ વિવિધસુરત મહાનગરપાલિકાહસ્તકની સુમન શાળા તથા ન.પ્રા.શિ.સ.ની શાળાઓમાં ઉધઈ ટ્રીટમેન્ટ કરાવવાનું કામ. (બીજો પ્રયાસ)	2,00,000	Sq.ft.		
TOTAL Quotation Amount					