

કાર્યપાલક ઈજનેર
સાઉથ વેસ્ટ (અઠવા) ઝોન,
આદર્શભવનની બાજુમાં,
અઠવાલાઈન્સ,
સુરત મહાનગરપાલિકા, સુરત.



ફોન નંબર : ૨૬૬૩૦૪૯-૫૦
૨૬૬૭૯૨૬
મ્યુનિસિપલ ઝોન ઓફિસ, સુરત.

સંમતિપત્ર

નં.સા.વે.ઝોન(અઠવા)/આ.૪૩૯૪
તારીખ: ૩૦/૦૮/૨૦૨૬

પ્રતિ,

.....
.....
.....
.....
.....

વિષય :- સાઉથ વેસ્ટ (અઠવા) ઝોન વિસ્તારમાં સબઝોન નંબર : ૦૧ થી ૦૫ વિસ્તારમાં ટી.પી.રસ્તા પર તથા સોસાયટીના આંતરીક રસ્તા પર પાણી પુરવઠાની જુદી જુદી સાઈઝની સી.આઈ./ડી.આઈ. નળીકા પર મુકવામાં આવેલ વાલ્વના નવા ચેમ્બર બનાવવા તથા હયાત વાલ્વ ચેમ્બરોના મરામત અને નિભાવની કામગીરી કરવાનું કામ.

સંદર્ભ :- (૧) સ્થા.સ.ઠ.નં.૨૧૬૦/૨૦૨૫, તા.૨૦/૧૧/૨૦૨૫ થી મંજૂર થયેલ ટેન્ડરના ભાવે અને શરતે
(૨) માન.ડેપુટી મ્યુ.કમિશનરશ્રી, સાઉથ વેસ્ટ(અઠવા)ઝોન, સુરત મહાનગરપાલિકાની તા.૩૦/૦૮/૨૦૨૬ ના રોજની મંજૂરી.

મહાશય,

સાઉથ વેસ્ટ (અઠવા) ઝોન વિસ્તારમાં સબઝોન નંબર : ૦૧ થી ૦૫ વિસ્તારમાં ટી.પી.રસ્તા પર તથા સોસાયટીના આંતરીક રસ્તા પર પાણી પુરવઠાની જુદી જુદી સાઈઝની સી.આઈ./ડી.આઈ. નળીકા પર મુકવામાં આવેલ વાલ્વના નવા ચેમ્બર બનાવવા તથા હયાત વાલ્વ ચેમ્બરોના મરામત અને નિભાવની કામગીરી કરવાના કામે ઉક્ત સંદર્ભ (૧) મુજબ સ્થા.સ.ઠ.નં. .૨૧૬૦/૨૦૨૫, તા.૨૦/૧૧/૨૦૨૫ થી મંજૂર થયેલ ભાવે અને શરતોને આધિન નેટ અંદાજીત રકમ રૂ.૧૮,૬૧,૩૪૪.૪૦ પૈસા (અંકે રૂપીયા અઠાર લાખ એકસઠ હજાર ત્રણસો ચુમ્માલીસ રૂપીયાને ચાલીસ પૈસા) તથા ગ્રોસ અંદાજીત રકમ રૂ.૨૪,૧૬,૦૨૬.૦૦ પૈસા (અંકે રૂપીયા ચોવીસ લાખ સોળ હજાર છવ્વીસ પુરા) ની મર્યાદામાં કામગીરી કરાવવા માટે સંદર્ભ (૨) હેઠળથી ઓનલાઈન સંમતિપત્ર મંગાવવા મળેલ મંજૂરી મુજબ આ કામ કરવા સંમત હોય તો આપશ્રીની લેખીત સંમતિ બંધ કવરમાં તા.૧૨/૧૦/૨૦૨૬ સુધીમાં નીચે સહી કરનારની કચેરીમાં પહોંચાડવા પ્રબંધ કરશો. ઉપરોક્ત જણાવેલ તારીખ પછી કોઈ બંધ કવરો સ્વીકારવામાં આવશે નહીં.

—: શરતો :—

૧. અર્નેસ્ટમની ડીપોઝીટની રકમ કમિશનરશ્રી, સુરત મહાનગરપાલિકાના નામનો સુરતની રાષ્ટ્રીયકૃત શીડયુલ બેંકના ડીમાન્ડ ડ્રાફ્ટ / પે. ઓર્ડરથી સંમતિપત્રક સાથે રૂ.૨૪,૨૦૦/- ની આપવાની રહેશે.
૨. ઈજારદારે અંદાજીત રકમ ના ૨૦% એટલે કે રૂ.૫,૦૦,૦૦૦.૦૦ પૈ. કે તેથી વધુ રકમની વર્તમાન (ચાલુ) વર્ષની રાષ્ટ્રીયકૃત બેંકની સોલવંશી સર્ટીફિકેટ સંમતિપત્રક સાથે આપવાની રહેશે.

૩. ઈજારદારે સમાન પ્રકારના કામના / અનુભવના સર્ટીફિકેટ (Form 3A / Work Completion Certificate / Work order) ની પ્રમાણીત નકલ સંમતિપત્રક સાથે આપવાની રહેશે.

૪. ઈજારદારે GST રજીસ્ટ્રેશન સર્ટીફિકેટની નકલ સંમતિપત્રક સાથે આપવાની રહેશે.

૫. ઈજારદારે પાન કાર્ડ રજુ કરવાનું રહેશે.

૬. ઈજારદારે શીડ્યુલ-બી માં જણાવેલ ભાવ અને ટેકનીકલ બીડની શરતોને બંધનકર્તા રહેશે.

૭. કોઈપણ તથા બધાજ સંમતિપત્રક રદ કરવાનો અધિકાર સુરત મહાનગરપાલિકાને અબાધિત રહેશે તે અંગે કોઈ પણ કારણો આપવામાં આવશે નહીં.

૮. તમામ પ્રકારના વેરા / સરકારી ટેક્ષ ઈજારદારે ભોગવવાનાં રહેશે.

૯. તમામ સરકારી/ અર્ધ સરકારી લાગુ પડતા કાયદાનું ઈજારદારે પાલન કરવાનું રહેશે.

૧૦. સદર કામગીરી બાબતે અત્રેના પાણી વિભાગના ટેકનીકલ સ્ટાફનો સંપર્ક કરવો.

બીડાણ : (૧) શીડ્યુલ-બી ની નકલ.

-Sd-
કાર્યપાલક ઈજનેર
સાઉથ વેસ્ટ(અઠવા)ઝોન
સુરત મહાનગરપાલિકા

નકલ રવાના : તમામ ખાતા/ઝોનના કાર્યપાલક ઈજનેરશ્રી પ્રતિ જાણ તથા નોટીસ બોર્ડ પર પ્રસિધ્ધ કરવા સારૂ.

SURAT MUNICIPAL CORPORATION					
SOTH WEST(ATHWA) ZONE					
Schedule-B					
NAME OF WORK:- Construction and Repairing work of valve Chamber During maintenance work of Different size of DI/CI water supply pipe line on T.P. road and society Interl road in sub zone 1 to 5 Area in South West (Athwa) Zone.					
ITEM NO.	DESCRIPTION	As per Tender S.O.R.			
		R & B (2023-24} & GWSSB-22-23 & Market rate Without GST & With Cess			
		QTY	RATE	UNIT	AMOUNT
			RS. PS.		RS. PS.
1	Excavation for foundation including sorting out and stacking of useful materials and disposing of the excavated stuff up to 50 meter lead.				
	(a) 0.00 mt. to 1.50 mt. depth	200.00	117.26	C.M.	23452.00
	(b) 1.50 mt. to 3.0 mt. depth.	50.00	129.98	C.M.	6499.00
	(c) 3.00 mt. to 4.5 mt. & all above depth	10.00	142.52	C.M.	1425.20
	S.O.R.-HOUSING R & B (2023-24), Item no.1				
2	Extra rate over item 1 for excavation of asphalt pavement of any thickness etc. complete with stacking the material as directed by the Engineer-in-charge (only carpet thickness shall be considered for calculation of quantity)	50.00	288.65	C.M.	14432.50
	S.O.R.GWSSB-22-23, Sec-B, Item no.2				
3	Filling available excavated earth(excluding rock) in trenches plinth,sides of foundations etc.in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering.	260.00	130.39	C.M.	33901.40
	S.O.R.-HOUSING R & B (2023-24), Item no.10				
4	Providing and laying C:C 1:3:6 (1 cement :3 coarse sand and : 6 graded stone aggregate of 40 mm nominal size) and curing, compacting excluding cost of form work for P.C.C.	30.00	3005.76	C.M.	90172.80
	S.O.R.-HOUSING R & B (2023-24), Item no.5				
5	Providing and constructing brick work using common Fly Ash bricks confirming to IS:13757, IS:5454, IS:3495 having crushing strength not less than 35 Kg./Sq.Cm. brick masonry as per the detailed drawing using brick of approval quality in foundation and plinth including racking out joints, watering etc. as directed in C.M.1: 6 (1 cement:6 fine sand) etc.complete	150.00	4237.00	C.M.	635550.00
	S.O.R.-HOUSING R & B (2023-24), Item no.9				
6	Providing 10 mm thick plaster in CM (1:3) in single coat for plastering for all heights for brick masnory surface and RCC surface and finished even and smooth with floating coat of neat cement slurry as directed by Engineer-in-Charge.	300.00	189.79	S.M.	56937.00
	S.O.R.-HOUSING R & B (2023-24), Item no.24 (a)				
7	Providing and laying M-200 nominal mix concrete (i.e in prporation of 1:1-1/2:3) 1 cement : 1-1/2 fine Agg.and 3 Graded stone agg. 20 mm nominal size kapachi including cost of form work but excluding the cost of reinforcement for RCC work in including etc complete.				
	(A) Foundation, Footing, Base of Columns and mass concrete	0.00	4146.15	CM	0.00
	(B) Slabs	40.00	6813.01	CM	272520.40
	S.O.R.-HOUSING R & B (2023-24), Item no.13-(C)-4				
8	Providing & fixing T.M.T Bar Fe-500 D reinforcement for RCC work including, bending,binding and placing in position etc. complete.	4200.00	76.21	KG	320082.00
	S.O.R.-HOUSING R & B (2023-24), Item no.15				

ITEM NO.	DESCRIPTION	As per Tender S.O.R.			
		R & B (2023-24} & GWSSB-22-23 & Market rate Without GST & With Cess			
		QTY	RATE	UNIT	AMOUNT
RS. PS.	RS. PS.				
9	Providing & fixing M.S. manhole frame and cover of 0.6 x 0.45 mt.size and approx.50 kg weight with prime coat of red oxide and two coats of oil paint having plate thickness of 12 mm etc.complete as directed by Engineer in charge.	200.00	90.48	KG	18096.00
	S.O.R.-HOUSING R & B (2023-24), Item no.98 (A)				
10	Providing & fixing PVC/ C.I.Steps of Size 300 mm x150 mm x25 mm.painted with a coat of primer and two coats of anti corrosive paint etc. complete as directed by Engineer in charge.	20.00	111.61	NO	2232.20
	R.A.C. APPROVED RATE				
11	Provding & laying 1:2:4 C.C. for the thrust block including cost of form work.	10.00	3601.33	C.M.	36013.30
	S.O.R.-R & B (2023-24) Item no.5.3.13				
12	Demolition/Dismantalling RCC work or masonry work in any part of nearby concrete structure including stacking of serviceable/useful material and disposal of unserviceable material with all lead and lift.				
	(a) Brick masonry work	60.00	550.40	C.M.	33024.00
	(b) RCC work	60.00	1057.47	C.M.	63448.20
	S.O.R.-HOUSING R & B (2023-24), Demolition Item no. 1, 2				
13	Providing & fixing R.C.C. Precast Manhole Frame with Cover in M:35 as per drawing for Manhole suitable for 450 X 600 cm opening including cost of reinforcement, M.S. Angles, Flats, mould work, curing etc. complete(Precast Heavy duty Cover)	90.00	2681.76	NO	241358.40
	S.O.R.-HOUSING R & B (2023-24), Item no. 76 (A)				
14	Providing & Installation of barricades including supplying painting with flourescent paint & fining CGI sheets 24 SWG of 1.0 mt height and M.S. posts, angle the same after completion of work as directed by Engineer as per site requirement.	50.00	220.00	S.M.	11000.00
15	Taking photographs of work in progress and submit with each R.A.Bill. Photographs shall cover details of locations of the activity of work in progress. The photographs shows the location in writing The Contractor shall submit photographs with Album in a .	40.00	30.00	Set	1200.00
		Net Total			1861344.40
	Add 10 % as per STD. COM. R. No.2160/2025 Dt. 20/11/2025 Rs.				186134.44
		Total			2047478.84
		CGST 9%			184273.10
		SGST 9%			184273.10
		Total			2416025.03
TOTAL GROSS ESTIMATE AMOUNT IN Rs.					2416026.00

-Sd-

Executive Engineer

South West (Athwa) Zone

Surat Municipal Corporation