Surat Municipal Corporation
New East (Sarthana)Zone
Quotation Inquiry form

QUOTATION NO. --		DATE:	03 / 11 /2026
NAME OF WORK	Electrification work of Newly constructed Shed at Pasodara Prathmik School No-383, falls under New East Zone (Sarthana)		
ESTIMATED AMOUNT (with GST):	61,000.00	EMD AMOUNT:	Rs.610/-
VALIDITY PERIOD :	120 Days	Agency Category :	Supplier/Dealer/Distributor
REQUIRED DOCUMENTS	(1) Permanent Account Number (PAN) Copy (2) GST registration Certificate (3) Experience Certificate		
TENDER AVAILIBILITY	-		
ISSUING AUTHORITY	Executive Engineer, New East(Sarthana) Zone, Surat		
ISSUING OFFICE	New East(Sarthana)Zone, Besides Sankalp Residency, B/h Shyamdham Temple, Sarthana,Surat-395013.		
INVITING AUTHORITY	Executive Engineer, New East (Sarthana)Zone, Surat		
SUBMISSION DATE	Last date: 18 / 11 / 2026		Time : 06.00 P.M.
SUBMITTED TO,	EXECUTIVE ENGINEER NEW EAST(SARTHANA) ZONE, BESIDES SANKALP RESIDENCY, B/H SHYAMDHAM TEMPLE, SARTHANA,SURAT-395013		

G.S.T. WILL BE APPLICABLE IN ACCORDANCE WITH THE PREVAILING NORMS OF GOVERNMENT.

GST clause for construction/ erection/ commissioning/ installation/ pairs/maintenance/ renovation/ fabrication of structure including building (means all works contract/ turnkey project/supply of material/goods)

GST(Goods & Service Tax) has come in existence from 1st July 2017 Contractor / Successful Bidder is bound to pay any amount of GST prescribed by the Govt. of India as per the Terms of Contract agreed upon during the course of execution of this Contract.

During the course of execution of Contract if there is any change in Rate of GST (Goods & Service Tax) by the Government the same shall be reimbursed / recovered separately by SMC, subject to the submission of Original Receipt / Proof for the amounts actually remitted by the Successful Tenderer / Contractor to the Competent Authority along with a Certificate firm Chartered Accountant of Contractor / Successful Bidder certifying that the amount of GST paid to the Government and the same shall be intimated / submitted / claimed within 30(Thirty) Days from the date of payment Remittance of GST within stipulated period shall be the sole responsibility of the Successful Bidder / Contractor, failing which , SMC may recover the amount due, from any other payable dues with SMC and decision of Municipal Commissioner shall be final and binding on the Contractor/ Successful Bidder in this regard Further, the nonpayment of GST to the Government may lead to the termination of contract and forfeiture of Security Deposit / Performance Guarantee Amount.
If imposition of any other new Taxes/Duties/Levies/Cess or any other incidentals etc. or any increase in the existing Taxes/Duties/Levies/Cess or any other incidentals etc. (Excluding GST) are imposed during the course of the contract. The same shall be borne by the Contractor/ Successful Bidder only, in no case SMC shall be liable for the same.

	SIGNATURE OF ISSUING AUTHORITY	
	-sd-	
	Executive Engineer New East (Sarthana) Zone Surat Municipal Corporation	

Executive Engineer
New East(Sarthana)Zone

Surat Municipal Corporation
New East(Sarthana)Zone Besides Sankalp Residency, B/h Shyamdham Temple, Sarthana,Surat-395013.
☎6359909506,6359909606

QUOTATION INQUIRY

New East Zone/Tech./No.7154
Dtd.: 03 / 11 /2026

To,
....,
....,
....,

Sub:- Electrification work of Newly constructed Shed at Pasodara Prathmik School No-383, falls under New East Zone (Sarthana)

Dear Sir,

Sealed quotations duly super scribed the subject name and returnable on or before Dt.18 /11/2026 to the office of the undersigned is invited for following Work: -

Quotation

Sr. No.	LOCATION	Description	Qty.	Unit	Price per Unit (Without GST)	Total Amount (Without GST)
1	Electrification work of newly constructed Shed at Pasodara Prathmik School	Point wiring for Light / Bell with 2-1.5 sq.mm & earth wire of 1.5 sq.mm (Green) both are of ISI marked 1.1 KV grade FRLS PVC insulated multi strand copper wires up to 10 mtr length , in below type of pipe erected with 6A Modular type switch / bell push & accessories and earth continuity of following type, erected on PVC/Metallic/Wooden box, single mounting base frame covered with textured/metallic/white front plate modules erected on / in wall / ceiling as per pipe erected, with necessary Lamp holder/ceiling rose / H.D.Connector as directed.(a) with medium class Rigid PVC pipe and accessories erected flushed on wall/ceiling complete Cat. III **Make- Finolex / Polycab / Kei / Havells/ RR Kabel**	13.00	Point		
2		Point wiring for Tissino / Modular secondary light point with 2-1.5 sq.mm & earth wire of 1.5 sq.mm (green) both are of ISI marked 1.1 KV grade FRLS PVC insulated multi strand copper wires, in below type of pipe to be erected complete with earth continuity and necessary connection with primary light with accessories erected on Metal / PVC / wooden box covered with 3 mm thick PC(Polycarbonate) / Acrylic sheet for open / concealed wiring. with necessary Lamp holder / ceiling rose / H.D.Connector as directed. (a) with medium class Rigid PVC pipe and accessories erected flushed on wall/ceiling complete **Make- Finolex / Polycab / Kei / Havells/ RR Kabel**	2.00	Point		
3		Point wiring for FAN with 2-1.5 sq.mm & earth wire of 1.5 sq.mm (Green) both are of .ISI marked 1.1 KV Grade FRLS PVC insulated multi strand copper wires up to 10 mtr length, in below type of pipe erected with 6A Modular type switch and hum free EME step type electronic fan regulator mounted and accessories with earth continuity of following type erected on PVC / Metallic/Wooden box, single mounting base frame covered with textured/metallic/white front plate modules erected on / in wall / ceiling as per pipe erected. with necessary ceiling rose / H.D.Connector as directed.(a) with medium class Rigid PVC pipe and accessories erected flushed on wall/ceiling complete Cat. III **Make- Finolex / Polycab / Kei / Havells/ RR Kabel**	6.00	Point		
4		Supplying and erecting LED indoor fittings with LEDs of wattage 0.2 Watt to 0.5 Watt assembled on single MCPCB, with housing used as a heat sink shall be made of thick sheet Steel conforming to IS: 513/CRCA/ aluminium die cast powder coated and high U.V. & corrosion resistance with diffuser with company mark/name 160V to 270V, Power Factor more than 0.95, THD < 15%, CCT 3000 K to 6500K, Luminaire efficacy> 85	15.00	Each		

		lumens/watt ,LED driver efficiency > 85 % (fitting required LM-79 & LM-80 Certificates)(NOTE: Below description have shown ranges of Wattage capacity of LED fittings.The Engineer incharge may select any wattage capacity between the ranges shown.) (A) Tube Light with integral driver (iv) 22-24 Watts, Surge - 2KV,IP-20, conventional 4 feet Cat-lll **Make- Keselec, Osram, Philips, Trilux, Wipro**				
5		Providing & erecting Approved make Power Saving 50 Watt Ceiling Fan with double ball bearing ISI mark with Condenser 230 volt A.C. 50 Hz 1200 mm sweep complete having 3blades with aluminium blades with , canopy & 30 cm. down rod erected with earthing.(Make shall be approved by Engineer in charge))	6.00	Each		
6		Supplying and erecting 19 / 20 mm. nominal bore Medium Class M.S. Pipe down rod erected duly painted for fan complete with proper insulation without leakage and earthing.	6.00	Mtr.		
7		Providing and erecting Mains with 1.1 KV grade FRLS PVC insulated ISI marked stranded Copper conductor wire in following type of pipe to be erected concealed in /flushed on wall/ceiling, with 1.5 sq. mm copper conductor FRLS PVC insulated stranded wire of green colour for earth continuity of following size (A) With medium class Rigid PVC pipe and accessories (a) 2 wire 1.5 sq. mm	200.00	Mtr.		
8		Providing and erecting Mains with 1.1 KV grade FRLS PVC insulated ISI marked stranded Copper conductor wire in following type of pipe to be erected concealed in /flushed on wall/ceiling, with 1.5 sq. mm copper conductor FRLS PVC insulated stranded wire of green colour for earth continuity of following size (A) With medium class Rigid PVC pipe and accessories (b) 2 wire 2.5 sq. mm	20.00	Mtr.		
9		Point wiring for Individual Plug with & earth wire of 1.5 sq.mm (Green) both are of ISI marked 1.1 KV grade FRLS PVC insulated multi strand copper wires up to 10 mtr length, in below type of pipe erected complete with Modular type switch & 5 pin Plug erected on PVC / Metallic/Wooden box covered with appropriate front plate modules erected on / in wall / ceiling as per pipe erected with following type of accessories. [I] For 6A Plug and 6 a switch with 2-1.5 sq.mm Cu. Wire from nearby switchboard/mcb db board (a) with medium class Rigid PVC pipe and accessories erected flushed on wall/ceiling complete Cat. III	5.00	Each		
10		Point wiring for on board Looped Plug with 6A Modular type switch & 5 pin socket erected on PVC / Metallic/Wooden box, single mounting base frame covered with textured / metallic/white front plate modules erected on / in wall / ceiling with following type accessories Cat. III	0.00	Each		
11		Providing & erecting Switch board for Computer or electric apparatus consisting of following modular type accessories mounted with PVC / Metallic concealed/open box with single mounting base frame covered with textured/metallic /white front plate,modules erected with necessary connections as directed 1 no. 6A/16A universal plug-switch combined. 3 nos. 6A Switch 3 nos. 6A 5 pin Plug For Modular Type Accessories Cat.III	3.00	Each		
12		Supplying & erecting XLPE(IS:7098)(I)-88 ISI unarmoured copper cable 1.1 KV grade to be erected as directed of following size.(E) 3 core 2.5 Sq. mm	40.00	Mtr.		
13		Providing & erecting 240 V MCB double pole switch for motor & inductive load (C Curve) having 10 KA breaking capacity & confirms to IS : 8828 in existing box having following capacity (A) 6 to 32 Amp. Cat.III	2.00	Each		
14		Plastic enclosure fitted with DIN rail suitable for incorporating One / Two nos. MCB	2.00	Each		
					Total Amount(Without GST):	
					Add 18% GST	
					Total Amount for SITC (With GST):	
					Total Amount for SITC(With GST) in Words:	

- Bidder must be use materials as per vendor list.
- Vendor List

Sr.No.	Item	Approved Make	Make Offered By Contractor
1	Other LT Switchgear	Siemens, Schneider, ABB, Hager, Legrand	
2	MCB, ELCB, & MCB Distribution Boards	Hager, Siemens, Schneider, ABB, Legrand	
3	Aluminium XLPE Armored Cables	R.R. Kable, Havells, Finolex, KEI	
4	Aluminium& Copper XLPE Un-armor Cables	R.R. Kable, Havells, Finolex, KEI	
5	Flexible Wire	R.R. Kable, Havell's, Finolex,	
6	Rigid PVC Pipe & Accessories	Precision, Nihir	
7	Lighting Fixtures, Indoor & Outdoor	Keselec, Osram, Philips, Trilux, Wipro	
8	Ceiling Fan	Havells, Crompton, Usha, Bajaj, Khetan, Orient, Ortem,	

Other Terms & Condition

- The rates should be excluding of GST & including of other taxes/duties/loading-unloading/Labor including Transporting.
- Validation of Quotation will be 120 days from the last date of submission of Quotation.
- Bidders are suggested to visit the site location before quoting this quotation and for any further query, bidder can contact Light department of New East (Sarthana) Zone, SMC.
- The Offer shall be submitted for the makes as mentioned in the quotation. The offer for the makes/s other than shown in the quotation will be rejected out rightly.
- Contractor will have to submit **Security deposit at the rate of 2.5 %** of work order value within 10 days from the date of work order otherwise; penalty @ 0.065% of the amount of security deposit per day of delay shall be levied.
- Successful Contractor have to execute Agreement, Surety & Undertaking on the non judicial stamp paper of Rs.300/- each purchased from Surat city only.
- Any "price variation clause" shall not be accepted.
- If contractor fails to complete above work than penalty @ 0.2% of amount of unexecuted work per day delayed should be recovered from bill. Maximum delay penalty shall be recovered 10%of unexecuted amount of work order.
- Any Other Miscellaneous items, which are necessary to complete the work should also be considered into the scope of work and needs to carry out by bidder/contractor free of cost.
- All required materials, tools, tackles and men power for the job shall be brought by the Contractor.
- Payment shall be made after satisfactory Completion of whole work in all respect and submission of required documents and invoices of the work.
- All The Central, State and Local government rules and regulations including Safety shall be strictly followed by the Contractor.
- The name of work i.e.“ **Quotation for the work of ……”** must be mentioned on the envelope.

Thanking You,

-sd-
Executive Engineer
New East(Sarthana)Zone
Surat Municipal Corporation

SIGNATURE & SEAL OF CONTRACTOR