સુરત મહાનગરપાલિકા

ટ્રાફિક–બી.આર.ટી.એસ.
પ્રોજેકટ સેલ

ગ્રાઉન્ડ ફ્લોર, અલથાણ સ્વીમીંગપુલ,
ડી.આર.બી. કોલેજની સામે,
ન્યુ સીટી લાઈટ રોડ, સુરત–૩૯૫૦૧૭
મો.નં. : ૯૮૭૯૫૪૦૦૪૪
E-mail: exen.traffic@suratmunicipal.org

ટ્રાફિક–બી.આર.ટી.એસ. પ્રોજેકટ સેલ /આ. નં./૧૬૦૯
તા.૦૪/૧૧/૨૦૨૬

–:સંમતિ પત્રકઃ–

પ્રતિ,

.....
.....
.....
.....

જાહેર પરિવહન પ્રવૃતિ સમિતિ ઠરાવ નં.૪/૨૦૨૩, તા.૨૮/૦૨/૨૦૨૩

વિષય :– સુરત મહાનગરપાલિકા ધ્વારા જાહેર પરિવહન તથા પર્યટનને પ્રોત્સાહન આપવાના ભાગરૂપે આગામી દિવસોમાં ડબલ ડેકર બસ સેવાના સંચાલન માટે મુસાફરોની સગવડતા હેતુસર વિવિધ નકકી થયેલ સ્થળો પર માર્કર પોલની સુવિધા આપવા બાબત.

મહાશય,

ઉપરોકત વિષયના અનુસંધાને જણાવવાનું કે, ડબલ ડેકરની ૦૨(બે) બસ સેવાના ભાગરૂપે માર્કર પોલ લગાવવાના કામે જાહેર પરિવહન પ્રવૃતિ સમિતિ ઠરાવ.નં. ૪/૨૦૨૩, તા.૨૮/૦૨/૨૦૨૩ થી મંજુર થયેલ ઠરાવના ભાવે અને શરતોને આધીન ઠરાવવામાં આવેલ વિગતોએ રૂા.૧,૦૦,૦૦૦.૦૦ ની મર્યાદામાં આગામી ૦૬ (છ) માસ માટે કામગીરી કરવા જો આપશ્રી રસ ધરાવતા હોવ, તો આપશ્રીનું સંમતિપત્રક **તા.૧૭/૧૧/૨૦૨૬** સુધીમાં નીચે સહી કરનારને ખુલ્લા કવરમાં ટ્રાફિક–બી.આર.ટી.એસ. પ્રોજેકટ સેલની કચેરીમાં મોકલવા ઘટતુ કરશો.

બિડાણ :– (૧) જાહેર પરિવહન પ્રવૃતિ સમિતિ ઠરાવ.નં. ૪/૨૦૨૩, તા.૨૮/૦૨/૨૦૨૩
(૨) શીડયુલ–બીની નકલ

SD/-
03/11/2026
કાર્યપાલક ઈજનેર
ટ્રાફિક સેલ
સુરત મહાનગરપાલિકા

સુરત મહાનગરપાલિકાની જાહેરપરિવહન પ્રવૃત્તિ સમિતિની તા.૨૮–૨–૨૦૨૩ ના રોજ મળેલ સભામાં નીચે મુજબનો ઠરાવ પસાર થયો હતો :–

* * * * * *

મ્યુ.કમિશ્નરશ્રીના તા.૬–૨–૨૦૨૩ ના પત્ર નં.સીમીસ/૯/૧૮ થી વિદિત થઈ, સાઉથ ઝોન, નવા માર્કર પોલ ઉભા કરવાના તેમજ હયાત બસ સ્ટોપ/માર્કર પોલ સહિત સીટી બસ રૂટ ડીટેઈલ્સ પ્રદર્શિત કરવાના કામે ટેન્ડર નોટીસ પ્રસિધ્ધ કરી માંગવામાં આવેલ ટેન્ડરોના સંદર્ભમાં નિયત સમયમર્યાદામાં આવેલ કુલ–૩ ટેન્ડરો પૈકી કવોલીફાય થયેલ કુલ–૨ ટેન્ડરો પૈકી નીચા ભાવના ટેન્ડરના ટેન્ડર૨ વેદાંશી સેફટી એન્ડ સાઈનનું ટેન્ડરની અંદાજી રકમ રૂા.૨૪,૯૬,૯૮૦–૭૫ થી ૮.૧૬% નીચું એટલે કે રૂા.૨૨,૯૩,૨૨૭–૧૨ નું બિનશરતી ટેન્ડર વ્યાજબી જણાતુ હોય કબુલ રાખવાનું તથા તેઓ સાથે કરારનામુ કરવા મ્યુ.કમિશનરશ્રીને અધિકૃત કરવાનું ઠરાવવામાં આવે છે.

ઠરાવ નં.૪/૨૦૨૩ સર્વાનુમતે મંજુર.

સ.૨.મ્યુ.કમિશનરશ્રી પ્રતિ,

Received On
Dt. ૨૭/૨/૨૩

મ્યુ.સેક્રેટરી,
સુરત મહાનગરપાલિકા
તા.૨૮–૨–૨૦૨૩.

ટ્રાફિક BRTS પ્રોજેક્ટ સેલ
ઈનવર્ડ નં.:–4374
તારીખ :–03/03/23

નં.સીમીસ/૯/૧૮/૨૫
UDT સ.૧/૩/૨૦૨૩

AE (RAC) W/OS
1/3/23

A-C-E
1/3/23

EAMC (BRTS)

આર.ગે.સી./૨૮/૧૯૬૯
૧/૩/૨૦૨૩

Name of Work: As part of its efforts to promote public transportation and tourism, proposes to provide marker poles at various designated locations for the convenience of passengers, in connection with the operation of a double-decker bus service in the coming days in Surat City.

Schedule - B

Item No.	Particulars	Qty.	Rate Rs. Ps.	Unit	Amount Rs. Ps.
1	Demolition and disposal of unserviceable materials with all lead and lift				
	(i) Unreinforced cement concrete	1.00	406.17	cumt	406.17
	(ii) RCC work	1.00	705.23	cumt	705.23
2	Demolition of brick work and stone masonary including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift				
	(i) in cement mortar	1.00	366.93	cumt	366.93
3	Exacavation for foundation include. Sorting out & stacking of useful materaials & disposing of the excavated stuff upto 50 mt. Lead & all lift, watering etc. Comp.(With Manual Labour)				
	(A) Loose or soft soil				
	(1) Up to 1.5 Mt. depth	59.00	150.24	cumt	8,864.16
4	Providing & laying cement concrete **1:1.5:3** (1 cement : 1.5 sand : 3 graded stone agg. 20 mm nominal size) & curing complete including cost of form work but excluding cost of reinforcement for reinforced concrete work in : **(A) Foundation, footing, Base of columns and Mass concrete.**				
	A) Foundation and plinth	59.00	4,127.14	cumt	2,43,501.26
5	Providing erecting and fixing in position structural steel sections of Yst 310 grade of TATA, Kamdhenu, Jindal or Asian confirming to IS:4923 purlins, roof trusses, columns, side runners, ties bracing, framing etc. including all types of base plate, gusset plate, cap plate, bearing plate, stiffner, cleats etc. complete and structural steel confirming to IS:226 including necessary pipes, rolled joists, channels, angles, tees, MS flats, angle cleats, gusset plate, bright bars, chequred plates, criss cross plates as per required thickness including cutting, welding, riveting as per structural details and good engineering practice grinding and cleaning the members as specified by Engineer in charge. (only finihed measurements will be paid for billing purpose). No extra payment shall be made for grouting that has to be done under the base plate to get full bearing on supporting sub statra. The paint shall be oil paint in three coats to get an even look over a coat of red lead paint as per the instruction of the engineer incharge. The rate shall also be inclusive of screw, bolts, nuts,washers, hinges, pivots.	4950.00	81.86	kg	4,05,207.00

Item No.	Particulars	Qty.	Rate Rs. Ps.	Unit	Amount Rs. Ps.
6	Fabricating, supplying, cutting, bending and fixing GI plain sheet JINDAL/HINDALCO make or equivalent of 1mm /2mm/3mm thickness fixed to MS framing with S.S. screws in counter sunk/ S.S. rivets, S.S. washers, necessary accessories and hardware complete as per detailed drawing and design. (Only finished measurements will be paid for billing purpose, M.S. framing shall not be part of this item.) The sheet type will be finalised by the Engineer in charge.	15150.00	83.00	kg	12,57,450.00
7	Providing, Desiging and Sticking Vinyl with eight color eco solvent epson printing. The Vinyl to be of 100 microns 3M media. The vinyl to be laminated by 80 microns film after the printing and before sticking. The sample of the same needs to be approved by the consultant. To be stuck in line and level without any crease or bubbles on the prelaminated board / acrylic sheet using 3M adhesives surface. The graphics shall be provided by the consultant. The contractor to check the graphic size and the available surface before printing. The 3M vinyl signage shall be stuck firmly on 3mm thick SS 304L grade sheet as per designs. The sheet shall be firmly fixed using SS 20mm dia studs as per the designs of the consultants fixed in correct line, level and plumb. The rates shall be excluding SS sheet but including signage material including fixing and other related costs like transportation, electricity etc.	620.00	920.00	sqmt	5,70,400.00
8	Providing, Designing and fixing of flex signage with printing for external use and with uniformity so that the same can be backlit. The flex is to be fixed neatly with adhesive to M.S. frame, stretched in line and level. The flex to be 15 ounce of LG Media for backlit and printed on vientech machine. The graphic size is to be cross checked with the area available before printing. The graphic shall be prepared as per instruction of Engineer In-Charge.	4.00	700.00	sqmt	2,800.00
9	Removing of Eco Vinayl from Existing Marker poles	650.00	11.20	sqft	7,280.00
				Total :	**24,96,980.75**