Executive Engineer (Workshop/Mech.)
Public Infrastructure Cell
Surat Municipal Corporation

Public Infrastructure Cell,
1st Floor, School No. 16, Nr. Soham Circle,
Althan Canal Road, Surat.

exen.ele.pic@suratmunicipal.org

ONLINE QUOTATION **P.I.Cell/Outward/No.1095**
Date. 04/11/2026

Public Infrastructure Cell of Surat Municipal Corporation hereby invites rates to carry out following work

Sub.: Dismantling, shifting, reinstallation, testing and commissioning of Air Conditioning Machines from DCHC to Head of the department of different faculties of the SMIMER Hospital and college of Surat municipal corporation.

(A.1) Quote:

Sr	Item / Description	Unit	Qty	Estimated Unit Rate (Without GST)	Total (Without GST)
1.	Dismantling the existing split type air conditioner of any type and capacity safely without any damages and making the site clear.	5	Unit	282.8	1414.00
2.	Installation Charge for Split Air Conditioner Indoor & Outdoor Unit Unit (E) for 1.5/2 ton capacity- 1/3Phase	22	No	1630.14	35863.08
3.	Supplying and erecting insulated pair of soft copper tubing open or concealed including power and control cable, necessary PVC drain pipes for Split/Cassette AC machine up to 4 TR capacity	100	Rmtr	1158.47	115847.00
4.	Supplying colorless non inflammable refrigerant Gas R-410	45	Kg	925.16	41632.20
5.	Supplying and installing MS angle, powder coated / Painted standard type of wall/floor stand mount for outdoor unit of split AC of following capacity, erected with necessary hardware materials as directed.				
	(B) 35mm*35mm*5mm thick M.S angle suitable for above 2 TR to 4 TR Capacity of ac machine	22	No	1510.96	33241.12
6.	Providing following type of Modular Type Accessories mounted with PVC / metallic/Wooden box, single mounting base frame covered with textured / metallic/white front plate, modules erected with necessary connections as per site situation directed by Engineer In charge.				
	(22) 16/20/25 Amp. Modular Starter for Motor / A.C. Unit Complete Cat-III	22	No	497.93	10954.46
7.	Replacing starting capacitor of 80 to 120 µF for 1.5 H.P. compressor motor of A.C. machine	12	No	326.23	3914.76
8.	Replacement of defective remote control hand set with new battery cells.				
	(A) Split Unit - Local make	6	No	847.39	5084.34
9.	Overhauling and servicing the Split type A.C.MACHINES by Chemical cleaning of the condenser, cooling coil etc. by veniclean/Eq. material, water & cleaning all necessary parts and putting the machine in working order.	22	Job	514.09	11309.98
10.	Providing and installing threaded bolts, anchor fastening, supporting plate etc. to rest the copper piping	50	Kg	120.00	6000.00
11.	Providing and Erecting PCB Circuit of Indoor Unit for Inverter Type 3 Star rating Split A.C. Machine up to 2.2 TR Capacity.	6	No	3639.03	21834.18
12.	Supplying & erecting FRLS-XLPE(IS:7098)(I)-88 ISI unarmoured copper cable 1.1 kV grade to be erected as directed of following size.				
	(E) 3 core 2.5 Sq. mm	220	Rmtr	171.70	37774.00
13.	Carry out RCC Core cutting- up to 100 mm dia./200mm thick Wall/beam/slab with providing PVC pipe of 3 mm thick inside and necessary finishing on both ends of wall .	12	Job	1199.88	14398.56
	TOTAL ESTIMATED COST (WITHOUT GST & WITH LABOUR CESS) Rs.			**3,39,267.68**	

(B) Scope of work:

(B.1) The stated work is proposed under renovation & development of sonography department at the vacant place of radiology department of SMIMER hospital.
(B.2) The proposed work includes dismantling of existing split type Cassette and High Wall units, shifting them to the radiology department, installation, testing and commissioning of these units. (B.3) The work shall be carried out as per related norms, conditions and latest practice laid out for these works.
(B.4) Only qualified and experienced technicians shall be deployed to carry out these works.
(B.5) SMC will not be responsible for any type of accident, injury or even death of the staff deployed by the contractor and no compensation shall be paid thereof.

Seal & Signature of the Bidding Agency

(C) General terms:

(C.1) Concern agency shall have to fill the rates in this format / page only. The offered rate shall be in form of % Above / Below / at par rates in comparison to the estimated amount shown in above table.

(C.2) **The offer must be submitted to: The Chief Accountant, Accounts Department, Surat Municipal Corporation, Tap Bhavan, Tapipura, Surat on or before Dt.21.11.2026.**

(C.3) **The mode of submission: Postal RPAD or Postal Speed Post**

(C.4) this page filled with rates shall be sealed in a cover. Each page of this quotation must be stamped and signed by the sending agency.

(C.5) **Following details should be written on the sealed cover:** (1) Name of work (2) Address of the recipient (The Chief Accountant, Accounts Department, Surat Municipal Corporation, Tap Bhavan, Tapipura, Surat) (3) Name and address of the sender (As actual) (4) Last date to submit the quotation i.e. Dt.23.10.2026

(C.6) The successful agency shall have to submit a security deposit @ a rate of 2% of the order value amount within 15 days from the award of the work order. The DD / pay order shall be issued in favor of "Commissioner, Surat Municipal Corporation" and shall be payable at Surat. A delay penalty at a rate of 0.065% of the SD value per day will be imposed for delayed days.

(C.7) The successful agency shall have to bind in contract with SMC. The agency shall have to submit three non-judicial stamp papers each costing Rs.300/- for agreement, surety and undertaking respectively.

(C.8) Overall lowest quotation shall be considered.

(C.9) Payment: 100% payment shall be made after completion of the entire work.

(C.10) Deductions: All the payments and deductions shall be made as per prevailing rules and standard practice of SMC.

(C.11) The defect liability period for this work shall be 12 months.

(C.12) Completion period: 15 days as mentioned in the work order.

(C.13) GST shall be paid extra as actual.

(D) THE QUOTE (To be filled by the agency)

I / We ..... (Name of the person), owner / proprietor / partner / authorized representative of the ..... (Name of the Firm) having address at ..... hereby agree to carry out the stated work as per the terms, conditions and scope of work laid in this quotation and at ..... % Above / Below / At Par compared to the estimated rates mentioned in table.

Executive Engineer (Workshop / Mech.)
Public Infrastructure Cell
Surat Municipal Corporation

Seal and Signature of the bidder

Contact No.

Seal & Signature of the Bidding Agency