સુરત મહાનગરપાલિકા
પૂર્વ ઝોન (વરાછા) – એ

કાર્યપાલક ઈજનેર
પ્રજાપિતા બ્રમ્હાકુમારી માર્ગ,
સૈફી સોસાયટીની બાજુમાં,
પંચવટી વાડી સામે,
લંબે હનુમાન રોડ, વરાછા, સુરત

ફોન : (ઓફીસ) ૨૫૪૭૭૫૦, ૨૫૫૧૩૬૩
ઈ – મેઈલ : eastzonelight@gmail.com

સંમતિ પત્ર

પુર્વઝોન–એ/આઉટ/નં.,૪૨૪૧
તારીખ :– ૨૧/૧૧/૨૦૨૬

પ્રતિ,
.....
.....
.....
.....

વિષયઃ– પુર્વ (વરાછા) ઝોન –એ ના સુમન હાઈસ્કુલ નં. ૨, ખાતે ૧૫૦/૧૫૦ લીટર કેપેસીટીના વોટર કુલર સપ્લાય કરી, પ્રસ્થાપિત કરી કાર્યરત કરી આપવા બાબત.

સંદર્ભ :– (૧) મા. ડેપ્યુટી મ્યુની. કમિશનરશ્રી સાઉથ ઝોન–એ ની તા.૦૨/૦૯/૨૦૨૬ ના રોજની મંજુરી.
(૨) સાઉથ ઝોન–એ નાં મંજુર ભાવનો વર્કઓર્ડર નં. સા.ઝોન–એ/ટેક/નં.૧૧૮, તા.૦૯/૦૯/૨૦૨૬
(૩) મા. કાર્યપાલક ઈજનેરશ્રી(પુર્વ (વરાછા)ઝોન– એ)ની મંજુરી તા.૧૬.૧૧.૨૦૨૬

મહાશય,

ઉપરોકત વિષય અંતર્ગત પુર્વ (વરાછા)ઝોન– એ ના સુમન હાઈસ્કુલ નં. ૨, મોહનની ચાલ, માતાવાડી ખાતે૧૫૦/૧૫૦ લીટર કેપેસીટીના વોટર કુલર નંગ ૦૧ સપ્લાય કરી, પ્રસ્થાપિત કરી કાર્યરત કરી આપવા કામગીરી ઉકત સંદર્ભ– (૧) અને (૨) હેઠળનાં મંજુર ભાવે અને શરતે આ સાથે સામેલ મંજુર શિડયુલ અને શરતો મુજબ કુલ રૂા.૫૬,૬૭૩.૭૩ (પ્રવર્તમાન GST અલગથી) નાં ખર્ચે કરવા ઈચ્છુક હોવ તો, તા.૦૪/૧૨/૨૦૨૬(૧૮.૦૦ કલાક) સુધીમાં ઉકત વિષયનાં ઉલ્લેખ સાથે આપના લેટર હેડ પર સંમતિ પત્ર, આ સાથે સામેલ પ્રાઈઝ શિડયુલમાં આપના સહી, સિકકા સાથે 'કાર્યપાલક ઈજનેર,પૂર્વ ઝોન (વરાછા)–એ , પ્રજાપિતા બ્રહમકુમારી માર્ગ, સૈફી સોસાયટીની બાજુમાં, પંચવટી વાડી સામે, લંબેહનુમાન રોડ, વરાછા, સુરત' ખાતે પહોંચતું કરવા પ્રબંધ કરશો.

સમય મર્યાદા વિત્યા બાદ કોઈ પણ અરજી / સંમતિ પત્ર ધ્યાને લેવામાં આવશે નહીં, જેની નોંધ લેશો.

કાર્યપાલક ઈજનેર
પુર્વ ઝોન(વરાછા)–એ
સુરત મહાનગરપાલિકા

SEAL & SIGNATURE OF THE CONTRACTOR

SURAT MUNICIPAL CORPORATION
EAST ZONE-A (VARACHHA)
LIGHT DEPARTMENT

ONLINE CONSENT LETTER NO. :- EXECUTIVE ENGINEER/EZ-A/18/2026-27,DT. 21.11.2026

SUB - SUPPLY, ERECTION, TESTING & COMMISSIONING OF 150/150 LTR CAPACITY WATER COOLER FOR SUMAN HIGHSCHOOL NO.2, AT EAST (VARACHHA) ZONE-A.

Ref:-(1) Sanction rate of South Zone,-A (UDHNA) W.O no.118, Dt.09/09/2026

SANCTIONED RATE					
SR. NO	ITEM DESCRIPTION	UNIT	QTY	Unit. Rate (Without GST)	Total Rate (Rs.) (Without GST)
1	SUPPLY, ERECTION, TESTING & COMMISSIONING OF 150/150 LTR CAPACITY WATER COOLER FOR SUMAN HIGHSCHOOL NO.2, AT EAST (VARACHHA) ZONE-A Water Cooler technical specification as per attached sheet.	Ea.	1	56,673.73	56,673.73
TOTAL (RS.)					56,673.73

Tenderer shall have to follow all the terms & conditions for this offer, failing which the quotation is liable to rejection.

Terms and Conditions:

1. After bidding process, Any deviation in quoted rate, terms and condition shall not be entertained later.
2. SMC will have right to reject the offer without any reason. Decision of competent authority of Surat Municipal Corporation shall be final.
3. Bidder will have to complete above work with all respect within 10 days from order of Light dept. of SMC. If contractor fails to complete above work than penalty @ 0.2 % of amount unexecuted work per day delayed should be recovered from your bill. Maximum delay penalty shall be recovered 10% of unexecuted amount of sub work order
4. SMC will not pay any transportation charges and also not provide any type of assistance which carrying out above mention work.
5. No payment shall be made in advance
6. 100% payment shall be released after completing SETC work as per requirement and submission of Bill. (Initial Security deposit should be released after defect liability period.)s
7. Defect liability period of the work is one year after installing 150/150 Ltr Water Cooler , Under defect liability period Spares/components needed to be replaced or repaired shall be done by contractor. Contractor must replace faulty spare with genuine spare only.
8. Corporation will not issue any 'C' or 'D' form.
9. The successful contractor shall also be required to submit security deposit 2.5% of awarded amount and also enter into contract agreement on Gujarat Stamp Paper purchased from Surat worth Rs.300.00 on getting the order. However, the stamp duty at prevailing rate shall be applicable if revised by Government.

Executive Engineer
East (Varachha) Zone-A
Surat Municipal Corporation

I/we_____

_____

_____am/are agree to do SETC of 150/150 LTR WATER COOLER at SUMAN HIGHSCHOOL NO.2, at East (Varachha) Zone-A with terms & condition of above ref. 1 sanctioned rates, worth Rs. 56,673.73 Ps. (in word Rupees Fifty-six thousand six hundred seventy-three Rupees and seventy-three paisa only).

SEAL & SIGNATURE OF THE CONTRACTOR:-

SURAT MUNICIPAL CORPORATION

EAST ZONE-A (VARACHHA), Light Department

TECHNICAL SPECIFICATIONS

VENDOR'S LIST

Sr.No.	Equipments/ Accessories	Vendor/Make list
1	WATER COOLER	BULE STAR, USHA,VOLTAS.

Scope of work:-

1. Contractor has to get approval of the make/ material out of list mention above before supply.
2. All Plumbing work like Drain pipe and other piping works etc. required for execution of this work shall be in the scope of contractor. No extra payment shall be made to contractor for this.
3. Contractor shall have to produce an authorization letter from concern manufacturer/ distributor for post purchase service support.
4. Contractor shall have to provide one year guarantee for all the products offered. Guarantee period shall be started after completion of testing, commissioning and handing over the system to SMC.
5. All types of transportation inside and outside of SMC premise shall be carried out by contractor without any extra cost.
6. During defect liability period (12 months from the date of satisfactory commissioning & till the handing over to O & M Contractor), contractor must replace/ repair all equipment/ components & accessories for bad workmanship, manufacturing defects, installation/ commissioning errors or factors. The Compressor Warranty should be as per warranty given by Manufacturer.

Type	**150/150 Ltr**
Cooling Capacity (Ltrs/Hr.)	**150**
Storage Capacity (Ltrs.)	**150**
Nos. of Cold Water Taps	**02**
Refrigerant	**R-134a/R-22 or latest**

Type of Compressor	**Reciprocating/Hermetic type with suction glass cooled motor, equipped with overload Protector.**
Condenser fan	**Propeller type**
Thermostat	**Automatically controls the temperature**
Power Supply	**230 Volts,50Hz, 15A, 3-pin plug with proper earth connection**
Water Supply	**Use pressure reducing valve if required**
Water Connection	**Necessary or as per site requirement Inlet and drain connection should be provided.**
Related IS/BIS	**BIS 1475 (Part-I) 2001 or as per latest**
Warrantee Period	**1 Year**

SEAL & SIGNATURE OF THE CONTRACTOR:-

Executive Engineer
East (Varachha) Zone-A
Surat Municipal Corporation

As per detail specification equivalent to make BLUE STAR Model SDLX