Surat Municipal Corporation
New East (Sarthana) Zone
Quotation Inquiry form

QUOTATION NO. -, 2026-27		DATE:	/ /2026
NAME OF WORK	Internal Wiring/electrification Renovation work at Gosaiji Nagar Prathmik Shala No. 309, managed by the Nagar Primary Education Committee, Under New East (Sarthana) Zone		
ESTIMATED AMOUNT:		EMD AMOUNT:	Rs.2000 /-
VALIDITY PERIOD :	120 Days	Agency Category :	Supplier/Dealer/Distributor
REQUIRED DOCUMENTS	(1) Permanent Account Number (PAN) Copy (2) GST registration Certificate (3) Experience Certificate (4)Electrical Contractor License		
TENDER AVAILIBILITY	120 Days		
ISSUING AUTHORITY	Executive Engineer, New East (Sarthana) Zone, Surat		
ISSUING OFFICE	Administrative office, New East (Sarthana) Zone, Beside Sankalp Residancy, Behind Syamdham Mandir Char Rasta, Sarthana, Surat.		
INVITING AUTHORITY	Executive Engineer, New East (Sarthana) Zone, Surat		
SUBMISSION DATE	Last date: 05 / 12 /2026 Time : 06.00 P.M.		
SUBMITTED TO,	EXECUTIVE ENGINEER NEW EAST (SARTHANA) ZONE, Beside Sankalp Residancy, Behind Syamdham Mandir Char Rasta, Sarthana, Surat.		

G.S.T. WILL BE APPLICABLE IN ACCORDANCE WITH THE PREVAILING NORMS OF GOVERNMENT.

GST clause for construction/ erection/ commissioning/ installation/ pairs/maintenance/ renovation/ fabrication of structure including building (means all works contract/ turnkey project/supply of material/goods)

GST(Goods & Service Tax) has come in existence from 1st July 2017 Contractor / Successful Bidder is bound to pay any amount of GST prescribed by the Govt. of India as per the Terms of Contract agreed upon during the course of execution of this Contract.

During the course of execution of Contract if there is any change in Rate of GST (Goods & Service Tax) by the Government the same shall be reimbursed / recovered separately by SMC, subject to the submission of Original Receipt / Proof for the amounts actually remitted by the Successful Tenderer / Contractor to the Competent Authority along with a Certificate firm Chartered Accountant of Contractor / Successful Bidder certifying that the amount of GST paid to the Government and the same shall be intimated / submitted / claimed within 30(Thirty) Days from the date of payment Remittance of GST within stipulated period shall be the sole responsibility of the Successful Bidder / Contractor, failing which , SMC may recover the amount due, from any other payable dues with SMC and decision of Municipal Commissioner shall be final and binding on the Contractor/ Successful Bidder in this regard Further, the nonpayment of GST to the Government may lead to the termination of contract and forfeiture of Security Deposit / Performance Guarantee Amount.

If imposition of any other new Taxes/Duties/Levies/Cess or any other incidentals etc. or any increase in the existing Taxes/Duties/Levies/Cess or any other incidentals etc. (Excluding GST) are imposed during the course of the contract. the same shall be borne by the Contractor/ Successful Bidder only, in no case SMC shall be liable for the same.

	SIGNATURE OF ISSUING AUTHORITY	
	Executive Engineer New East (Sarthana) Zone Surat Municipal Corporation	

નવે ઈસ્ટ ઝોન(બી)-ઇંજનેરી વિભાગ
આઉટ વર્ડ નં. ૭૩૪૮
તારીખ ૨૫-૧૧-૨૬

Scanned with OKEN Scanner

Executive Engineer

New East(Sarthana)Zone
Surat Municipal Corporation
New East (Sarthana) Zone, Beside Sankalp Residancy, Behind Syamdham Mandir
Char Rasta, Sarthana, Surat.
Ph. : 6359909506 - 6359909606

QUOTATION INQUIRY

To,

.....
.....
.....
.....
.....

નવે ઈસ્ટ ઝોન(બી) ઇન્ટરેસી વિભાગ
આવેટ વર્ક નં. 9388
તારીખ 24-12-25

SUB :- Internal Wiring/electrification Renovation work at Gosaiji Nagar Prathmik Shala No. 309, managed by the Nagar Primary Education Committee, Under New East (Sarthana) Zone.

You are requested to send your offer in a sealed cover with **E.M.D of Rs. 2000/-** in the form of demand draft / banker's cheque in favour of the "Municipal Commissioner, Surat Municipal Corporation" payable at Surat. So as to reach in the office of Executive Engineer [New East(Sarthana)Zone] **on or before Dt. 05 / 12 /2026 up to 6.00 pm**. Please note that the sealed cover shall be super scribed with the name of work " **Internal Wiring/electrification Renovation work at Gosaiji Nagar Prathmik Shala No. 309, managed by the Nagar Primary Education Committee, Under New East (Sarthana) Zone** " The terms & conditions for this offer are as follow, failing which the quotation shall be rejected out rightly.

SR No	Description	Unit	QTY	Rate	Total (Without GST)
1	Point wiring for Light / Bell with 2-1.5 sq.mm & earth wire of 1.5 sq.mm (Green) both are of ISI marked 1.1 kV grade FRLS PVC insulated multi strand copper wires up to 10 mtr length , in below type of pipe erected with 6A Modular type switch / bell push & accessories and earth continuity of following type, erected on PVC / Metallic/Wooden box, single mounting base frame covered with textured/metallic/white front plate modules erected on / in wall / ceiling as per pipe erected, with necessary Lamp holder/ceiling rose / H.D.Connector as directed.				
	(a) with medium class Rigid PVC pipe and accessories erected flushed on wall/ceiling complete Cat. III	Pt.	10		
2	Point wiring for FAN with 2-1.5 sq.mm & earth wire of 1.5 sq.mm (Green) both are of .ISI marked 1.1 kV Grade FRLS PVC insulated multi strand copper wires up to 10 mtr length, in below type of pipe erected with 6A Modular type switch and hum free EME step type electronic fan regulator mounted and accessories with earth continuity of following type erected on PVC / Metallic/Wooden box, single mounting base frame covered with textured/metallic/white front plate modules erected on / in wall / ceiling as per pipe erected. with necessary ceiling rose / H.D.Connector as directed.				
	(a) with medium class Rigid PVC pipe and accessories erected flushed on wall/ceiling complete Cat. III	Pt.	10		
3	Point wiring for Individual Plug with & earth wire of 1.5 sq.mm (Green) both are of ISI marked 1.1 kV grade FRLS PVC insulated multi strand copper wires up to 10 mtr length, in below type of pipe erected complete with Modular type switch & 5 pin Plug erected on PVC / Metallic/Wooden box covered with appropriate front plate modules erected on / in wall / ceiling as per pipe erected with following type of accessories.				
	[I] For 6A Plug and 6 a switch with 2-1.5 sq.mm Cu. Wire from nearby switchboard/mcb db board				
	(a) with medium class Rigid PVC pipe and accessories erected flushed on wall/ceiling complete Cat. III	Pt.	10		

Scanned with OKEN Scanner

	[II] For 16A Plug and 16 amp switch with 2-2 .5 sq.mm Cu. Wire from mcb db board.				
	(a) with medium class Rigid PVC pipe and accessories erected flushed on wall/ceiling complete Cat. III	Pt.	10		
4	Point wiring for on board Looped Plug with 6A Modular type switch & 5 pin socket erected on PVC / Metallic/Wooden box, single mounting base frame covered with textured / metallic/white front plate modules erected on / In wall / ceiling with following type accessories Cat. III	Pt.	30		
5	Providing following type of Modular Type Accessories mounted with PVC / metallic/Wooden box, single mounting base frame covered with textured / metallic/white front plate , modules erected with necessary connections as per site situation directed by Engineer In charge.				
	(5) Electronic hum Free steps EME Fan regulator Cat. III	Ea.	75		
	(7) Blank Plate Single Cat. III	Ea.	50		
	(10) 6/16Amp. Universal socket Cat. III	Ea.	10		
	(13) 6A/10A/16A/20A/25A/32A Single pole Modular MCB Switch Cat. III	Ea.	25		
6	Providing & erecting following type of Modular Type Accessories with necessary connection. As desired by Engineer In charge				
	(1) 6 Amp. SP one way switch	Ea.	200		
	(2) 16 Amp. SP one way switch	Ea.	10		
	(3) 6/16Amp. Universal socket	Ea.	50		
7	Providing & erecting following type of Modular Type Accessories with necessary connection. As desired by Engineer In charge				
	12 Modular Board	Ea.	5		
	12 Modular Plate	Ea.	5		
	16 Modular Board	Ea.	10		
	16 Modular Plate	Ea.	10		
	18 Modular Board	Ea.	20		
	18 Modular Plate	Ea.	20		
8	Providing and erecting ISI mark Medium class RIGID PVC PIPES of following size complete to be erected on/in wall or ceiling erected with necessary PVC fittings & Junction boxes fixed with adhesive solution & Clamps with following dia of pipes, in approved manner as directed				
	(a)20 mm	Mtr.	50		
	(b) 25 mm	Mtr.	50		
9	Providing and erecting Mains with 1.1 kV grade FRLS PVC insulated ISI marked stranded Copper conductor wire in following type of pipe to be erected concealed in /flushed on wall/ceiling, with 1.5 sq. mm copper conductor FRLS PVC insulated stranded wire of green colour for earth continuity of following size				
	(A) With medium class Rigid PVC pipe and accessories				
	(a) 2 wire 1.5 sq. mm	Mtr.	100		
	(b) 2 wire 2.5 sq. mm	Mtr.	100		
10	providing and erecting Mains with 1.1 kV grade FRLS PVC insulated ISI marked stranded Copper conductor wire in following type of pipe to be erected in / on wall / ceiling with 2.5 sq. mm copper conductor FRLS PVC insulated stranded wire of green colour for earth continuity of following size				
	(a) with medium class Rigid PVC pipe and accessories erected flushed on wall/ceiling complete Cat. III	Mtr.	20		
11	Supplying and erecting Flexible PVC insulated multi strand multi core 1.1 kV grade ISI marked copper wires of following size to be erected as directed. (b) 1.00 Sq.mm twin twisted	Mtr.	100		

Scanned with OKEN Scanner

12	Providing & erecting Switch board for Computer or electric apparatus consisting of following modular type accessories mounted with PVC / Metallic concealed/open box with single mounting base frame covered with textured/metallic /white front plate,modules erected with necessary connections as directed1 no. 6A/16A universal plug-switch combined.3 nos. 6A Switch3 nos. 6A 5 pin Plug Cat. III	Ea.	2		
13	Supplying and erecting LED indoor fittings with LEDs of wattage 0.2 Watt to 0.5 Watt assembled on single MCPCB, with housing used as a heat sink shall be made of thick sheet Steel conforming to IS: 513/CRCA/ aluminium die cast powder coated and high U.V. & corrosion resistance with diffuser with company mark/name 160V to 270V, Power Factor more than 0.95, THD < 15%, CCT 3000 K to 6500K, Luminaire efficacy> 85 lumens/watt ,LED LED driver efficiency > 85 % (fitting required LM-79 & LM-80 Certificates)(NOTE: Below description have shown ranges of Wattage capacity of LED fittings.The Engineer incharge may select any wattage capacity between the ranges shown.)				
	(A) Tube Light with integral driver (iv) 22-24 Watts, Surge - 2kV,IP-20, conventional 4 feet Cat-III	Ea.	30		
14	Supplying and erecting led lamps with following wattage capacity of 220 to 240 voltage, minimum 15000 burning hours life, 500 V in built-surge protection,Polycarbonate diffuser, mounting suitable for E14 / E27 / B22 lamp holders, pf >= 0.5				
	(A) LED Lamps integral type, with PC diffuser suitable LAMP holder (ii) 5 to 8 watts Cat-III	Ea.	10		
15	Providing and erecting Approved make Four pole moulded case circuit breaker having breaking capacity ICU of 35 KA. at 415 V. having normal current rating 125A. with Fixed thermal & magnetic release suitable to work on A.C.supply 50 Hz. with all internal connections, spreader tinned copper & complete erected in existing 16 G.M.S. housing. ICS=100% of ICU only Cat III	Ea.	1		
16	Providing and erecting busbar chamber confirming to IS-375 fabricated from 16 G.M.S. sheet, dust & vermin proof having hinged door with rubber gasket and necessary busbar supports with COPPER busbar having current density not more than 1.6 Amp. / sq.mm (Rated current / cross section area) duly wrapped with colour insulation tape for phase sequence, three phase & neutral each suitable for following current capacity with necessary painting mounted on wall or pedestal frame of required size with necessary connections.(B) Suitable for 200 Amp. capacity	Rn.Mtr	1		
17	providing and erecting Miniature circuit breaker single pole 6A to 25A suitable to operate on 240 V A.C. system and having breaking capacity 10 KA to be erected in existing box. confirming to IS 8828/1996 with ISI Mark Cat.III	Ea.	5		
18	Providing & erecting 240 V MCB double pole switch for motor & inductive load (C Curve) having 10 KA breaking capacity & confirms to IS : 8828 in existing box having following capacity (A) 6 to 32 Amp. Cat.III	Ea.	5		
19	Providing & erecting 415 V MCB Four Pole for Motor & Inductive Load (C Curve) having 10KA breaking capacity & confirms to IS :8828 in existing box having following capacity (c)63 Amp. Cat.III	Ea.	1		
20	Providing and erecting Approved make RCCBs conforming to IS: 12640 and having sensitivity of 30 mA and Short Circuit withstand capacity of 10 KA and suitable for operation on 3 phase and neutral 415V,50Hz. having characteristic of quick action & tripping with all advance feature & do not incorporate any electronic component for following Max. rating erected as directed. (iv) 100 Amps. FP (100 mA Sensitivity) Cat. III	Ea.	1		

Scanned with OKEN Scanner

21	Providing and erecting metallic vitrified danger notice board as per language suggested by engineer incharge for HIGH VOLTAGE installation to be erected as per IS.-2551.	Ea.	2		
				TOTAL (Without GST)	
				SGST 9%	
				CGST 9%	
				TOTAL (With GST)	

- Bidder must be use materials as per vendor list.
- Vendor List

Sr.No.	Item	Approved Make	Make Offered By Contractor
1	PVC CONDUITS ANDACCESSORIES, UPVC TRUNKING	PRECISION / ANCHOR / POLYCAB/NIHIR	
2	MODULAR SWITCHES, SOCKETS &, OTHER	MK / LEGRAND /HAVELLS / GM / ANCHOR/ALEX	
3	MEDIUM VOLTAGE CABLE & WIRE	FINOLEX / POLYCAB / KEI / HAVELLS	
4	Fan Accessories	Havells , Bajaj , crompton	
5	MODULAR LIGHT POINT WITH	ANCHOR /HAVELLS / MK / LEGRAND	

Other Terms & Condition

- The rates should be excluding of GST & including of other taxes/duties/loading-unloading/Labor including Transporting.
- Validation of Quotation will be 120 days from the last date of submission of Quotation.
- Bidders are suggested to visit the site location before quoting this quotation and for any further query, bidder can contact Light department of New East (Sarthana) Zone, SMC.
- The Offer shall be submitted for the makes as mentioned in the quotation. The offer for the makes/s other than shown in the quotation will be rejected out rightly.
- Contractor will have to submit **Security deposit at the rate of 2.5 %** of work order value within 10 days from the date of work order otherwise; penalty @ 0.065% of the amount of security deposit per day of delay shall be levied.
- Successful Contractor have to execute Agreement, Surety & Undertaking on the non judicial stamp paper of Rs.300/- each purchased from Surat city only.
- Any "price variation clause" shall not be accepted.
- If contractor fails to complete above work than penalty @ 0.2% of amount of unexecuted work per day delayed should be recovered from bill. Maximum delay penalty shall be recovered 10%of unexecuted amount of work order.
- Any Other Miscellaneous items, which are necessary to complete the work should also be considered into the scope of work and needs to carry out by bidder/contractor free of cost.
- All required materials, tools, tackles and men power for the job shall be brought by the Contractor.
- Payment shall be made after satisfactory Completion of whole work in all respect and submission of required documents and invoices of the work.
- All The Central, State and Local government rules and regulations including Safety shall be strictly followed by the Contractor.
- The name of work i.e." **Quotation for the work of .....**" must be mentioned on the envelope.

Thanking You,

Executive Engineer
New East(Sarthana)Zone
Surat Municipal Corporation

SIGNATURE & SEAL OF CONTRACTOR

Scanned with OKEN Scanner