

A.J.DESAI

Executive Engineer

Public Infrastructure Cell



Surat Municipal Corporation,

School No.16, Near Soham Circle,

Althan Canal Road, Althan, Surat.

P. I. Cell/Outward/No.366

Date: 16/06/2022

Sub :- Providing & Fixing M.S Grill and other civil works on existing south side Compound Wall of SMIMER, Umarwada, Surat.

Quotation letter duly super scribed and returnable on or before Dt. 23/06/2022 up to 17.00 hrs.to the office of “Chief Accountant, Surat Municipal Corporation, Muglisara, Surat” in person or by Speed Post is invited to carry out the following.

Quotation Letter

Sr. No.	ITEM	Quantity	Unit	Rate		Amount	
				Rs.	Ps.	Rs.	Ps.
1	Demolition of brick work and stone masonry including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift. (i) On Cement Mortar.	0.17	CM	366.93		62.38	
2	Providing & laying C.C 1:3:6 (1cement :3 coarse sand :6 crushed stone agg. 20 m.m Nominal size)& curing comp. incl. cost of form work in: wall caps/ copings.	0.67	CM	3476.32		2329.13	
3	Steel work welded in built up sections, framed work including cutting, hoisting, fixing in position and applying a priming coat of red lead paint (A) in beams & joists channels angles, tees, flats with connection plates or angle cleats as in main & cross beams, hip & trussed purlins connected to common ruffers & the like.	20.93	Qtl	6393.75		133821.19	
4	Painting two coat (excluding priming coat) on new steel and other metal surface with synthetic enemal paint, burshing to give an even shade including cleaning the surface of all dirt, dust and other foreign matters.	75.00	SM	48.15		3611.25	

5	<p>Providing & applying two coats of weather shield max paint (3coats may be required in case of darker colours.) of ICI Dulux or Apex Ultima of Asian Paint including applying exterior acrylic primer coat as per manufacturers specification and directions in shade and colour approved by architects, on exterior surfaces of the building including scaffolding, preparing the surface, watering, curing etc. complete and as directed by the architects and manufacturers.</p> <p>Surface Preparation: surface is thoroughly clean, dry and free from all loose dirt, chalk, grease, fungi, algae and flaking paint. This can be achieved by brushing with a wire/ stiff coir brush, followed by water jetting if required. Fill up all minor cracks and defects with white cement and sand mixture in the ratio 1:3. For application on previously painted wall, previous coatings of paint must be thoroughly scraped off and Clean the surface thoroughly using wire brushes.</p> <p>Priming: Apply a liberal coat of exterior acrylic primer and allow it to dry for 4-5 hours. Application of putty is not recommended. Minimum 4-6 hours duration is required between each coat of weather shield max paint.</p>	67.50	SM	80.00	5400.00
Total Amount					1,45,223.95
% Above/Below					
Net Amount (Incl.GST)					

I/We do hereby give quotation to execute above mentioned work in accordance with the accompanying specifications and conditions in considerations.

TERMS AND CONDITIONS:-

1. Bidder having experience of similar works is eligible to bid the quotation.
2. The quotation complies in 1 cover.

Sealed Cover-Technical documents, experience of similar works, GST Registration Certificate and EMD of Rs.10,000/- in the form of Crossed Demand Draft /Pay order/ Cheque of Local Nationalized Bank with duly sealed financial quotation letter.

Cover shall mention on top name of work, name of agency and duly sealed.

3. Bidder has to deposit EMD of Rs.10,000/- in the form of Crossed Demand Draft / Pay order/ Cheque of Local Nationalized Bank, acceptable to Surat Municipal Corporation, drawn in favour of the Municipal Commissioner, SURAT MUNICIPAL CORPORATION payable which shall be refunded after sanction of work.

4. Quotation once offered shall not be withdrawn by Vendor.
5. Quotation once accepted shall be binding to the Vendor/Contractor.
6. The rates quoted must include all taxes, duties/ levies, GST (Goods and Service Taxes), freight, insurance, transportation, delivery and loading /unloading at the site etc. complete.
7. The decision of Add. City Engineer, Public infrastructure Cell, SMC shall be final in respect of disputes what so ever arise.
8. Right to accept any or to reject any or all the quotations without assigning any reason thereof is reserved by the competent authority of Surat Municipal Corporation, Surat.
9. The Intended Bidders has to contact Deputy Engineer/Junior Engineer/Asst. Engineer, Public infrastructure Cell, SMIMER on working days between 9.00 AM to 12.30 PM at D-Block, SMIMER Hospital & visit the site and gather information before quoting rates.
10. Accordingly, Bidder have to quote and submit in the above said time limit.
11. All necessary safety measures and precautions (including those laid down in the various relevant Indian Standards) shall be taken to ensure the safety of men, materials and machinery on the works as also of the work itself.
12. The Vendor/Agency's rate of the item of work shall be for the work completed in all respects.
13. Approval of the samples of various materials given by the Engineer-in-charge shall not absolve the Vendor from the responsibility of replacing defective material brought on site or material used in the work found defective at a later date. The Vendor shall have no claim to any payment or compensation what-so-ever on account of any such materials being rejected by the Engineer-in-charge.
14. Conditional quotation letter shall not be accepted.
15. The contract shall be constituted according to and subject to laws in India and state of Gujarat and under the jurisdiction of Courts of Gujarat at Surat City only.
16. Bidder to whom the award is made shall furnish a performance guarantee (Initial Security Deposit) for amount equal to Two percent (2.00%) of the contract amount by a demand draft of a Scheduled Nationalized Bank acceptable to owner on the Surat Branch. Security Deposit shall be paid in time and if it is paid after Ten (10) days from the date of work order, then the penalty of 0.065 % per day of the amount of Security Deposit shall be recovered from the contractor. The performance guarantee (Security Deposit) will be returned to the contractor after the defect liability period (one year after completion of work) and on completion of audit related procedure. Two percent (2.00%) shall be deducted from running bills as retention money and will be released in final bill.
17. On Completion of the work, total amount of work done at sanctioned rate shall be compared with the total amount of work done, had it been executed at the rate of the bidder of the quotation which one is next higher than sanctioned one (i.e. second lowest bidder). In case the latter is less than the total amount of work done at sanctioned rate

than the amount of difference between the due shall be deducted from the final bill before making payment.

18. Time limit of the work is 30 (Thirty) days (Including Monsoon). If the bidder fails to complete the work within the stipulated completion date for the work, he shall pay liquidated damages 0.20% of contract value per day in completion or part there of as the case may however be, Subjected to a maximum of 10% (Ten Percent) of the contract value.

Executive Engineer
Public Infrastructure Cell
Surat Municipal Corporation

Seal & Signature of the Contractor

Name :-

GST No. :-

Address :-

Date :-

Copy to: Chief Accountantshri,
Surat Municipal Corporation,
Muglisara, Surat... for necessary action