



**SURAT MUNICIPAL M CORPORATION  
WEST ZONE  
QUOTATION/CONSENT FORM**

<b>QUOTATION NO. DY.COMMISSIONER /West Zone/25/2022-23</b>		<b>DATE : 04/02/2023</b>
<b>Name of Work: Desilting of Storm drainage inlet chamber, manholes with proper safety measures in T.P.S. No.10,14,15,16 &amp; 74 (Pal), Pal village and T.P.S. No.10,11,12,13,31,32 (Adajan), Adajan village &amp; Bhatha area in West Zone (Rander).</b>		
<b>ESTIMATED AMOUNT :Rs. 15,54,330=00</b>		<b>EMD AMOUNT: Rs.10,000/-</b>
<b>validity period : 120 Days</b>		<b>Agency Category : "E-2 " Class</b>
<b>Required Documents</b>		
1	Registration Certificate	Yes
2	GST Registration Certificate	Yes
3	Experience Certificate	Yes
4	Solvency Certificate	Yes
<b>QUOTATION/CONSENT AVAILABILITY</b>		
<b>ISSUING AUTHORITY</b>	Executive Engineer, West Zone, Surat	
<b>ISSUING OFFICE</b>	Administrative office, West Zone(Rander), Balasaheb Devras Road, Tadvadi, Rander, Surat	
<b>INVITING AUTHORITY</b>	Executive Engineer, West Zone, Surat	
<b>Submission Date</b>	Last date:15 /02/2023	
	<b>SUBMITTED To,</b>	
Time : 18.00 P.M.	EXECUTIVE ENGINEER ADMINISTRATIVE BUILDING, WEST ZONE (RANDER), BALASAHEB DEVRAS ROAD, TADWADI, RANDER, SURAT	
<b><u>GST CLAUSE FOR CONSTRUCTION/ ERECTION/ COMMISSIONING/ INSTALLATION/ REPAIRS/ MAINTENANCE/ RENOVATION/ FABRICATION OF STRUCTURE INCLUDING BUILDING (MEANS ALL WORKS CONTRACT/ TURN KEY PROJECT/ SUPPLY OF MATERIAL/ GOODS)</u></b>		
GST (Goods and service tax has come in existence from 1st July, 2017. Contractor / Successful Bidder is bound to pay any amount of GST prescribed by the govt. of India as per the terms of contract agreed upon during the course of execution of this contract.		
During the course of execution of contract, if there is any change in rate if GST (Goods and Service Tax) by the Government, the same shall be reimbursed/recovered separately by SMC. subject to the submission of original receipt/proof for the amounts actually remitted by the contractor/ successful Tenderer to the competent Authority along with a certificate from Chartered Accountant of contractor/ successful Tenderer certifying that the amount of GST paid to the government and the same shall be intimated/submitted/claimed within 30 (Thirty) days from the date of payment. Remittance of GST within stipulated period shall be the sole responsibility of the successful contractor/Tenderer, failing which SMC may recover the amount due, from any other payable dues with SMC and decision of Municipal Commissioner shall be final and binding on the contractor/ successful Tenderer in this regard. Further, the non-payment of GST to the government may lead to the termination of contract and forfeiture of security Deposit/Performance Guarantee Amount.		
If imposition of any other new taxes/Duties/levies/Cess or any other incidentals etc. or any increase in the existing taxes/Duties/Levies/Cess or any other incidentals etc. (Excluding GST) are imposed during the course of the contract, the same shall be borne by the successful contractor/Tenderer only, in no case SMC shall be liable for the same.		
<b>SIGNATURE OF ISSUING AUTHORITY</b>		
<b>EXECUTIVE ENGINEER WEST ZONE SURAT MUNICIPAL CORPORATION</b>		

**Executive Engineer**  
West Zone.



West Zone (Rander)  
Surat Municipal Corporation,  
Tadwadi, Rander Road, Surat.  
Ph. (O) 2786181-82-83

**CONSENT LETTER**

WZ/OUT No./  
Date : /01/2023

TO,

.....  
.....  
.....  
.....

**Sub: - Desilting of Storm drainage inlet chamber, manholes with proper safety measures in T.P.S. No.10,14,15,16 & 74 (Pal), Pal village and T.P.S. No.10,11,12,13,31,32 (Adajan), Adajan village & Bhatha area in West Zone (Rander).**

**Ref.:- Standing Committee Resolution No.539/2022, Dtd.07/04/2022 Unit Rate, Conditions and Specifications. (36.30% Below of Estimated Amount)**

**Dear Sir/Madam,**

Consent Letters duly superscribed and returnable on or before **Dt.15/02/2023** with EMD to the office of the undersigned are invited for working of the following work.

<b>Sr. No.</b>	<b>Work Name</b>	<b>Est.Amt. (Rs.)</b>	<b>Tender Amt. (Rs.)</b>	<b>EMD Amt. (Rs.)</b>
1	Desilting of Storm drainage inlet chamber, manholes with proper safety measures in T.P.S. No.10,14,15,16 & 74 (Pal), Pal village and T.P.S. No.10,11,12,13,31,32 (Adajan), Adajan village & Bhatha area in West Zone (Rander).	15,54,330.00	9,90,108.21	10,000.00

**Terms and Conditions**

- Tederers must submit Solvency Certificate, Attested copy of Registration Certificate, GST Registration & Completion Certificates (3A Form) of Similar Works Carriedout during last 7 years issued by Government / Semi Government departments only.
- **Successful Tederers must submit Workmen Compensation Policy at time of receiving work order.**
- EMD amout must submit in the form of Cheque or Pay Order or Demand Draft in the Name of "The Commissioner, Surat Municipal Corporation" payable at Surat.
- The name of work must be mentioned on the envelope.
- All workers/Labours deployed for the said work shall be provided with the Personal Safety Equipments & Accessories and the Contractor shall be held responsible for any accident/injury/loss to any of the staff members of them.
- Contractor shall follow all applicable Laws, Rules and Regulation for such type of work.
  
- **Please note that the scope of work includes desilting of Storm Drainage Inlet Chambers and Machineholes with the help of shovel only, along with carting of desilted materials from desilted site. SMC will not pay any transportation charges and also not provide any type of assistance while carrying out mention work.**
- **No workers/Labours should enter inside the Machinehole for above mentioned work.**

(( 2 ))

- **All the required tools, equipments, accessories and manpower for carrying out desilting work shall be in the contractor's scope only.**
- Contractor shall follow the instructions by the SMC representative from concerned department at the site.
- Consent once offered shall not be withdrawn by Tenderer.
- Consent once accepted shall be binding to the Tenderer.
- Right to accept any or to reject any or all the Consent(s) or to reduce or increase the scope of work without assigning any reason thereof is reserved by the competent authority of Surat Municipal Corporation.
- Tenderer to whom the award of work is made must enter into agreement with Surat Municipal Corporation on Rs. 300 + Rs. 300 + Rs. 300 Stamp Paper.
- Consents received after due date will not be accepted.
- In absence of EMD, the Consent letter will be liable for outright rejection.
- Fulfillment of all the conditions is must or else the consent shall be liable for outright rejection.

**SD/-**  
**Executive Engineer**  
**West Zone (Rander)**  
**Surat Municipal Corporation**

**\* SIGNATURE & SEAL OF TENDERER \***

SURAT MUNICIPAL CORPORATION  
SOUTH EAST ZONE (LIMBAYAT)  
SCHEDULE-B

**Name of work: Desilting of Storm drainage inlet chamber, manholes with proper safety measures in T.P.S. No.10,14,15,16 & 74 (Pal), Pal village and T.P.S. No.10,11,12,13,31,32 (Adajan), Adajan village & Bhatha area in West Zone (Rander).**

ITEM NO.	DESCRIPTION OF ITEM	QUANTITY	UNIT	RATE Rs. P.	AMOUNT Rs. P.
1	Desilting of garbage, rubbish, clay, silt, grit, industrial waste like acidic hot water, chemical water etc. and Carting of the desilted material and other waste material collection from masonry/RCC storm box drain up to lead of 10.00 k.m. at any depth and cross drain in dry or wet condition including pumping to facilitate the work and flushing the same with water, disposing of the desilted material etc. complete and strictly directed by the Engineer-in-Charge Note:-add Rs.2.50 per C.M for more than 10 KM	7890.00	C.M	197.00	1554330.00
2	Providing and making gaps of any size and shape required on top/sides of masonry R.C.C. storm water box drain/pipe drain facilitate to remove the waste and stack the same nearby the road within lead of 100 mt. as directed including breaking of asphalt road, all kinds of pavements, masonry or R.C.C. slab and Machine hole shaft of box drains etc. and reinstate the same after completion of as work of directed with masonry R.C.C. work/brick work etc. complete and strictly directed by the Engineer-in-charge.	0.00	NO.	2250.00	0.00
3	Providing and constructing Machine hole shaft of 900 mm dia with 230 mm thick brick masonry in cement mortar 1:6 (1 Cement: 6 fine sand) plastering the walls 12 mm thick to inside surface with 1:3 including providing and fixing C.I. steps of standard weight to be fixed at 300 mm c/c and staggered carbelling the shaft of tope fixing 229 Kg.wt. C.I./RCC Machine hole cover with frame of 525 mm opening dia in cement mortar 1:3 concreted around with cement concrete in prop. (1:2:4) and cement pointing in 1:3 for outer surface of wall curing etc. completed as directed by Engineer-in-charge.	0.00	R.M	1280.00	0.00
<b>TOTAL Rs.</b>					<b>1554330.00</b>
<b>Below 36.30% as Per Standing Committee Resolution No.539/2022, Dtd.07/04/2022</b>					
<b>Unit Rates, Conditions &amp; Specifications.</b>					<b>564221.79</b>
<b>TENDER AMOUNT:-</b>					<b>990108.21</b>

EXECUTIVE ENGINEER,  
SOUTH EAST ZONE (LIMBAYAT)  
SURAT MUNICIPAL CORPORATION